

### **Minutes of 615<sup>th</sup> SEAC-1 Meeting Dated 03/01/2022**

The 615<sup>th</sup> meeting of SEAC-1 was held in the Directorate of Environment, U.P. through dual-mode (physically/virtually) at 11:00 AM on 03/01/2022. Following members participated in the meeting:

- |    |                             |                              |
|----|-----------------------------|------------------------------|
| 1. | Shri Rajive Kumar,          | Chairman, SEAC-1 (Virtually) |
| 2. | Dr. Ajai Mishra,            | Member, SEAC-1 (Virtually)   |
| 3. | Shri Om Prakash Srivastava, | Member, SEAC-1 (Virtually)   |
| 4. | Dr. Brij Bihari Awasthi,    | Member, SEAC-1 (Virtually)   |
| 5. | Shri Umesh Chandra Sharma,  | Member, SEAC-1 (Virtually)   |
| 6. | Dr. Ratan Kar,              | Member, SEAC-1 (Virtually)   |

The Chairman welcomed the members to the 615<sup>th</sup> SEAC-2 meeting which was conducted via dual-mode (virtually/physically). Nodal Officer, SEAC-1 informed the committee that the agenda has been approved by the Member Secretary, SEAC-2/Director Environment. Nodal Officer, SEAC-1 placed the agenda items along with the available file and documents before the SEAC-1.

- 1. Stone (Sand stone) Mining at Arai No - 399, in Village: Jigna, Tehsil-Chunar, District - Mirzapur, Shri Om Prakash Singh. (Area- 0.606 Ha.). File No. 6722/Proposal No. SIA/UP/MIN/69695/2021**

#### **RESOLUTION AGAINST AGENDA NO-01**

The project proponent/consultant did not appear. The committee discussed and deliberated that project file should be closed and be opened only after request from the project proponent. The file shall not be treated as pending at SEAC. The matter will be discussed only after submission of online request on prescribed online portal.

- 2. Stone (Khanda, Giiti, Boulder, Ballast & Red Morrum) Mining at Arai No.: 288, Khand No.:04, , Village: Majhol, Tehsil: Charkhari, Mahoba, , Shri Ganga Charan Area: 0.809 Ha. File No. 6725/Proposal No. SIA/UP/MIN/69407/2021**

The consultant informed the committee that they are strictly following the rules, regulations and other instructions of QCI/NABET. A presentation was made by the project proponent along with their consultant M/s Globus Environment Engineering Services. Based on the documents submitted and presentation made by the project proponent along with the consultant, the following facts have emerged: -

1. The terms of reference is sought for Stone (Khanda, Giiti, Boulder, Ballast & Red Morrum) Mining at Arai No. 288, Khand No.:04, Village: Majhol, Tehsil: Charkhari, Mahoba, U.P. (Leased Area: 0.809 Ha.).
2. Salient features of the project as submitted by the project proponent:

|   |   |
|---|---|
| 1. On-line proposal No.                                   | SIA/UP/MIN/69407/2021   |
| 2. File no. allotted by SEIAA,UP                          | 6725  |
| 3. Name of Proponent                                      | Siyarani Rajpoot Filling Station,<br>Prop. Shri Ganga Charan S/o Shri Ram Swaroop |
| 4.Full correspondence address of proponent and mobile no. | R/o- Mo. Pathanpura Kasba & Thana- Rath,<br>District: Hamirpur, U.P.              |

|  |  |                   |
|--|--|-------------------|
|  | Pin Code- 210431   |                   |
| 5. Name of Project   | Building Stone/ Khanda, Boulder, Gitti, Ballast & Red Morrum Mine  |                   |
| 6. Project location (Plot/Khasra/Gata No.)                                 | Araji No.288 (Khand - 04)  |                   |
| 7. Name of River   | -  |                   |
| 8.Name of Village  | Majhol   |                   |
| 9. Tehsil  | Charkhari  |                   |
| 10.District  | Mahoba, U.P.   |                   |
| 11. Name of Minor Mineral  | Building Stone "Khanda, Boulder, Gitti, Ballast & Red Morrum"  |                   |
| 12. Sanctioned Lease Area (in Ha.)   | Total Lease Area: 0.809 Ha   |                   |
| 13. Mineable Area (in Ha.)   | 0.809 Ha   |                   |
| 14. Zero Level mRL   | -  |                   |
| 15. Max. & Min mRL within lease area                                       | Highest Point :206mRL<br>Lowest Point :185mRL  |                   |
| 16. Pillar Coordinates (Verified by DMO)                                   | Sanction Lease Area Co-ordinate  |                   |
| (Source: Verified Khasra Map)  | Pillars  | Latitude (N)      |
|  | A  | 25°23'49.86"N     |
|  | B  | 25°23'48.51"N     |
|  | C  | 25°23'44.97"N     |
|  | D  | 25°23'45.95"N     |
|  |  | Longitude (E)     |
|  |  | 79°46'36.67"E     |
|  |  | 79°46'38.27"E     |
|  |  | 79°46'35.17"E     |
|  |  | 79°46'33.58"E     |
| 17. Total Geological Reserves<br>(Source: Approved Mining Plan)            | 5,06,790m <sup>3</sup>   |                   |
| 18. Total Mineable Reserves<br>(Source: Approved Mining Plan)              | 1,59,348m <sup>3</sup>   |                   |
| 19. Total Proposed Production (in five years)                              | 1,31,465 m3  |                   |
| 20. Proposed Production/year   | 26,293 m3 per annum  |                   |
| 21. Sanctioned Period of Mine lease  | 10 years   |                   |
| 23. Method of Mining   | Opencast, semi-mechanized  |                   |
| 24. No. of Working days  | 260 Days   |                   |
| 25. Working hours/day  | 8 -10 hours/day  |                   |
| 26. No. Of Workers   | 28   |                   |
| 27. No. of vehicles movement/day   | 14 Units (Assumed Loading Capacity: 20 T/Unit)   |                   |
| 28. Type of Land   | State Government Land  |                   |
| 29. Ultimate Depth of Mining   | 36 m (206mRL – 170mRL)<br>(Source: Approved Mining Plan)   |                   |
| 30. Nearest metalled road from site  | 850 m  |                   |
| Water Requirement  | Purpose  | Requirement (KLD) |
|  | Drinking   | 0.140             |
|  | Suppression of Dust  | 1.62              |
|  | Plantation   | 11.9              |
|  | Total  | 13.66             |
| 32. Name of QCI Accredited Consultant with QCI No. and period of validity. | GLOBUS ENVIRONMENT ENGINEERING SERVICES<br>Certificate No. NABET/EIA/1821/IA0034, Valid Till March 26/2022           |                   |
| 33. Any litigation pending against the project or hand in any court        | No   |                   |
| 34. Details of 500 m Cluster Map & certificate issued by Mining Officer    | Cluster certificate issued by DMO (Mining Section), Mahoba Letter No. 1308/ एम. एम. सी 30/2021-22, Date – 13-08-2021 |                   |
| 35. Details of Lease Area in approved DSR                                  | Approved DSR Amendment Letter, Mahoba: 154/ एम. एम. सी-30-खनिज (2021-22) Pg No.:03, Sr No.82, दिनांक 12.05.2021      |                   |
| 36. Proposed CER Cost  | Rs. 3.13 Lakhs (3% of the total Project Cost)  |                   |
| 37. Proposed EMP Cost  | Rs. 25.13 Lakhs  |                   |
| 38. Length and width of Approach Road                                      | Approach Road Length 850 m & Width 7 m   |                   |

|                                |           |
|--------------------------------|-----------|
| 39. No. of Trees to be Planted | 810 Trees |
|--------------------------------|-----------|

3. The mining would be restricted to the unsaturated zone only above the phreatic water table and will not intersect the groundwater table at any point in time.
4. The mining operation will not be carried out in the safety zone of any bridge or embankment or eco-fragile zone such as the habitat of any wild fauna.
5. There is no litigation pending in any court regarding this project.
6. The project proposal falls under category-1(a) of EIA Notification, 2006 (as amended).

**RESOLUTION AGAINST AGENDA NO. 02**

**The committee discussed the matter and recommended to issue the standard terms of reference for the preparation of EIA as annexed at Annexure-1 to the minutes. The committee also stipulated following additional TOR Points:**

**Additional TOR:**

1. The project proponent/Consultant should identify the core & buffer zone (2.5 km) of the mining site.
3. **Sand Stone (Khanda, Gitti & Red Morrum) Mine at Gata No.-52Mi, Village- Sirsiya Thakurai, Tehsil- Robertsganj, District- Sonbhadra, Smt. Binduwati Devi, Leased Area -2.024 ha. File No. 5828/Proposal No. SIA/UP/MIN/239225/2021**

The project proponent/consultant informed the committee that the environmental clearance for the above project proposal was issued by SEIAA, U.P. vide letter no. 141/Parya/SEAC/5828/2019, dated 12/06/2021 for the production capacity 1,50,000 m<sup>3</sup> in year 2020 & 1,43,073 m<sup>3</sup> in year 2021. The mining leased area sanctioned in favour of Smt. Binduwati Devi W/o Shri Ramchandra Ratna for the period of 27/05/2016 to 26/05/2026. The project proponent submit the revised mining plan approved by Director, Geology and Mining Department, Lucknow vide letter no. 2021/11/19/92147, dated 26/11/2021 for the revised quantity of 33600 cum/year Stone, Gitty, Khanda, Boulders and 22400 cum/year overburden red morrum mining. The project proponent also informed that the gata no. of the mining lease area mentioned as 52 in environmental clearance letter dated 12/06/2021, it should be corrected as gata no. 52 Mi.

The consultant informed the committee that they are strictly following the rules, regulations and other instructions of QCI/NABET. A presentation was made by the project proponent along with their consultant M/s Environmental Research and Analysis, Lucknow (U.P.). Based on the documents submitted and presentation made by the project proponent along with the consultant, the following facts have emerged: -

1. The environmental clearance is sought for Sand Stone (Khanda, Gitti & Red Morrum) Mine at Gata No.-52Mi, Village- Sirsiya Thakurai, Tehsil- Robertsganj, District- Sonbhadra, U.P., (Leased Area - 2.024 ha.).
2. Salient features of the project as submitted by the project proponent:

|                                   |  |
|-----------------------------------|--|
| 1. On-line proposal No.           | SIA/UP/MIN/239225/2021                           |
| 2. File No. allotted by SEIAA, UP | 5828   |
| 3. Name of Proponent              | Smt. Bindu Wati Devi W/o - Sri Ram Chandra Ratna |

**Minutes of 615<sup>th</sup> SEAC-1 Meeting Dated 03/01/2022**

|  |  |                           |  |
|--|--|---------------------------|--|
| 4. Full correspondence address of proponent and mobile no.                               | R/o Bijari Harhua, Churk District: Sonbhadra (U.P.). 231206  |                           |  |
| 5. Name of Project   | Sand Stone (Khanda,Gitti & Red Morrum Project  |                           |  |
| 6. Project location (Plot/Khasra/Gata No.)   | Arazi No: 52 Mi  |                           |  |
| 7. Name of River   | NA   |                           |  |
| 8. Name of Village   | Sirsiya Thakurai   |                           |  |
| 9. Tehsil  | Robertsganj  |                           |  |
| 10. District   | Sonbhadra (U.P)  |                           |  |
| 11. Name of Minor Mineral  | Sand Stone (Khanda, Gitti & Red Morrum)  |                           |  |
| 12. Sanctioned Lease Area (in Ha.)   | 2.024 Ha   |                           |  |
| 13. Mineable Area (in Ha.)   | 1.61 Ha (0.414 Ha safety margin)   |                           |  |
| 14. Zero level mRL   | NA   |                           |  |
| 14. Max. & Min mrl within lease area   | Maximum mRL is 287.2 mRL and Minimum mRL is 285.3 mRL  |                           |  |
| 15. Pillar Coordinates (Verified by DMO)   |  |                           |  |
|  | Points   | Latitude                  | Longitude                                    |
|  | A  | 24°52'08.57"N             | 82°59'32.19"E                                |
|  | B  | 24°52'09.13"N             | 82°59'37.18"E                                |
|  | C  | 24°52'05.03"N             | 82°59'37.57"E                                |
|  | D  | 24°52'04.30"N             | 82°59'31.21"E                                |
|  |  |                           |  |
| 16. Total Geological Reserves  | 5,82,818 m <sup>3</sup>  |                           |  |
| 17. Total Mineable Reserves  | 33,600m <sup>3</sup> per year  |                           |  |
| 18. Total Proposed Production (in five year)<br>(Sand Stone (Khanda, Gitti & Red Morrum) | Year   | Overburden / Morrum (cum) | ROM sand Stone Gitty, Khanda, Boulders (cum) |
|  | 1 <sup>st</sup>  | 22400                     | 33600  |
|  | 2 <sup>nd</sup>  | 22400                     | 33600  |
|  | 3 <sup>rd</sup>  | 22400                     | 33600  |
|  | 4 <sup>th</sup>  | 22400                     | 33600  |
|  | 5 <sup>th</sup>  | 22400                     | 33600  |
|  | Total  | 112000                    | 168000                                       |
| 19. Proposed Production/year   | Year   | Overburden / Morrum (cum) | ROM sand Stone Gitty, Khanda, Boulders (cum) |
|  | 1 <sup>st</sup>  | 22400                     | 33600  |
| 20. Sanctioned Period of Mine lease  | 10 Years (Lease Life – 27.05.2016 to 26.05.2026)   |                           |  |
| 21. Production of mine/day   | ▪ ROM sand Stone Gitty, Khanda, Boulders<br>▪ Overburden / Morrum  |                           |  |
| 22. Method of Mining   | Open cast, Manual, Semi-mechanized   |                           |  |
| 23. No. of working days  | 250  |                           |  |
| 24. Working hours/day  | 8 hours/day  |                           |  |
| 25. No. Of workers   | 25   |                           |  |
| 26. No. Of vehicles movement/day   | 11-17 Vehicles movement/day  |                           |  |
| 27. Type of Land   | Open cast, Manual, Semi-mechanized   |                           |  |
| 28. Ultimate Depth of Mining   | 3.0 m  |                           |  |
| 29. Nearest metallad road from site  | Sirsiya Thakurai Village road  |                           |  |
| 30. Water Requirement  | PURPOSE  |                           | REQUIREMENT(KLD)                             |
|  | Drinking   |                           | 0.35 KLD                                     |
|  | Suppression of dust  |                           | 3.6 KLD                                      |
|  | Plantation   |                           | 2.024 KLD                                    |
|  | Others (if any)  |                           | NA   |
|  | Total  |                           | 6.0 KLD approx..                             |
| 31. Name of QCI Accredited Consultant with QCI No<br>And period of validity.             | M/s Environmental Research and Analysis, Lucknow (U.P.)<br>Certificate No. NABET/EIA//1922/RA0200 and Extension valid up to 30/12/2022 |                           |  |
| 32. Any litigation pending against the project or  | NO   |                           |  |

|   |   |
|---|---|
| land in any court   |   |
| 33. Details of 500 m Cluster Map & certificate issued by Mining Officer | Letter No-2001/Khanij/2020 Dated 28-09-2020 |
| 34. Details of Lease Area in approved DSR                               | NA  |
| 35. Proposed EMP cost   | Rs 25,00,000/-                              |
| 36. Proposed Project cost   | Rs 90,00,000/-                              |
| 37. Length and breadth of Haul Road                                     | 150 m length and 6 m width                  |
| 38. No. of Trees to be Planted  | 2024  |

The project proponent requested to amend the environmental clearance letter dated 12/06/2021 as per above details.

### **RESOLUTION AGAINST AGENDA NO. 03**

The committee discussed the matter in depth and recommended to amend the environmental clearance letter no. 141/Parya/SEAC/5828/2019, dated 12/06/2021 as per the above details. Rest all the contents mentioned in environmental clearance letter no. 141/Parya/SEAC/5828/2019, dated 12/06/2021 shall remain same.

#### **4. Sand Mining at Gata No.-99 mi,101 mi, 102 mi & 103, Khanda No.- 02, Village-Bijhalpur, Tehsil- Ajitmal, Auraiya., Shri Dheeraj Panday., Area-11.9595 Ha. File No. 6766/5749/Proposal No. SIA/UP/MIN/70187/2021**

### **RESOLUTION AGAINST AGENDA NO-04**

The project proponent/consultant did not appear. The committee discussed and deliberated that project file should be closed and be opened only after request from the project proponent. The file shall not be treated as pending at SEAC. The matter will be discussed only after submission of online request on prescribed online portal.

#### **5. Sand/Morrum Mining from Yamuna Riverbed at Khand No.- 15/35 to 15/39, (Khand Sr. No.- 03) Village- Umrawan, Tehsil- Manjhanpur, Kaushambi., Shri Santosh Tiwari.,Area: 10.00 ha. File No. 6248/Proposal No. SIA/UP/MIN/62155/2021**

The consultant informed the committee that they are strictly following the rules, regulations and other instructions of QCI/NABET. A presentation was made by the project proponent along with their consultant M/s Globus Environment Engineering Services. Based on the documents submitted and presentation made by the project proponent along with the consultant, the following facts have emerged: -

1. The environmental clearance is sought for Sand/Morrum Mining from Yamuna Riverbed at Khand No.- 15/35 to 15/39, (Khand Sr. No.- 03) Village- Umrawan, Tehsil- Manjhanpur, Kaushambi, U.P. (Leased Area: 10.00 ha.).
2. The terms of reference in the matter were issued by SEIAA, U.P. vide letter no. 108/Parya/SEAC/6248/2021 dated 11/06/2021.
3. The public hearing was organized on 04/12/2021 at Auditorium, Tehsil- Manjhanpur, Dist- Kaushambi. Final EIA report submitted by the project proponent on 17/12/2021.
4. Salient features of the project as submitted by the project proponent:

|  |   |
|--|---|
| 1. On-line proposal No.                        | SIA/UP/MIN/62155/2021,Dated: 17-12-2021                                 |
| 2.File no. allotted by SEIAA,UP                | 6248  |
| 3. Name of Proponent                           | M/s Khushi Enterprises<br>Shri Santosh Tiwari, S/o Shri Surendra Tiwari |
| 4.Full correspondence address of proponent and | R/o- H. No.- C 144 Sector E, Thana- Aliganj,                            |

**Minutes of 615<sup>th</sup> SEAC-1 Meeting Dated 03/01/2022**

|   |  |                   |                |
|---|--|-------------------|----------------|
| mobile no.  | District- Lucknow, U.P - 226024                                    |                   |                |
| 5. Name of Project  | “Sand/ Morrum Mining”  |                   |                |
| 6. Project location (Plot/Khasra/Gata No.)                                    | Khand No. 15/35 to 15/39 (Khand Sr. No.:03)                        |                   |                |
| 7. Name of River  | Yamuna River, Core Zone  |                   |                |
| 8. Name of Village  | Umrawan  |                   |                |
| 9. Tehsil   | Manjhanpur   |                   |                |
| 10. District  | Kaushambi  |                   |                |
| 11. Name of Minor Mineral   | River Bed Material (Sand/Morrum)                                   |                   |                |
| 12. Sanctioned Lease Area (in ha.)  | Total Lease Area: 10.0 Ha  |                   |                |
| 13. Mineable/Workable Area (in ha.)   | 7.1 Ha   |                   |                |
| 14. Zero level mRL  | 79mRL  |                   |                |
| 15. Max. & Min mRL within lease area  | The Highest Point at 81.0 mRL<br>The Lowest Point at 79.0 mRL      |                   |                |
|   | Sanctioned Area(Geo Coordinates)                                   |                   |                |
| 16. Pillar Coordinates (Verified by DMO)<br><br>(Source: Verified Khasra Map) | Pillar   | Latitudes (N)     | Longitudes (E) |
|   | A  | 25°22'51.06"N     | 81°10'21.24"E  |
|   | B  | 25°22'36.90"N     | 81°10'52.98"E  |
|   | C  | 25°22'33.90"N     | 81°10'51.78"E  |
|   | D  | 25°22'48.00"N     | 81°10'19.68"E  |
|   | Coordinates of Area under active water channel                     |                   |                |
|   | C  | 25°22'33.90"N     | 81°10'51.78"E  |
|   | F  | 25°22'38.10"N     | 81°10'42.30"E  |
|   | G  | 25°22'38.26"N     | 81°10'43.99"E  |
|   | H  | 25°22'34.69"N     | 81°10'52.11"E  |
|   | Coordinates of other Area under active water channel               |                   |                |
|   | A  | 25°22'51.06"N     | 81°10'21.24"E  |
|   | D  | 25°22'48.00"N     | 81°10'19.68"E  |
|   | E  | 25°22'45.32"N     | 81°10'25.94"E  |
|   | Coordinates of workable area                                       |                   |                |
|   | A  | 25°22'51.06"N     | 81°10'21.24"E  |
|   | B  | 25°22'36.90"N     | 81°10'52.98"E  |
|   | H  | 25°22'34.69"N     | 81°10'52.11"E  |
|   | G  | 25°22'38.26"N     | 81°10'43.99"E  |
|   | F  | 25°22'38.10"N     | 81°10'42.30"E  |
|   | E  | 25°22'45.32"N     | 81°10'25.94"E  |
| 17. Total Geological Reserves<br>(Source: Approved Mining Plan)               | 1,67,912 m <sup>3</sup>  |                   |                |
| 18. Total Mineable Reserves<br>(Source: Approved Mining Plan)                 | 1,00,000 m <sup>3</sup>  |                   |                |
| 19. Total Proposed Production (in five years)                                 | 5,00,000 m <sup>3</sup>  |                   |                |
| 20. Proposed Production/year  | 1,00,000 m <sup>3</sup> /Annum                                     |                   |                |
| 21. Sanctioned Period of Mine lease   | 05 years   |                   |                |
| 23. Method of Mining  | Opencast, semi-mechanized  |                   |                |
| 24. No. of Working days   | 260 Days   |                   |                |
| 25. Working hours/day   | 8 hours/day  |                   |                |
| 26. No. of Workers  | 52   |                   |                |
| 27. No. of vehicles movement/day  | 19 Units (Assumed Loading Capacity: 20m <sup>3</sup> /Unit)        |                   |                |
| 28. Type of Land  | State Government Land  |                   |                |
| 29. Ultimate Depth of Mining  | 2.01 meters (84 mRL – 81.99 mRL)<br>(Source: Approved Mining Plan) |                   |                |
| 30. Nearest metalled road from site   | Length 2794 m & Width 7 m  |                   |                |
| 31. Water Requirement   | Purpose  | Requirement (KLD) |                |
|   | Drinking   | 0.26              |                |
|   | Suppression Of   | 14.00             |                |

|  |  |       |
|--|--|-------|
|  | Dust   |       |
|  | Plantation   | 20.00 |
|  | Total  | 34.26 |
| 32. Name of QCI Accredited Consultant with QCI No. and period of validity. | GLOBUS ENVIRONMENT ENGINEERING SERVICES Certificate No. NABET/EIA/1821/IA0034, Extension Validity Till March 26/2022 |       |
| 33. Any litigation pending against the project or hand in any court        | No   |       |
| 34. Details of 500 m Cluster Map & certificate issued by Mining Officer    | Cluster certificate issued by DMO (Mining Section), Kaushambi. Letter No. 1210/ खनन सहायक कौ०, दिनांक -29-01-2021    |       |
| 35. Details of Lease Area in approved DSR                                  | Approved DSR, Kaushambi : Page No-2, In Table Sr. No-3, 1586(3)/खनन सहायक कौ०, दिनांक- 10/02/2020                    |       |
| 36. Proposed CER Cost  | Rs. 6.23 Lakhs (2% of the total Project Cost)  |       |
| 37. Proposed EMP Cost  | Rs. 43.68 Lakhs  |       |
| 38. Length and breadth of Haul Road  | Length 2794 m & Width 7 m  |       |
| 39. No. of Trees to be Planted   | 10,000 Trees/Year (1000 trees/ha.)   |       |

5. The mining would be restricted to the unsaturated zone only above the phreatic water table and will not intersect the groundwater table at any point in time.
6. The mining operation will not be carried out in the safety zone of any bridge or embankment or eco-fragile zone such as the habitat of any wild fauna.
7. There is no litigation pending in any court regarding this project.
8. The project proposal falls under category-1(a) of EIA Notification, 2006 (as amended).

**RESOLUTION AGAINST AGENDA NO. 05**

The committee discussed the matter and recommended the grant of environmental clearance for the project proposal along with general and specific conditions as annexed at Annexure-3 to the minutes.

- 6. Stone (Gitti, Khanda) Mining at Gata No.- 314, Khand No.-04, Village- Pangara, Tehsil-Naraini, Bnada, Shri Ram Krishna Pandey. Area-0.628 ha. File No. 6767/Proposal No. SIA/UP/MIN/245567/2021**

**RESOLUTION AGAINST AGENDA NO. 06**

The consultant informed the committee that they are strictly following the rules, regulations and other instructions of QCI/NABET. A presentation was made by the project proponent along with their consultant M/s Environmental Research and Analysis, Lucknow (U.P.). The committee discussed the matter and directed the project proponent to submit khasra map approved by competent authority.

- 7. Granite Gitti, Khanda, Boulders & Pahari Red Morrum Mining at Khasra No./Plot No.-2131/3, Village- Rauli Kalyanpur, Tehsil- Karwi, District- Chitrakoot., Shri Arvind Kumar Mishra, Area -2.6313 ha. File No. 5624/Proposal No. SIA/UP/MIN/40307/2019**

**RESOLUTION AGAINST AGENDA NO-07**

The project proponent/consultant did not appear. The committee discussed and deliberated that project file should be closed and be opened only after request from the project proponent. The file shall not be treated as pending at SEAC. The matter will be discussed only after submission of online request on prescribed online portal.

**8. Granite ( Khanda, Gitti & Boulders & Pahadi Red Morrum) at Gata No.- 2131/07, Village- Raulikalyanpur, Tehsil- Karwi, District- Chitrakoot, Shri Rasmeet Singh Malhotra., M/s Malhotra Brothers., Area-2.4289 ha. File No. 6769/5677/Proposal No. SIA/UP/MIN/70291/2020**

The consultant informed the committee that they are strictly following the rules, regulations and other instructions of QCI/NABET. A presentation was made by the project proponent along with their consultant M/s Paramarsh (Servicing Environment and Development), Lucknow, U.P. Based on the documents submitted and presentation made by the project proponent along with the consultant, the following facts have emerged: -

1. The environmental clearance is sought for Granite (Khanda, Gitti, Boulder & Pahadi Red Morrum) Mining at Gata No.- 2131/07, Village- Raulikalyanpur, Tehsil- Karwi, District- Chitrakoot, U.P., (Leased Area- 2.4289 ha.), M/s Malhotra Brothers.
2. The terms of reference in the matter were issued by SEIAA, U.P. vide letter no. 214/Parya/SEAC/5677/2019 dated 27/07/2020.
3. The public hearing was organized on 19/07/2021. Final EIA report submitted by the project proponent on 19/12/2021.
4. Salient features of the project as submitted by the project proponent:

|     |   |  |  |   |
|-----|---|--|--|---|
| 1.  | On-line proposal No.                                    | SIA/UP/MIN/70291/2020  |  |   |
| 2.  | File No. allotted by SEIAA, UP                          | 6769 / 5677  |  |   |
| 3.  | Name of Proponent                                       | M/s Malhotra Brothers,<br>Prop.- Shri Rasmeet Singh Malhotra S/o Shri Ajeet Singh Malhotra |  |   |
| 4.  | Full correspondence address of proponent and mobile no. | R/o- Near Railway Gate, Main Road, Pipariya, District- Hosangabad (M.P.)                   |  |   |
| 5.  | Name of Project   | Granite (Khanda, Gitti, Boulder & Pahadi Red Morrum) Mining Project                        |  |   |
| 6.  | Project location (Plot/ Khasra /Gata No.)               | Gata No.- 2131/07  |  |   |
| 7.  | Name of Village   | Raulikalyanpur   |  |   |
| 8.  | Tehsil  | Karwi  |  |   |
| 9.  | District  | Chitrakoot   |  |   |
| 10. | Name of Minor Mineral                                   | Granite (Khanda, Gitti, Boulder & Pahadi Red Morrum)                                       |  |   |
| 11. | Sanctioned Lease Area (in Ha.)                          | 2.4289 ha.   |  |   |
| 12. | Max.& Min mrl within lease area                         | 200 mRL- 167 mRL   |  |   |
| 13. | Pillar Coordinates(Verified by DMO)                     | Pillars  | Latitude (N)                           | Longitude (E)   |
|     |   | A  | 25° 11.994'N                           | 80° 42.840'E  |
|     |   | B  | 25° 11.944'N                           | 80° 42.874'E  |
|     |   | C  | 25° 11.861'N                           | 80° 42.796'E  |
|     |   | D  | 25° 11.922'N                           | 80° 42.749'E  |
| 14. | Total Geological Reserves                               | 1900271 m <sup>3</sup>   |  |   |
| 15. | Total Mineable Reserves                                 | 654738 m <sup>3</sup>  |  |   |
| 16. | Total Proposed Production (in five year)                | 150000 m <sup>3</sup>  |  |   |
| 17. | Proposed Production / year                              | Year   | Pahadi Red Morram (in m <sup>3</sup> ) | Granite (Gitti, Khanda, Boulder) (in m <sup>3</sup> ) |
|     |   | Ist  | 6000                                   | 24000   |
|     |   | IIInd  | 3045                                   | 26955   |
|     |   | IIIrd  | 200                                    | 29800   |
|     |   |  |  | Total (Granite + Morram) (in m <sup>3</sup> )         |
|     |   |  |  | 30000   |



|     |   |  |       |                   |        |
|-----|---|--|-------|-------------------|--------|
|     |   | IVth   | 4000  | 26000             | 30000  |
|     |   | Vth  | 2500  | 27500             | 30000  |
|     |   |  | 15745 | 134255            | 150000 |
| 18. | Sanctioned Period of Mine lease                                       | 20 Years   |       |                   |        |
| 19. | Method of Mining  | Opencast Semi-Mechanized   |       |                   |        |
| 20. | No.of working days  | 300 days   |       |                   |        |
| 21. | Working hours/day   | 8 Hours/Day  |       |                   |        |
| 22. | No.Of workers   | 35   |       |                   |        |
| 23. | No.Of vehicle movement /day   | 10 (average)   |       |                   |        |
| 24. | Type of Land  | Govt. Revenue Land   |       |                   |        |
| 25. | Ultimate Depth of Mining  | 18 meter (average)   |       |                   |        |
| 26. | Nearest metalled road from site                                       | 600m   |       |                   |        |
| 27. | Water Requirement   | PURPOSE  |       | REQUIREMENT (KLD) |        |
|     |   | Drinking& Others   |       | 0.35              |        |
|     |   | Suppression of dust  |       | 3.60              |        |
|     |   | Plantation   |       | 0.25              |        |
|     |   | Others( if any)  |       | -----             |        |
|     |   | Total  |       | 4.20              |        |
| 28. | Name of QCI Accredited Consultant with QCI No and period of validity. | M/s Paramarsh (Servicing Environment and Development)., Lucknow, U.P.<br>QCI/NABET/EIA/1821/RA0120<br>Validity- 13/01/2022 |       |                   |        |
| 29. | Any litigation pending against the project or land in any court       | No   |       |                   |        |
| 30. | Details of 500 m Cluster Map & certificate Verified by Mining Officer | DMO, Chitrakoot vide Letter No. 830/Khanij/2019-20, Dated 13 <sup>th</sup> March, 2020                                     |       |                   |        |
| 31. | Details of Lease Area in approved DSR                                 | S.No.- 05, Page No.- 30<br>Correction Letter No.- 1109/Khanij/2021-22, dated- 01/01/2022                                   |       |                   |        |
| 32. | Proposed CER cost   | 1.35 Lakh  |       |                   |        |
| 33. | Proposed EMP cost   | 12.20 Lakh   |       |                   |        |
| 34. | Length and breadth of Haul Road.                                      | Length- 600m, Width- more than 6.0 m   |       |                   |        |
| 35. | No. of Trees to be Planted  | 250  |       |                   |        |

5. The mining would be restricted to the unsaturated zone only above the phreatic water table and will not intersect the groundwater table at any point in time.
6. The mining operation will not be carried out in the safety zone of any bridge or embankment or eco-fragile zone such as the habitat of any wild fauna.
7. There is no litigation pending in any court regarding this project.
8. The project proposal falls under category-1(a) of EIA Notification, 2006 (as amended).

### **RESOLUTION AGAINST AGENDA NO. 08**

**The committee noted that complaint letter dated 31/12/2021 of Shri Ashok Kumar Mishra, M/s Kamadgiri Traders, R/o Bihara, Tehsil-Karvi, District-Chitrakoot, U.P. have been received by the committee members.**

**The committee decided to share the aforesaid complaint letters with the Project Proponent/ Consultant. The Project Proponent/ Consultant mentioned that these complaints are baseless, and they will be able to give a written reply regarding the aforesaid complaints today itself i.e., 03/01/2022. The committee deliberated that the case shall be taken after receiving a satisfactory reply in this regard.**

The Project Proponent / Consultant have submitted a reply to the complaint of Shri Ashok Kumar Mishra. The reply are given below:

***“We are hereby clarifying that our Coordinates are as per the Vigypti published by the office of District Magistrate, Chitrakoot vide letter No. 2026/ Khanij/e-tender/ 2019 dated 18.11.2019, at Sr. No. -2 which is again verified by the District Magistrate, Chitrakoot vide letter No.- 1074/Khanij/2020-21. Dated 17-10-2020 & these geo coordinates are the base of preparing Mining Plan approved by the Directorate of Geology & Mining & consequently submitted in all Documents for the environment clearance of the Proposed “Granite (Khanda, Gitti, Boulder & Pahadi Red Morrum)” Project at Gata No.-2131/07, Village- Raulikalyanpur, Tehsil- Karwi, District- Chitrakoot, U.P.”***

**After detailed analysis, the committee did not find any merit in the complaint and recommended the grant of environmental clearance for the project proposal along with general and specific conditions as annexed at annexure-2 to these minutes. The committee also stipulated the following specific conditions:**

1. The project proponent shall install solar light in their site office.
2. During the submission of 6 monthly compliance reports, the project proponent should make sure that the periodically taken site photographs should also be annexed along with the compliance report.
3. Preference should be given to indigenous local species as per the consultation of the local district Forest Officer.
4. The maximum height of the bench should be 06 meters and the width of the bench should be at least twice the height of the bench as per the mine plan approval letter by DGM, U.P
5. In case the blasting is proposed during a mining operation, the project proponent needs to assess its impact on the displacement of human beings/wild animals/birds/other species, and the suitable measures proposed and taken for their rehabilitation and resettlement need to be clearly described in first 6 monthly compliance report.
6. The project proponent shall submit a final mine closure plan/Exit protocol for rehabilitation of mined-out land to match its surrounding land use 3years before the closure of the mine to SEIAA, UP and Department of Mines and Geology, UP for approval. The project proponent shall ensure the implementation of the approved plan under the supervision of the Dept. of Mines and Geology.
7. The project proponent shall plan and implement collection drain and siltation basins of adequate size to arrest the silt and sediment flow from the quarry area. The surface runoff rainwater harvesting and other water conservation measures on a long-term basis are to be taken in consultation with the Central/State Groundwater Board. The water so collected should be utilized for watering the haulage area, roads, and green belt development, etc.
8. The project proponent shall take all suitable measures to prevent pollution of groundwater and nearby water bodies in consultation with the State Pollution Control Board and consent to operate (if applicable) should be obtained from the State Pollution Control Board before the start of production from the mine.
9. Link Road from the quarry site to the main road shall be constructed as an all-weather road with blacktopping and maintained by the project proponent.
10. Vehicular emissions should be kept under control and regularly monitored. Suitable measures shall be taken for proper maintenance of vehicles used in a quarry operation and transportation.
11. The project proponent should explore the possibilities of rainwater harvesting.

**9. Stone (Sand Stone) Mining at Araj No.-01 Ka, Village- Sonpur, Tehsil- Chaunar, Mirzapur, U.P., Shri Prashant Kumar Singh, Area -0.809 ha. File No. 6771/4993/Proposal No. SIA/UP/MIN/70303/2019**

The consultant informed the committee that they are strictly following the rules, regulations and other instructions of QCI/NABET. A presentation was made by the project proponent along with their consultant M/s Paramarsh (Servicing Environment and Development), Lucknow, U.P. Based on the documents submitted and presentation made by the project proponent along with the consultant, the following facts have emerged: -

1. The environmental clearance is sought for Building Stone (Sand Stone) at Araj No.-1 Ka, Village- Sonpur, Tehsil- Chunar, District- Mirzapur, U.P., (Leased Area- 0.809 ha.).
2. The terms of reference in the matter were issued by SEIAA, U.P. vide letter no. 413/Parya/SEAC/4993/2019 dated 27/11/2019.
3. The public hearing was organized on 29/10/2020. Final EIA report submitted by the project proponent on 20/12/2021.
4. Salient features of the project as submitted by the project proponent:

|  |  |   |                                 |                      |
|--|--|---|---------------------------------|----------------------|
| 17. Salient features of the project as submitted by the project proponent. |  |   |                                 |                      |
| 1.   | On-line proposal No.                     | SIA/UP/MIN/70303/2019   |                                 |                      |
| 2.   | File No. allotted by SEIAA, UP           | 6771 / 4993   |                                 |                      |
| 3.   | Name of Proponent                        | Shri Prashant Kumar Singh S/o Shri Ramdhani Singh                                 |                                 |                      |
| 4.   | Full correspondence address of proponent | R/o- Patelnagar Garaudi, Thana- Adalhat, Tehsil- Chunar, District- Mirzapur, U.P. |                                 |                      |
| 5.   | Name of Project                          | Building Stone (Sand Stone) Mining Project  |                                 |                      |
| 6.   | Project location (Plot/ Khasra /GataNo.) | Araji No.-1 Ka  |                                 |                      |
| 7.   | Name of Village                          | Sonpur  |                                 |                      |
| 8.   | Tehsil                                   | Chunar  |                                 |                      |
| 9.   | District                                 | Mirzapur  |                                 |                      |
| 10.  | Name of Minor Mineral                    | Building Stone (Sand Stone)   |                                 |                      |
| 11.  | Sanctioned Lease Area (in Ha.)           | 0.809 ha.   |                                 |                      |
| 12.  | Max.& Min mRL within lease area          | 121.20 mRL- 108.10 mRL  |                                 |                      |
| 13.  | Pillar Coordinates (Verified by DMO)     | Pillars   | Latitude (N)                    | Longitude (E)        |
|  |  | A   | 25° 2.708"N                     | 83° 0.328"E          |
|  |  | B   | 25° 2.721"N                     | 83° 0.377"E          |
|  |  | C   | 25° 2.668"N                     | 83° 0.380"E          |
|  |  | D   | 25° 2.656"N                     | 83° 0.333"E          |
| 14.  | Total Geological Reserves                | 243962 m <sup>3</sup>   |                                 |                      |
| 15.  | Total Mineable Reserves                  | 61440 m <sup>3</sup>  |                                 |                      |
| 16.  | Total Proposed Production (in five Year) | 40450 m <sup>3</sup>  |                                 |                      |
| 17.  | Proposed Production / year               | Year  |                                 | Production           |
|  |  | 1 <sup>st</sup>   |                                 | 8090 m <sup>3</sup>  |
|  |  | 2 <sup>nd</sup>   |                                 | 8090 m <sup>3</sup>  |
|  |  | 3 <sup>rd</sup>   |                                 | 8090 m <sup>3</sup>  |
|  |  | 4 <sup>th</sup>   |                                 | 8090 m <sup>3</sup>  |
|  |  | 5 <sup>th</sup>   |                                 | 8090 m <sup>3</sup>  |
|  |  | Total   |                                 | 40450 m <sup>3</sup> |
|  |  | 18.   | Sanctioned Period of Mine lease | 20 Years             |
| 19.  | Method of Mining                         | Opencast Semi-Mechanized  |                                 |                      |
| 20.  | No.of working days                       | 300 days  |                                 |                      |
| 21.  | Working hours/day                        | 8 Hours/Day   |                                 |                      |
| 22.  | No.Of workers                            | 30 (approx.)  |                                 |                      |
| 23.  | No.Of vehicle movement /day              | 3 (approx.)   |                                 |                      |
| 24.  | Type of Land                             | Govt. revenue land  |                                 |                      |

|     |   |  |                   |
|-----|---|--|-------------------|
| 25. | Ultimate Depth of Mining  | 12 meter (average)   |                   |
| 26. | Nearest metalled road from site                                       | 0.50 km  |                   |
| 27. | Water Requirement   | PURPOSE  | REQUIREMENT (KLD) |
|     |   | Drinking & Others  | 0.30              |
|     |   | Suppression of dust  | 3.00              |
|     |   | Plantation   | 0.10              |
|     |   | Others( if any)  | -----             |
|     |   | Total  | 3.40              |
| 28. | Name of QCI Accredited Consultant with QCI No and period of validity. | M/s Paramarsh (Servicing Environment and Development), Lucknow, U.P.<br>QCI/NABET/EIA/1821/RA0120, Validity-13/01/2022 |                   |
| 29. | Any litigation pending against the project or land in any court       | No   |                   |
| 30. | Details of 500 m Cluster Map & certificate Verified by Mining Officer | DMO, Mirzapur vide Letter No. 511, Dated 12 <sup>nd</sup> June, 2019   |                   |
| 31. | Details of Lease Area in approved DSR                                 | Page No.-10, S.No.- 9  |                   |
| 32. | Proposed CER cost   | 1.20 Lakh  |                   |
| 33. | Proposed EMP cost   | 10.05 Lakh   |                   |
| 34. | Length and breadth of Haul Road.                                      | Length- 0.50 Km, Width- more than 6.0 m  |                   |
| 35. | No. of Trees to be Planted  | 100  |                   |

- The mining would be restricted to the unsaturated zone only above the phreatic water table and will not intersect the groundwater table at any point in time.
- The mining operation will not be carried out in the safety zone of any bridge or embankment or eco-fragile zone such as the habitat of any wild fauna.
- There is no litigation pending in any court regarding this project.
- The project proposal falls under category-1(a) of EIA Notification, 2006 (as amended).

### **RESOLUTION AGAINST AGENDA NO. 09**

**The committee discussed the matter and recommended the grant of environmental clearance for the project proposal along with general and specific conditions as annexed at Annexure-2 to the minutes. The committee also stipulated the following specific conditions:**

- The project proponent shall install solar light in their site office.
- During the submission of 6 monthly compliance reports, the project proponent should make sure that the periodically taken site photographs should also be annexed along with the compliance report.
- Preference should be given to indigenous local species as per the consultation of the local district Forest Officer.
- The maximum height of the bench should be 06 meters and the width of the bench should be at least twice the height of the bench as per the mine plan approval letter by DGM, U.P
- In case the blasting is proposed during a mining operation, the project proponent needs to assess its impact on the displacement of human beings/wild animals/birds/other species, and the suitable measures proposed and taken for their rehabilitation and resettlement need to be clearly described in first 6 monthly compliance report.
- The project proponent shall submit a final mine closure plan/Exit protocol for rehabilitation of mined-out land to match its surrounding land use 3years before the closure of the mine to SEIAA, UP and Department of Mines and Geology, UP for approval. The project proponent shall ensure the implementation of the approved plan under the supervision of the Dept. of Mines and Geology.
- The project proponent shall plan and implement collection drain and siltation basins of adequate size to arrest the silt and sediment flow from the quarry area. The surface runoff rainwater harvesting and other water conservation measures on a long-term basis are to be taken in consultation with the

Central/State Groundwater Board. The water so collected should be utilized for watering the haulage area, roads, and green belt development, etc.

8. The project proponent shall take all suitable measures to prevent pollution of groundwater and nearby water bodies in consultation with the State Pollution Control Board and consent to operate (if applicable) should be obtained from the State Pollution Control Board before the start of production from the mine.
9. Link Road from the quarry site to the main road shall be constructed as an all-weather road with blacktopping and maintained by the project proponent.
10. Vehicular emissions should be kept under control and regularly monitored. Suitable measures shall be taken for proper maintenance of vehicles used in a quarry operation and transportation.
11. The project proponent should explore the possibilities of rainwater harvesting.

**10. Soil Mining at Gata No-131 & 30, Village- Kondri, Tehsil- Bilari & District- Moradabad., Shri Subhan, Area: 1.905 Ha. File No. 6772/Proposal No. SIA/UP/MIN/246217/2021**

The consultant informed the committee that they are strictly following the rules, regulations and other instructions of QCI/NABET. A presentation was made by the project proponent along with their consultant M/s Ind Tech House Consult. Based on the documents submitted and presentation made by the project proponent along with the consultant, the following facts have emerged: -

1. The environmental clearance is sought for “Ordinary Soil Excavation” Project at Gata No.–131 & 30 Village-Kondri, Tehsil-Bilari, District- Moradabad, Uttar Pradesh. (Leased Area : 1.905 Ha.).
2. Salient features of the project as submitted by the project proponent:

| 1.            | On Line Proposal No.                                    | SIA/UP/MIN/246217/2021  |               |  |  |       |           |           |   |               |               |   |               |               |   |               |               |   |               |               |              |  |  |   |               |               |   |               |               |   |               |               |   |               |               |
|---------------|---|---|---------------|--|--|-------|-----------|-----------|---|---------------|---------------|---|---------------|---------------|---|---------------|---------------|---|---------------|---------------|--------------|--|--|---|---------------|---------------|---|---------------|---------------|---|---------------|---------------|---|---------------|---------------|
| 2.            | File No. allotted by SEIAA, UP                          | 6772  |               |  |  |       |           |           |   |               |               |   |               |               |   |               |               |   |               |               |              |  |  |   |               |               |   |               |               |   |               |               |   |               |               |
| 3.            | Name of Proponent                                       | Shri. Subhan  |               |  |  |       |           |           |   |               |               |   |               |               |   |               |               |   |               |               |              |  |  |   |               |               |   |               |               |   |               |               |   |               |               |
| 4.            | Full correspondence address of proponent and mobile no. | Shri Subhan S/o Mohd. Alam Vill- Karanpur, P.O- Yusufpur Nagaliya Tehsil & District- Moradabad U.P.   |               |  |  |       |           |           |   |               |               |   |               |               |   |               |               |   |               |               |              |  |  |   |               |               |   |               |               |   |               |               |   |               |               |
| 5.            | Name of Project   | Ordinary Soil Excavation” Project Subhan Gata No.–131 & 30 Village-Kondri, Tehsil-Bilari, District- Moradabad, Uttar Pradesh. (Area:1.905 Ha.)  |               |  |  |       |           |           |   |               |               |   |               |               |   |               |               |   |               |               |              |  |  |   |               |               |   |               |               |   |               |               |   |               |               |
| 6.            | Project Location(Plot.Khsra/Gata/Araji No.)             | Gata No.–131 & 30   |               |  |  |       |           |           |   |               |               |   |               |               |   |               |               |   |               |               |              |  |  |   |               |               |   |               |               |   |               |               |   |               |               |
| 7.            | Name of Village   | Kondri  |               |  |  |       |           |           |   |               |               |   |               |               |   |               |               |   |               |               |              |  |  |   |               |               |   |               |               |   |               |               |   |               |               |
| 8.            | Tehsil  | Bilari  |               |  |  |       |           |           |   |               |               |   |               |               |   |               |               |   |               |               |              |  |  |   |               |               |   |               |               |   |               |               |   |               |               |
| 9.            | District  | Moradabad   |               |  |  |       |           |           |   |               |               |   |               |               |   |               |               |   |               |               |              |  |  |   |               |               |   |               |               |   |               |               |   |               |               |
| 10.           | Name of Minor Mineral                                   | Ordinary Soil Excavation  |               |  |  |       |           |           |   |               |               |   |               |               |   |               |               |   |               |               |              |  |  |   |               |               |   |               |               |   |               |               |   |               |               |
| 11.           | Sanctioned Lease Area (in Ha.)                          | 1.905 Ha.   |               |  |  |       |           |           |   |               |               |   |               |               |   |               |               |   |               |               |              |  |  |   |               |               |   |               |               |   |               |               |   |               |               |
| 12.           | Max. & Min mRL within lease area                        | 202.0mRL& 200.00mRL   |               |  |  |       |           |           |   |               |               |   |               |               |   |               |               |   |               |               |              |  |  |   |               |               |   |               |               |   |               |               |   |               |               |
| 13.           | Pillar Coordinates (Verified by DMO)                    | <table border="1"> <thead> <tr> <th align="center" colspan="3">Gata No : 131</th></tr> <tr> <th>Point</th><th>Lattitude</th><th>Longitude</th></tr> </thead> <tbody> <tr> <td>A</td><td>28°46'14.98"N</td><td>78°40'20.01"E</td></tr> <tr> <td>B</td><td>28°46'17.21"N</td><td>78°40'24.19"E</td></tr> <tr> <td>C</td><td>28°46'15.33"N</td><td>78°40'25.98"E</td></tr> <tr> <td>D</td><td>28°46'13.80"N</td><td>78°40'20.65"E</td></tr> <tr> <th align="center" colspan="3">Gata No : 30</th></tr> <tr> <td>A</td><td>28°46'16.07"N</td><td>78°40'14.62"E</td></tr> <tr> <td>B</td><td>28°46'19.56"N</td><td>78°40'17.65"E</td></tr> <tr> <td>C</td><td>28°46'17.30"N</td><td>78°40'19.90"E</td></tr> <tr> <td>D</td><td>28°46'14.53"N</td><td>78°40'16.70"E</td></tr> </tbody> </table> | Gata No : 131 |  |  | Point | Lattitude | Longitude | A | 28°46'14.98"N | 78°40'20.01"E | B | 28°46'17.21"N | 78°40'24.19"E | C | 28°46'15.33"N | 78°40'25.98"E | D | 28°46'13.80"N | 78°40'20.65"E | Gata No : 30 |  |  | A | 28°46'16.07"N | 78°40'14.62"E | B | 28°46'19.56"N | 78°40'17.65"E | C | 28°46'17.30"N | 78°40'19.90"E | D | 28°46'14.53"N | 78°40'16.70"E |
| Gata No : 131 |   |   |               |  |  |       |           |           |   |               |               |   |               |               |   |               |               |   |               |               |              |  |  |   |               |               |   |               |               |   |               |               |   |               |               |
| Point         | Lattitude   | Longitude   |               |  |  |       |           |           |   |               |               |   |               |               |   |               |               |   |               |               |              |  |  |   |               |               |   |               |               |   |               |               |   |               |               |
| A             | 28°46'14.98"N   | 78°40'20.01"E   |               |  |  |       |           |           |   |               |               |   |               |               |   |               |               |   |               |               |              |  |  |   |               |               |   |               |               |   |               |               |   |               |               |
| B             | 28°46'17.21"N   | 78°40'24.19"E   |               |  |  |       |           |           |   |               |               |   |               |               |   |               |               |   |               |               |              |  |  |   |               |               |   |               |               |   |               |               |   |               |               |
| C             | 28°46'15.33"N   | 78°40'25.98"E   |               |  |  |       |           |           |   |               |               |   |               |               |   |               |               |   |               |               |              |  |  |   |               |               |   |               |               |   |               |               |   |               |               |
| D             | 28°46'13.80"N   | 78°40'20.65"E   |               |  |  |       |           |           |   |               |               |   |               |               |   |               |               |   |               |               |              |  |  |   |               |               |   |               |               |   |               |               |   |               |               |
| Gata No : 30  |   |   |               |  |  |       |           |           |   |               |               |   |               |               |   |               |               |   |               |               |              |  |  |   |               |               |   |               |               |   |               |               |   |               |               |
| A             | 28°46'16.07"N   | 78°40'14.62"E   |               |  |  |       |           |           |   |               |               |   |               |               |   |               |               |   |               |               |              |  |  |   |               |               |   |               |               |   |               |               |   |               |               |
| B             | 28°46'19.56"N   | 78°40'17.65"E   |               |  |  |       |           |           |   |               |               |   |               |               |   |               |               |   |               |               |              |  |  |   |               |               |   |               |               |   |               |               |   |               |               |
| C             | 28°46'17.30"N   | 78°40'19.90"E   |               |  |  |       |           |           |   |               |               |   |               |               |   |               |               |   |               |               |              |  |  |   |               |               |   |               |               |   |               |               |   |               |               |
| D             | 28°46'14.53"N   | 78°40'16.70"E   |               |  |  |       |           |           |   |               |               |   |               |               |   |               |               |   |               |               |              |  |  |   |               |               |   |               |               |   |               |               |   |               |               |

|     |   |  |                                 |
|-----|---|--|---------------------------------|
| 14. | Total Geological Reserves   | 41910 m3   |                                 |
| 15. | Total Mineable Reserve  | 22,000m <sup>3</sup> (3 months)                                      |                                 |
| 16. | Total Proposed Production   | 22,000m <sup>3</sup> (3 months)                                      |                                 |
| 17. | Total Proposed Production in 3months                                  | 22,000m <sup>3</sup>   |                                 |
| 18. | Sanctioned Period of Mine lease                                       | 3 months   |                                 |
| 19. | Method of Mining  | Open cast Manual/ Semi Mechanized Mining                             |                                 |
| 20. | No. of working days   | 90 Days  |                                 |
| 21. | Working hours/day   | 8 Hours  |                                 |
| 22. | No. of worker   | 25 Workers   |                                 |
| 23. | No. of vehicles movement/day  | 27Trucks / Day (Depending on market demand)                          |                                 |
| 24. | Type of Land  | Pvt. Land (Uneven Agricultural Land)                                 |                                 |
| 25. | Ultimate of Depth of Mining   | 2.2 m  |                                 |
| 26. | Nearest metalled road from site                                       | 1.0 Km   |                                 |
| 27. | Water Requirement   | PURPOSE  | REQUIREMENT (KLD)               |
|     |   | Drinking   | 0.19 KLD                        |
|     |   | Suppression of dust  | 1.14 KLD                        |
|     |   | Plantation   | 0.1KLD                          |
|     |   | Others (if any)  |                                 |
|     |   | Total  | <b>1.43 KLD Approx. 2.0 KLD</b> |
| 28. | Name of QCI Accredited Consultant with QCI No and period of validity. | Ind Tech House Consult QCI No.- 85<br>Period of Validity- 27-01-2022 |                                 |
| 29. | Any litigation pending against the project or land in any court       | No   |                                 |
| 30. | Details of 500 m Cluster Map & Certificate verified by Mining Officer | Letter No-542/Khanij/2021<br>Date-22.11.2021                         |                                 |
| 31. | Proposed CER cost   | 2% of total project cost i.e. Rs.33570                               |                                 |
| 32. | Proposed EMP cost   | 1.63 Lakhs   |                                 |
| 33. | Length and breadth of Haul Road                                       | 350 mt Length & 6m width haulage road                                |                                 |
| 34. | No. of Trees to be Planted  | 25Trees  |                                 |

3. The mining would be restricted to the unsaturated zone only above the phreatic water table and will not intersect the groundwater table at any point in time.
4. The mining operation will not be carried out in the safety zone of any bridge or embankment or eco-fragile zone such as the habitat of any wild fauna.
5. There is no litigation pending in any court regarding this project.
6. The project proposal falls under category-1(a) of EIA Notification, 2006 (as amended).

#### **RESOLUTION AGAINST AGENDA NO. 10**

**The committee discussed the matter and recommended grant of environmental clearance for the project proposal along with general and specific conditions as annexed at Annexure-4 to these minutes.**

#### **11. Stone (Gitti, Khanda & Boulder) Mining at Gata No.-745/2, Village-Makarbai, Tehsil-Sadar, Jhansi., Shri Suraj Prasad Gupta., area-1.182 ha. File No. 6422/Proposal No. SIA/UP/MIN/ 217555/2021**

The committee noted that the matter was earlier discussed in 507<sup>th</sup> SEIAA meeting dated 01/11/2021 and directed is as follows:

“SEIAA noted that SEAC has recommended to issue EC to the above project. SEIAA gone through a file and documents and found that in title there is a typographical error in the name of the district it should be Mahoba instead of Jhansi. SEIAA also noted that number of projects have been granted

EC in the same village, hence SEIAA opined that the project should be referred to SEAC to firm up the recommendation for the project with due diligence i.e. whether it is B1 or B2 category project.”

As per the direction of SEIAA, the matter was listed in 569<sup>th</sup> SEAC meeting dated 3/01/2022. The committee went through the file and documents and noted that due to typographical error in meeting of minutes dated 09/09/2021 the name of District mentioned as Jhansi instead of Mahoba, It should be read as Mahoba. The committee also noted that the project proponent submit a revised cluster certificate dated 17/11/2021 issued by Shri Shailendra Singh, Mining Officer, Mahoba mentioning that there is no other mining lease area within 500 meter radius of the Gata No. 745/2, Village-Makarbai and the total lease area within 500 meter radius is 1.182 hectare which is less than 5.0 hectare and project proposal comes under category B-2.

In view of above, the committee discussed the matter and recommended grant of environmental clearance for the project proposal along with general and specific conditions earlier prescribed in 569<sup>th</sup> SEAC meeting dated 09/09/2021.

**12. Granite Mine at Gata No.-1876, Khand No.-07 Village- Girwan, Tehsil- Naraini, Banda. Smt. Deepali Singh, Area-0.8 ha., File No. 6370/Proposal No. SIA/UP/MIN/64011/2021**

The committee noted that the matter was earlier discussed in 500<sup>th</sup> SEIAA meeting dated 12/10/2021 and directed is as follows:

“SEIAA noted that SEAC has recommended to issue ToR to the above project. SEIAA gone through file, documents and letter no. 1374/Khanij-30 dated 13.08.2019 regarding amendment in DSR and found that there is discrepancy in mode of mining operation. Hence SEIAA opined to refer back the project to SEAC. Further, validity period of consultant has not been mentioned.”

As per the direction of SEIAA, the matter was listed in 569<sup>th</sup> SEAC meeting dated 3/01/2022. The committee went through the file and documents and observed that the project proponent submit a clarification letter dated 07/12/2021 issued by Mining Officer, Banda mentioning that the method of mining is open cast with the help of hand tool machine. The project proponent also submits an extension of validity of accreditation letter dated 27/12/2021 issued by National Accreditation Board for Education and Training.

In view of above, the committee discussed the matter and recommended to issue terms of reference for the preparation of EIA report as earlier prescribed in 564<sup>th</sup> SEAC meeting dated 26/08/2021.

**13. Stone Mining at Gata No.-22, Khand No.-15, Village-Dunara, Tehsil-Sadar, Jhansi. Shri Mukul Yadav, Area-2.0 ha. File No. 6388/Proposal No. SIA/UP/MIN/64088/2021**

The committee noted that the matter was earlier discussed in 532<sup>nd</sup> SEIAA meeting dated 08/12/2021 and directed is as follows:

“SEIAA noted that the above project was taken in its meeting dated 21.10.2021 in which SEIAA noted that SEAC has recommended to issue the additional ToRs to the title proposal. SEIAA gone through file and documents and found that Geo coordinate proposed and Geo coordinates mentioned in mining plan are different. Hence SEIAA opined to refer back the project to SEAC for review/comments. The project proponent has submitted his reply vide letter dated 02.11.2021 which should have been submitted to SEAC for deliberation. SEIAA opined to refer the said letter to SEAC for deliberation.”

As per the direction of SEIAA, the matter was listed in 569<sup>th</sup> SEAC meeting dated 3/01/2022. The committee noted that the project proponent submitted their replies vide letter dated 02/11/2021 in reference to query raise by SEIAA. The project proponent submit revised geo-coordinates on notarized affidavit. The revised geo-coordinates are as follows:

| Pillars | Latitude(N)   | Longitude(E)  |
|---------|---------------|---------------|
| A       | 25°20'33.50"N | 78°41'28.46"E |
| B       | 25°27'33.00"N | 78°41'36.63"E |
| C       | 25°27'30.38"N | 78°41'36.35"E |
| D       | 25°27'30.38"N | 78°41'31.16"E |
| E       | 25°27'27.70"N | 78°41'31.00"E |
| F       | 25°27'27.70"N | 78°41'29.32"E |
| G       | 25°27'29.73"N | 78°41'29.96"E |
| H       | 25°27'32.00"N | 78°41'28.78"E |

In view of above, the committee discussed the matter and recommended to issue terms of reference for the preparation of EIA report as earlier prescribed in 567<sup>th</sup> SEAC meeting dated 03/09/2021 along with geo-coordinates mentioned as above.

**14. Integrated Industrial Township “Trans-Ganga City” at village- Shankarpur Sharai, Kanhwapur, Manbhauna, District- Unnao, U.P. M/s UP State Industrial Development Authority. File No. 1932/Proposal No. SIA/UP/MIS/ 247035/2021**

The committee noted that the environmental clearance for the above project was issued by SEIAA, U.P. vide letter no. 1714/Parya/1932/SEAC/2014/AD(H), dated 03/11/2014 for the plot area 4710971 sqm (1164.1 acres) and built-up area is 6338663.6 sqm respectively. The project proponent informed the committee that the environmental clearance was granted for the residential, commercial and mixed use development including Industrial units. The industries allowed in the EC are as follows:

- Glass Industry



- Bakery Production Industry
- Handloom and carpet Industry
- Cotton and Woolen Hosiery Industry
- Flour Mills
- Electronic Industry
- IT Based Industry
- Engineering Goods Assembling Units

During the presentation the project proponent informed that the validity of Environmental Clearance is valid for period of Seven Years, the existing EC is valid up to 02 November, 2022, the project proponent also informed that one year environment clearance validity extension has also been provided by MoEF&CC, Govt. of India vide notification dated 18/01/2021 due to COVID outbreak. As per EIA Notification, 2006 (as amended) also read along with Notification No. S.O. 221 (E) dated 18/01/2021 which mentions that:

*...“Notwithstanding anything contained in this notification, the period from the 1st April, 2020 to the 31st March, 2021 shall not be considered for the purpose of calculation of the period of validity of Prior Environmental Clearances granted under the provisions of this notification in view of outbreak of Corona Virus (COVID-19) and subsequent lockdowns (total or partial) declared for its control, however, all activities undertaken during this period in respect of the Environmental Clearance granted shall be treated as valid.”*

The project proponent UPSIDA proposed to add Beverages / Soft Drink industries under the premises of Trans-Ganga City and they have applied amended in environmental clearance dated 03/11/2014 which was earlier issued by SEIAA, U.P.

A presentation was made by the project proponent along with their consultant M/s Paramarsh (Servicing Environment and Development), Lucknow, U.P. The project proponent requested to add the industry of Soft Drink/Beverages in environmental clearance letter dated 03/11/2014 alongwith details mentioned below:

- Type of Industry – Soft drink/ Beverages
- Product – Flavor concentrates for Beverages
- Raw materials – Natural Flavors, Solvents, Emulsifiers and Treated water
- Major machinery for food processing – Liquid manufacturing and filling equipment, Dry salts Filling and Assembling Equipment, Utilities (Boiler, DG etc).
- Water requirements – 200 KLD
- Waste water requirement – 100 KLD
- Power requirements – 3800 KVA

#### **RESOLUTION AGAINST AGENDA NO. 14**

**The committee discussed the matter and recommended to amend the environmental clearance letter dated 03/11/2014 and add the industry of Soft drink/ Beverages as per above project proposal. Rest all the contents mentioned in environmental clearance letter no.**

1714/Parya/1932/SEAC/2014/AD(H), dated 03/11/2014 shall remain same. The committee stipulated following additional specific condition:

1. The project proponent shall ensure that no industrial effluent/waste water shall be discharged in the Ganga River.

Assistant Nodal, SEAC-1

Nodal, SEAC-1

(Dr. Ajai Mishra)  
**Member**

(Om Prakash Srivastava)  
**Member**

(Dr. Brij Bihari Awasthi)  
**Member**

(Umesh Chandra Sharma)  
**Member**

(Dr. Ratan Kar)  
**Member**

(Rajive Kumar)  
**Chairman**

**Annexure-1**

**Standard Terms of Reference for the Mining Project prescribed by MoEF&CC, GoI**

- 1) Year-wise production details since 1994 should be given, clearly stating the highest production achieved in any one year prior to 1994. It may also be categorically informed whether there had been any increase in production after the EIA Notification 1994 came into force, w.r.t. the highest production achieved prior to 1994.
- 2) A copy of the document in support of the fact that the proponent is the rightful lessee of the mine should be given.
- 3) All documents including approved mine plan, EIA and Public Hearing should be compatible with one another in terms of the mine lease area, production levels, waste generation and its management, mining technology etc. and should be in the name of the lessee.
- 4) All corner coordinates of the mine lease area, superimposed on a High Resolution Imagery/toposheet, topographic sheet, geomorphology and geology of the area should be provided. Such an Imagery of the proposed area should clearly show the land use and other ecological features of the study area (core and buffer zone).
- 5) Information should be provided in Survey of India Toposheet in 1:50,000 scale indicating geological map of the area, geomorphology of land forms of the area, existing minerals and mining history of the area, important water bodies, streams and rivers and soil characteristics.
- 6) Details about the land proposed for mining activities should be given with information as to whether mining conforms to the land use policy of the State; land diversion for mining should have approval from State land use board or the concerned authority.
- 7) It should be clearly stated whether the proponent Company has a well laid down Environment Policy approved by its Board of Directors? If so, it may be spelt out in the EIA Report with description of the prescribed operating process/procedures to bring into focus any infringement/deviation/ violation of the environmental or forest norms/ conditions? The hierarchical system or administrative order of the Company to deal with the environmental issues and for ensuring compliance with the EC conditions may also be given. The system of reporting of non-compliances / violations of environmental norms to the Board of Directors of the Company and/or shareholders or stakeholders at large, may also be detailed in the EIA Report.
- 8) Issues relating to Mine Safety, including subsidence study in case of underground mining and slope study in case of open cast mining, blasting study etc. should be detailed. The proposed safeguard measures in each case should also be provided.
- 9) The study area will comprise of 10 km zone around the mine lease from lease periphery and the data contained in the EIA such as waste generation etc. should be for the life of the mine / lease period.
- 10) Land use of the study area delineating forest area, agricultural land, grazing land, wildlife sanctuary, national park, migratory routes of fauna, water bodies, human settlements and other ecological features should be indicated. Land use plan of the mine lease area should be prepared to encompass preoperational, operational and post operational phases and submitted. Impact, if any, of change of land use should be given.
- 11) Details of the land for any Over Burden Dumps outside the mine lease, such as extent of land area, distance from mine lease, its land use, R&R issues, if any, should be given.
- 12) A Certificate from the Competent Authority in the State Forest Department should be provided, confirming the involvement of forest land, if any, in the project area. In the event of any contrary claim by the Project Proponent regarding the status of forests, the site may be inspected by the State Forest Department along with the Regional Office of the Ministry to ascertain the status of forests, based on which, the Certificate in this regard as mentioned above be issued. In all such cases, it would be desirable for representative of the State Forest Department to assist the Expert Appraisal Committees.

- 13) Status of forestry clearance for the broken up area and virgin forestland involved in the Project including deposition of net present value (NPV) and compensatory afforestation (CA) should be indicated. A copy of the forestry clearance should also be furnished.
- 14) Implementation status of recognition of forest rights under the Scheduled Tribes and other Traditional Forest Dwellers (Recognition of Forest Rights) Act, 2006 should be indicated.
- 15) The vegetation in the RF / PF areas in the study area, with necessary details, should be given.
- 16) A study shall be got done to ascertain the impact of the Mining Project on wildlife of the study area and details furnished. Impact of the project on the wildlife in the surrounding and any other protected area and accordingly, detailed mitigative measures required, should be worked out with cost implications and submitted.
- 17) Location of National Parks, Sanctuaries, Biosphere Reserves, Wildlife Corridors, Ramsar site Tiger/ Elephant Reserves/(existing as well as proposed), if any, within 10 km of the mine lease should be clearly indicated, supported by a location map duly authenticated by Chief Wildlife Warden. Necessary clearance, as may be applicable to such projects due to proximity of the ecologically sensitive areas as mentioned above, should be obtained from the Standing Committee of National Board of Wildlife and copy furnished.
- 18) A detailed biological study of the study area [core zone and buffer zone (10 km radius of the periphery of the mine lease)] shall be carried out. Details of flora and fauna, endangered, endemic and RET Species duly authenticated, separately for core and buffer zone should be furnished based on such primary field survey, clearly indicating the Schedule of the fauna present. In case of any scheduled- I fauna found in the study area, the necessary plan alongwith budgetary provisions for their conservation should be prepared in consultation with State Forest and Wildlife Department and details furnished. Necessary allocation of funds for implementing the same should be made as part of the project cost.
- 19) Proximity to Areas declared as 'Critically Polluted' or the Project areas likely to come under the 'Aravali Range', (attracting court restrictions for mining operations), should also be indicated and where so required, clearance certifications from the prescribed Authorities, such as the SPCB or State Mining Department should be secured and furnished to the effect that the proposed mining activities could be considered.
- 20) R&R Plan/compensation details for the Project Affected People (PAP) should be furnished. While preparing the R&R Plan, the relevant State/National Rehabilitation & Resettlement Policy should be kept in view. In respect of SCs /STs and other weaker sections of the society in the study area, a need based sample survey, family-wise, should be undertaken to assess their requirements, and action programmes prepared and submitted accordingly, integrating the sectoral programmes of line departments of the State Government. It may be clearly brought out whether the village(s) located in the mine lease area will be shifted or not. The issues relating to shifting of village(s) including their R&R and socio-economic aspects should be discussed in the Report.
- 21) One season (non-monsoon) [i.e. March-May (Summer Season); October-December (post monsoon season) ; December-February (winter season)]primary baseline data on ambient air quality as per CPCB Notification of 2009, water quality, noise level, soil and flora and fauna shall be collected and the AAQ and other data so compiled presented date-wise in the EIA and EMP Report. Site-specific meteorological data should also be collected. The location of the monitoring stations should be such as to represent whole of the study area and justified keeping in view the pre-dominant downwind direction and location of sensitive receptors. There should be at least one monitoring station within 500 m of the mine lease in the pre-dominant downwind direction. The mineralogical composition of PM10, particularly for free silica, should be given.
- 22) Air quality modeling should be carried out for prediction of impact of the project on the air quality of the area. It should also take into account the impact of movement of vehicles for transportation of mineral. The details of the model used and input parameters used for modeling should be provided. The air quality contours may be shown on a location map clearly indicating the location of the site, location of sensitive

receptors, if any, and the habitation. The wind roses showing pre-dominant wind direction may also be indicated on the map.

- 23) The water requirement for the Project, its availability and source should be furnished. A detailed water balance should also be provided. Fresh water requirement for the Project should be indicated.
- 24) Necessary clearance from the Competent Authority for drawl of requisite quantity of water for the Project should be provided.
- 25) Description of water conservation measures proposed to be adopted in the Project should be given.
- 26) Details of rainwater harvesting proposed in the Project, if any, should be provided.
- 27) Impact of the Project on the water quality, both surface and groundwater, should be assessed and necessary safeguard measures, if any required, should be provided.
- 28) Based on actual monitored data, it may clearly be shown whether working will intersect groundwater.
- 29) Necessary data and documentation in this regard may be provided. In case the working will intersect groundwater table, a detailed Hydro Geological Study should be undertaken and Report furnished. The Report inter-alia, shall include details of the aquifers present and impact of mining activities on these aquifers. Necessary permission from Central Ground Water Authority for working below ground water and for pumping of ground water should also be obtained and copy furnished.
- 30) Details of any stream, seasonal or otherwise, passing through the lease area and modification / diversion proposed, if any, and the impact of the same on the hydrology should be brought out.
- 31) Information on site elevation, working depth, groundwater table etc. Should be provided both in AMSL and bgl. A schematic diagram may also be provided for the same.
- 32) A time bound Progressive Greenbelt Development Plan shall be prepared in a tabular form (indicating the linear and quantitative coverage, plant species and time frame) and submitted, keeping in mind, the same will have to be executed up front on commencement of the Project. Phase-wise plan of plantation and compensatory afforestation should be charted clearly indicating the area to be covered under plantation and the species to be planted. The details of plantation already done should be given. The plant species selected for green belt should have greater ecological value and should be of good utility value to the local population with emphasis on local and native species and the species which are tolerant to pollution.
- 33) Impact on local transport infrastructure due to the Project should be indicated. Projected increase in truck traffic as a result of the Project in the present road network (including those outside the Project area) should be worked out, indicating whether it is capable of handling the incremental load. Arrangement for improving the infrastructure, if contemplated (including action to be taken by other agencies such as State Government) should be covered. Project Proponent shall conduct Impact of Transportation study as per Indian Road Congress Guidelines.
- 34) Details of the onsite shelter and facilities to be provided to the mine workers should be included in the EIA Report.
- 35) Conceptual post mining land use and Reclamation and Restoration of mined out areas (with plans and with adequate number of sections) should be given in the EIA report.
- 36) Occupational Health impacts of the Project should be anticipated and the proposed preventive measures spelt out in detail. Details of pre-placement medical examination and periodical medical examination schedules should be incorporated in the EMP. The project specific occupational health mitigation measures with required facilities proposed in the mining area may be detailed.
- 37) Public health implications of the Project and related activities for the population in the impact zone should be systematically evaluated and the proposed remedial measures should be detailed along with budgetary allocations.
- 38) Measures of socio economic significance and influence to the local community proposed to be provided by the Project Proponent should be indicated. As far as possible, quantitative dimensions may be given with time frames for implementation.
- 39) Detailed environmental management plan (EMP) to mitigate the environmental impacts which, should

inter-alia include the impacts of change of land use, loss of agricultural and grazing land, if any, occupational health impacts besides other impacts specific to the proposed Project.

- 40) Public Hearing points raised and commitment of the Project Proponent on the same along with time bound Action Plan with budgetary provisions to implement the same should be provided and also incorporated in the final EIA/EMP Report of the Project.
- 41) Details of litigation pending against the project, if any, with direction /order passed by any Court of Law against the Project should be given.
- 42) The cost of the Project (capital cost and recurring cost) as well as the cost towards implementation of EMP should be clearly spelt out.
- 43) A Disaster management Plan shall be prepared and included in the EIA/EMP Report.
- 44) Benefits of the Project if the Project is implemented should be spelt out. The benefits of the Project shall clearly indicate environmental, social, economic, employment potential, etc.
- 45) Besides the above, the below mentioned general points are also to be followed:-
  - a) Executive Summary of the EIA/EMP Report
  - b) All documents to be properly referenced with index and continuous page numbering.
  - c) Where data are presented in the Report especially in Tables, the period in which the data were collected and the sources should be indicated.
  - d) Project Proponent shall enclose all the analysis/testing reports of water, air, soil, noise etc. using the MoEF&CC/NABL accredited laboratories. All the original analysis/testing reports should be available during appraisal of the Project.
  - e) Where the documents provided are in a language other than English, an English translation should be provided.
  - f) The Questionnaire for environmental appraisal of mining projects as devised earlier by the Ministry shall also be filled and submitted.
  - g) While preparing the EIA report, the instructions for the Proponents and instructions for the Consultants issued by MoEF&CC vide O.M. No. J-11013/41/2006-IA.II(I) dated 4th August, 2009, which are available on the website of this Ministry, should be followed.
  - h) Changes, if any made in the basic scope and project parameters (as submitted in Form-I and the PFR for securing the TOR) should be brought to the attention of MoEF&CC with reasons for such changes and permission should be sought, as the TOR may also have to be altered. Post Public Hearing changes in structure and content of the draft EIA/EMP (other than modifications arising out of the P.H. process) will entail conducting the PH again with the revised documentation.
  - i) As per the circular no. J-11011/618/2010-IA.II(I) dated 30.5.2012, certified report of the status of compliance of the conditions stipulated in the environment clearance for the existing operations of the project, should be obtained from the Regional Office of Ministry of Environment, Forest and Climate Change, as may be applicable.
  - j) The EIA report should also include: (i) surface plan of the area indicating contours of main topographic features, drainage and mining area, (ii) geological maps and sections and (iii) sections of the mine pit and external dumps, if any, clearly showing the land features of the adjoining area.

**General and Specific Conditions for Gitti, Patthar& Boulder Mining Projects: -**

**A. General Conditions:**

1. This environmental clearance is subject to allotment of mining lease in favour of project proponent by District Administration/Mining Department.
2. Forest clearance shall be taken by the proponent as necessary under the law.
3. Any addition of the mining area, change of Khasra numbers, enhancement of capacity, change in mining technology, modernization, and scope of working shall again require prior environmental clearance as per EIA notification, 2006.
4. No change in the calendar plan including excavation, the quantum of mineral and waste shall be made.
5. Mining will be carried out as per the approved mining plan. In case of any violation of the mining plan, the Environmental Clearance given by SEIAA will stand cancelled.
6. Four ambient air quality monitoring stations shall be established in the core zone as well as in the buffer zone for RSPM, SPM, SO<sub>2</sub>, NO<sub>x</sub> monitoring. The location of the stations should be decided based on the meteorological data, topographical features, and environmentally and ecologically sensitive targets and frequency of monitoring should be undertaken in consultation with the State Pollution Control Board. The monitored data for criteria pollutants shall be regularly uploaded on the company's website and also displayed on the website.
7. Data on ambient air quality (RPM, SPM, SO<sub>2</sub>, NO<sub>x</sub>) should be regularly submitted to the Integrated Regional Office, MoEF&CC, GoI, Lucknow and the State Pollution Control Board / Central Pollution Control Board once in six months.
8. Ambient air quality at the boundary of the mine premises shall conform to the norms prescribed in MoEF notification no. GSR/826(E) dated 16.11.09.
9. Fugitive dust emissions from all the sources shall be controlled regularly. Water spraying arrangement on haul roads, loading and unloading, and at transfer points shall be provided and properly maintained.
10. Measures shall be taken for control of noise levels below 85 dBA in the work environment. Workers engaged in operations of HEMM, etc. shall be provided with earplugs/muffs and health records of the workers shall be maintained.
11. Industrial wastewater (workshop and wastewater from the mine) should be properly collected, treated to conform to the standards prescribed under GSR 422 (E) dated 19th May 1993 and 31st December 1993 or as amended from time to time. Oil and grease traps shall be installed before the discharge of workshop effluents.
12. Personnel working in areas shall be provided with protective respiratory devices like masks and they shall also be imparted adequate training and information on safety and health aspects.
13. Special measures shall be adopted to prevent the nearby settlements from the impacts of mining activities.
14. The transportation of the materials shall be limited to the day hours' time only.
15. Provision shall be made for housing the laborers within the site with all necessary infrastructure and facilities such as fuel for cooking, mobile toilets, safe drinking water, medical health care, crèche, etc. The housing may be in the form of temporary structures to be removed after the completion of the project.
16. A separate Environmental Management Cell with suitably qualified personnel shall be setup under the control of a Senior Executive, who will report directly to the Head of the Organization.
17. The Project Proponent shall inform the Integrated Regional Office, MoEF&CC, GoI, Lucknow and State Pollution Control Board regarding the date of financial closures and final approval of the project by the concerned authorities and the date of start of land development work.

18. The funds earmarked for environmental protection measures shall be kept in a separate account and shall not be diverted for other purposes. The year-wise expenditure shall be reported to the Integrated Regional Office, MoEF&CC, GoI, Lucknow and State Pollution Control Board
19. The Integrated Regional Office, MoEF&CC, GoI, Lucknow and State Pollution Control Board shall monitor compliance with the stipulated conditions. A complete set of documents including Environment Impact Assessment Report, Environmental Management Plan, Public hearing, and other documents information should be given to the Integrated Regional Office, MoEF&CC, GoI, Lucknow and State Pollution Control Board
20. A copy of the environmental clearance shall be submitted by the Project Proponent to the Heads of the Local Bodies, Panchayat, and Municipal Bodies as applicable in the matter.
21. The Project Proponent shall advertise at least in two local newspapers widely circulated, one of which shall be in the vernacular language of the locality concerned, within 7 days of the issue of the clearance letter informing that the project has been accorded environmental clearance and a copy of the clearance letter is available with the State Level Environment Impact Assessment Authority (SEIAA).
22. The Project Proponent has to submit a regular half-yearly compliance report of the stipulated prior environmental clearance terms and conditions in hard and soft copy to the SEIAA, U.P. on 1<sup>st</sup> June and 1<sup>st</sup> December of each calendar year.
23. The SEIAA may alter/modify the above conditions or stipulate any further condition in the interest of environmental protection.
24. Concealing factual data or submission of false/fabricated data and failure to comply with any of the conditions mentioned above may result in withdrawal of this clearance and attract action under the provisions of the Environment (Protection) Act, 1986.

**B. Specific Conditions:**

1. At the time of operation, the project proponent will comply with all the guidelines issued by the Government of India/State Govt./District Administration related to Covid-19.
2. This environmental clearance does not create or verify any claim of the applicant on the proposed site/activity.
3. In case it has been found that the E.C. obtained by providing incorrect information, submitting that the distance between the two adjoining mines is greater than 500mt. and the area is less than 05ha, but factually the distance is less than 500 mt, and the mine is located in the cluster of area equal to or more than 05ha, the E.C issued will stand revoked.
4. This environmental clearance shall be subject to a valid lease in favor of the project proponent for the proposed mining proposals. In case, the project proponent does not have a valid lease, this environmental clearance shall automatically become null and void.
5. The Environmental clearance will be co-terminus with the mining lease period/Mining Plan. The Mining plan approved by the Dept. of Mines and Geology shall be strictly implemented and shall not be operated beyond the validity period.
6. Explosive cannot be stored on the site. The Project proponent shall take approval from Chief Controller of Explosive, if applicable for use or storage of explosive or any such materials.
7. A comprehensive EIA including mining areas within 15 K.M. to assess the impact of the mining activity on the surrounding area shall be undertaken and a report submitted to this Authority within one year.
8. No two pits shall be simultaneously worked i.e. before the first is exhausted and reclamation work completed, no mineral bearing area shall be worked.
9. After exhausting the first mine pit and before starting mining operations in the next pit, reclamation and plantation work in the exhausted pit shall be completed to ensure that reclamation, forest cover, and vegetation are visible during the first year of mining operations in the next pit. This process



will follow till the last pit is exhausted. Adequate rehabilitation of mined pit shall be completed before any new ore-bearing area is worked for expansion.

10. An adequate buffer zone shall be maintained between two consecutive mineral-bearing deposits.
11. The sprinkling of water on haul roads to control dust will be ensured by the project proponent.
12. Green belt development shall be carried out considering CPCB guidelines including the selection of plant species and in consultation with the local DFO / Agriculture Department. Herbs and shrubs shall also form a part of the afforestation programme besides tree plantation. The company shall involve local people in the plantation programme. Details of year-wise afforestation programme including rehabilitation of mined-out area shall be submitted to the Integrated Regional Office, MoEF&CC, GoI, Lucknow every year.
13. Blast vibrations study shall be conducted and an observation report submitted to the Integrated Regional Office, MoEF&CC, GoI, Lucknow and UPPCB within six months. The report shall also include measures for the prevention of blasting associated impact on nearby houses and agricultural fields.
14. Controlled blasting techniques with sequential blasting shall be adopted. The blasting shall be carried out in the daytime only. The project proponent shall ensure prevention of displacement of human beings/wild animals/birds etc. and in case any such displacement is caused due to blasting/mining operation by any chance the project proponent shall take suitable measures for their rehabilitation and resettlement.
15. Appropriate arrangement for shelter and drinking water for the mining workers has to be ensured at the mining site.
16. Maintenance of village roads used for transportation of minerals is to be done by the company regularly at its own expenses. The link roads from mining area to main road shall be constructed as all-weather road with black topping and maintained by the project proponent.
17. The surface runoff rain water harvesting/rain water recharge and water conservation measures will be taken by project proponent in consultation with central /State ground water Board. The project proponent shall plan and implement collection drain and siltation basins of adequate size to arrest the silt and sediment flows from the mining area. The supernatant of the siltation basin and rain water harvested water shall be utilized for watering the haulage area, roads and green belt development etc.
18. Status of implementation shall be submitted to the Integrated Regional Office, MoEF&CC, GoI, Lucknow and UP Pollution Control Board within six months and thereafter every year from the next consequent year.
19. The self-environmental audit shall be conducted annually. Every three years third-party environmental audit shall be carried out.
20. Measures for prevention and control of soil erosion and management of silt shall be undertaken. Protection of dumps against erosion shall be carried out with geotextile matting or other suitable material, and thick plantations of native trees and shrubs shall be carried out at the dump slopes. Dumps shall be protected by retaining walls.
21. Trenches/garland drains shall be constructed at foot of dumps and coco filters installed at regular intervals to arrest silt from being carried to water bodies. An adequate number of Check Dams and Gully Plugs shall be constructed across seasonal/perennial nallahs if any flowing through the ML area and silts arrested. De silting at regular intervals shall be carried out.
22. Garland drain of appropriate size, gradient, and length shall be constructed for both mine pit and waste dump and sump capacity shall be designed keeping 50% safety margin over and above peak sudden rainfall (based on 50 years data) and maximum discharge in the area adjoining the mine site. Sump capacity shall also provide an adequate retention period to allow proper settling of silt material. Sedimentation pits shall be constructed at the corners of the garland drains and de silted at regular intervals.
23. Ground and surface water, if any in and near the core zone (within 5.0 km of the lease) shall be regularly monitored for contamination and depletion due to mining activity and records maintained.

The monitoring data shall be submitted to the Integrated Regional Office, MoEF&CC, GoI, Lucknow and U.P. Pollution Control Board regularly. Further, monitoring points shall be located between the mine, and drainage in the direction of flow of groundwater shall be set up and records maintained.

24. Fugitive dust generation shall be controlled. Fugitive dust emission shall be regularly monitored at locations of nearest human habitation (including schools and other public amenities located nearest to sources of dust generation as applicable) and records submitted to the Integrated Regional Office, MoEF&CC, GoI, Lucknow and U.P. Pollution Control Board regularly.
25. Baseline data for ambient air quality shall be generated and maintained and RSPM level in ambient air in the nearby human habitation (villages) shall also be monitored along with other parameters.
26. Corporate Environmental Responsibility (CER) shall be by the project proponent and the details of the various heads of expenditure are to be submitted as per the guidelines provided in the recent CER notification No. 22-65/2017-IA.III dated 01/05/2018. Work to be executed with the installation of five hand pumps for drinking water, solar light in villages of streets, construction of two numbers of toilets at the primary school with name displayed and address and details of the beneficiary and gram Pradhan along with phone number, photographs should be submitted to Directorate as well as to the District Magistrate / Chief Development officers.
27. Transportation of minerals shall be done by covering the trucks with tarpaulin or other suitable mechanisms so that no spillage of mineral/dust takes place.
28. Occupational health and safety measures for the workers including identification of work-related health hazards, training on malaria eradication, HIV, and health effects on exposure to mineral dust, etc. shall be carried out. Periodic monitoring for exposure to respirable mineral dust on the workers shall be conducted and records maintained including the health records of the workers. Awareness programmes for workers on the impact of mining on their health and precautionary measures like the use of personal protective equipment etc. shall be carried out periodically. A review of the impact of various health measures shall be conducted followed by follow-up action wherever required.
29. The project proponent will ensure for employing local people as per requirement, necessary protection measures around the mine pit and waste dump, and garland drain around the mine pit and waste dump.
30. Topsoil / solid waste shall be stacked properly with proper slope and adequate safeguards and shall be utilized for backfilling (wherever applicable) for reclamation and rehabilitation of the mined-out area. Topsoil shall be separately stacked for utilization later for reclamation and shall not be stacked along with overburden.
31. Overburden (OB) shall be stacked at the earmarked dump site(s) only and shall not be kept active for long period. The maximum height of the dump shall not exceed 20 m, each stage shall preferably be of a maximum of 10 m and the overall slope of the dump shall not exceed 35°. The OB dump shall be backfilled. The OB dumps shall be scientifically vegetated with suitable native species to prevent erosion and surface runoff.
32. Monitoring and management of rehabilitated areas shall continue until the vegetation becomes self-sustaining. Compliance status shall be submitted to the Regional Office, Ministry of Environment & Forests, GoI, Lucknow, and U.P. Pollution Control Board on a six-monthly basis.
33. The slope of the mining bench and ultimate pit limit shall be as per the mining scheme approved by the Indian Bureau of Mines.
34. Permission for the abstraction of groundwater shall be taken from Central Ground Water Board. Regular monitoring of ground and surface water sources for level and quality shall be carried out by establishing a network of existing wells and constructing new piezometers during the mining operation. The monitoring shall be carried out four times in a year i.e., premonsoon (April/May), monsoon (August), post-monsoon (November), and winter (January), and the data thus collected shall be regularly sent to MoEF&CC, Central Ground Water Authority, and Regional Director, Central Ground Water Board.

35. The wastewater from the mine shall be treated to conform to the prescribed standards before discharging into the natural stream. The discharged water from the Tailing Dam, if any shall be regularly monitored and report submitted to the Integrated Regional Office, MoEF&CC, GoI, Lucknow, Central Pollution Control Board, and the State Pollution Control Board.
36. Hydrogeological study of the area shall be reviewed by the project proponent annually. In case the adverse effect on groundwater quality and quantity is observed mining shall be stopped and resumed only after mitigating steps to contain any adverse impact on groundwater is implemented.
37. Vehicular emissions shall be kept under control and regularly monitored. Vehicles used for transportation of minerals and others shall have valid permissions as prescribed under Central Motor Vehicle Rules, 1989 and its amendments. The vehicles transporting minerals shall be covered with a tarpaulin or other suitable enclosures so that no dust particles / fine matters escape during the period of transportation. No overloading of minerals for transportation shall be committed. The trucks transporting minerals shall not pass through the wildlife sanctuary if any in the study area.
38. Prior permission from the Competent Authority shall be obtained for the extraction of groundwater if any.
39. A final mine closure plan, along with details of Corpus Fund, shall be submitted to the Integrated Regional Office, MoEF&CC, GoI, Lucknow and U.P. Pollution Control Board 5 years in advance of final mine closure for approval.
40. Project Proponent shall explore the possibility of using solar energy where ever possible.
41. Commitment towards CER has to be followed strictly.
42. Regular health checkup record of the mineworkers has to be maintained at the site in a proper register. It should be made available for inspection whenever asked.
43. Project Proponent has to strictly follow the direction/guidelines issued by MoEF&CC, CPCB, and other Govt. Agencies from time to time.
44. The blasting will be done only after getting permission from the Mining Department.

**General and Specific Conditions for Sand/Morum Mining Proposals**

**General Conditions:**

1. This environmental clearance is subject to allotment of mining lease in favour of project proponent by District Administration/Mining Department.
2. Forest clearance shall be taken by the proponent as necessary under law.
3. Any change in mining area, khasra numbers, entailing capacity addition with change in process and or mining technology, modernization and scope of working shall again require prior Environmental Clearance as per the provisions of EIA Notification, 2006 (as amended).
4. Precise mining area will be jointly demarcated at site by project proponent and officials of Mining/Revenue department prior to starting of mining operations. Such site plan, duly verified by competent authority along-with copy of the Environmental Clearance letter will be displayed on a hoarding/board at the site. A copy of site plan will also be submitted to SEIAA within a period of 02 months.
5. Mining and loading shall be done only within day hours' time.
6. No mining shall be carried out in the safety zone of any bridge and/or embankment.
7. It shall be ensured that standards related to ambient air quality/effluent as prescribed by the Ministry of Environment & Forests are strictly complied with. Water sprinklers and other dust control majors should be applied to take-care of dust generated during mining operation. Sprinkling of water on haul roads to control dust will be ensured by the project proponent.
8. All necessary statutory clearances shall be obtained before start of mining operations. If this condition is violated, the clearance shall be automatically deemed to have been cancelled.
9. Parking of vehicles should not be made on public places.
10. No tree-felling will be done in the leased area, except only with the permission of Forest Department.
11. No wildlife habitat will be infringed.
12. It shall be ensured that excavation of minor mineral does not disturb or change the underlying soil characteristics of the river bed /basin, where mining is carried out.
13. It shall be ensured that mining operation of Sand/Moram will not in any way disturb the, velocity and flow pattern of the river water significantly.
14. It shall be ensured that there is no fauna dependant on the river bed or areas close to mining for its nesting. A report on the same, vetted by the competent authority shall be submitted to the RO, PCB and SEIAA within 02 months.
15. Primary survey of flora and fauna shall be carried out and data shall be submitted to the RO, PCB and SEIAA within six months.
16. Hydro-geological study shall be carried out by a reputed organization/institute within six months and establish that mining in the said area will not adversely affect the ground water regime. The report shall be submitted to the RO, PCB and SEIAA within six months. In case adverse impact is observed /anticipated, mining shall not be carried out.
17. Adequate protection against dust and other environmental pollution due to mining shall be made so that the habitations (if any) close by the lease area are not adversely affected. The status of implementation of measures taken shall be reported to the RO, UPPCB and SEIAA and this activity should be completed before the start of sand mining.
18. Need-based assessment for the nearby villages shall be conducted to study economic measures which can help in improving the quality of life of economically weaker section of society. Income generating projects/tools such as development of fodder farm, fruit bearing orchards, vocational training etc. can form a part of such program me. The project proponent shall provide separate budget for community development activities and income generating programmes.

19. Green cover development shall be carried out following CPCB guidelines including selection of plant species and in consultation with the local DFO/Horticulture Officer.
20. Separate stock piles shall be maintained for excavated top soil, if any, and the top soil should be utilized for green cover/tree plantation.
21. Dispensary facilities for first-aid shall be provided at site.
22. An Environmental Audit should be annually carried out during the operational phase and submitted to the SEIAA.
23. The District Mining Officer should quarterly monitor compliance of the stipulated conditions. The project proponent will extend full cooperation to the District Mining Officer by furnishing the requisite data/information/monitoring reports. In case of any violations of stipulated conditions the District Mining Officer will report to SEIAA.
24. The project proponent shall submit six monthly reports on the status of compliance of the stipulated environmental clearance conditions including results of monitored data (both in hard & soft copies) to the SEIAA, the District Officer and the respective Regional Office of the State Pollution Control Board by 1st June and 1st December every year.
25. A copy of the clearance letter shall be sent by the proponent to concerned Panchayat, Zila Parisad/ Municipal Corporation and Urban Local Body.
26. Transportation of materials shall be done by covering the trucks / tractors with tarpaulin or other suitable mechanism to avoid fugitive emissions and spillage of mineral/dust.
27. Waste water, from temporary habitation campus be properly collected & treated before discharging into water bodies the treated effluent should conform to the standards prescribed by MoEF/CPCB.
28. Measures shall be taken for control of noise level to the limits prescribed by C.P.C.B.
29. Special Measures shall be adopted to protect the nearby settlements from the impacts of mining activities. Maintenance of Village roads through which transportation of minor minerals is to be undertaken, shall be carried-out by the project proponent regularly at his own expenses.
30. Measure for prevention & control of soil erosion and management of silt shall be undertaken. Protection of dumps against erosion, if any, shall be carried-out with geo textile matting or other suitable material.
31. Under corporate social responsibility a sum of 5% of the total project cost or total income whichever is higher is to be earmarked for total lease period. Its budget is to be separately maintained. CER component shall be prepared based on need of local habitant. Income generating measures which can help in upliftment of poor section of society, consistent with the traditional skills of the people shall be identified. The programme can include activities such as development of fodder farm, fruit bearing orchards, free distribution of smokeless Chula etc.
32. Possibility for adopting nearest three villages shall be explored and details of civic amenities such as roads, drinking water etc proposed to be provided at the project proponent's expenses shall be submitted within 02 months from the date of issuance of Environment Clearance.
33. The funds earmarked for environmental protection measures should be kept in separate account and should not be diverted for other purpose. Year wise expenditure should be reported to the Integrated Regional Office, MoEF&CC, GoI, Lucknow, SEIAA, U.P and UPPCB.
34. Action plan with respect to suggestion/improvement and recommendations made and agreed during Public Hearing shall be submitted to the District mines Officer, concern Regional Officer of UPPCB and SEIAA within 02 months.
35. Environmental clearance is subject to obtaining clearance under the Wildlife (Protection) Act, 1972 from the competent authority, if applicable to this project.
36. The proponent shall observe every 15 day for nesting of any turtle in the area. Based on the observations so made, if turtle nesting is observed, necessary safeguard measures shall be taken in consultation with the State Wildlife Department. For the purpose, awareness shall be created amongst the workers about the nesting sites so that such sites, if any, are identified by the workers during operations of the mine for taking required safeguard measures. In this regards the safety notified zone should be left so that the habitat/nesting area is undisturbed.

37. The project proponent shall undertake adequate safeguard measures during extraction of river bed material and ensure that due to this activity the hydro geological regime of the surrounding area shall not be affected.
38. The project proponent shall obtain necessary prior permission of the competent Authorities for withdrawal of requisite quantity of water (surface water and groundwater), required for the project.
39. Appropriate mitigative measures shall be taken to prevent pollution of the river in consultation with the State Pollution Control Board. It shall be ensured that there is no leakage of oil and grease in the river from the vehicles used for transportation.
40. Vehicular emissions shall be kept under control and regularly monitored. The vehicles carrying the mineral shall not be overloaded.
41. Provision shall be made for the housing of construction labour within the site with all necessary infrastructure and facilities such as fuel for cooking, mobile toilets, mobile STP, safe drinking water, medical health care, crèche etc. (MoEF circular Dated : 22-09-2008 regarding stipulation of condition to improve the living conditions of construction labour at site).
42. Personnel working in dusty areas should wear protective respiratory devices and they should also be provided with adequate training and information on safety and health aspects. Occupational health surveillance program of the workers should be undertaken periodically to observe any contractions due to exposure to dust and take corrective measures, if needed.
43. A copy of the clearance letter shall be sent by the proponent to concerned Panchayat, Zila Parishad/ Municipal Corporation, Urban Local Body and the Local NGO, if any, from whom suggestions/ representations, if any, were received while processing the proposal. The clearance letter shall also be put on the website of the Company by the proponent.
44. The environmental statement for each financial year ending 31st March in Form-V as is mandated to be submitted by the project proponent to the concerned State Pollution Control Board as prescribed under the Environment (Protection) Rules, 1986, as amended subsequently, shall also be put on the website of the company along with the status of compliance of environmental clearance conditions and shall also be sent to the Integrated Regional Office, MoEF&CC, GoI, Lucknow by e-mail.
45. The green cover development/tree plantation is to be done in an area equivalent to 20% of the total leased area either on river bank or along road side (Avenue Plantation).
46. Debris from the river bed will be collected and stored at secured place and may be utilized for strengthen the embankment.
47. Safety measures to be taken for the safety of the people working at the mine lease area should be given, which would also include measure for treatment of bite of poisonous reptile/insect like snake.
48. Periodical and Annual medical checkup of workers as per Mines Act and they should be covered under ESI as per rule.

**Specific Conditions:**

1. The Environmental clearance will be co-terminus with the mining lease period.
2. At the time of operation, project proponent will comply with all the guidelines issued by Government of India/State Govt./District Administration related to Covid-19.
3. Environment management in according to environmental status and impact of the project.
4. During the school opening and closing time transportation of minerals will be restricted.
5. Selection of plants for green belt should be on the basis of pollution removal index. Project proponent should ensure survival of tree saplings. Mortality should be replaced from time to time.
6. No mining activity should be carried out in-stream channel as per SSMMG, 2016.
7. Pakkamotorable haul road to be maintained by the project proponent.
8. A separate Environmental Management Cell with suitable qualified personnel shall be set-up under the control of a Senior Executive, who will report directly to the Head of the Organization.

9. Permission from the competent authority regarding evacuation route should be taken.
10. One month monitoring report of the area for air quality, water quality, Noise level. Besides flora & fauna should be examined twice a week and be submitted within 45 days for a record.
11. Provision for cylinder to workers should be made for cooking.
12. The capacity of trucks/tractor for loading purpose will be in tonnes as per Transport Department applicable norms and standard fixed by the Government.
13. Approach road kaccha is to be made motarable and tree saplings to be planted on both sides of the road. Width of the haul road shall be more than 6 meter.
14. Indigenous plants should be planted according to CPCB guidelines and in consultation with local Divisional Forest Officer.
15. The project proponent shall in 2 years conduct detailed replenishment study duly authenticated by a QCI-NABET accredited consultant, and the District Mines Officer.
16. Provision for two toilets and hand pumps should be made at mining site.
17. Drinking water for workers would be provided by tankers.
18. Mining should be done by Bar scalping methods extraction (typically 0.3 -0.6 m or 1 - 2 ft) as per sustainable sand mining management guidelines 2016.
19. A buffer/safe zone shall be maintained from the habitation as per mining guidelines.
20. Corporate Environmental Responsibility (CER) plan shall be prepared by the project proponent and the details of the various heads of expenditure to be submitted as per the guidelines provided in the recent CER notification No. 22-65/2017-IA.III dated 01/05/2018.
21. Health/Insurance card, Medical claim, regular health check-up camps, facilities shall be provided to the regular/temporary/Contractual or any base workers. Copy of receipt shall be produced to the Directorate of Environment along with the compliance report.
22. Measure for conservation of water through rainwater harvesting and cleaning and maintenance of natural surface water bodies of the nearby areas may be considered as one of the activity in CER.
23. The excavated mining material should be carried and transported in such a way that no obstruction to the free flow of water takes place. Suitable measure should be taken and details to be provided to concern Department.
24. Submit annual replenishment report certified by an authorized agency. In case the replenishment is lower than the approved rate of production, then the mining activity / production levels shall be decreased / stopped accordingly till the replenishment is completed.
25. The project proponent shall ensure that if the project area falls within the eco-sensitive zone of National park/ Sanctuary prior permission of statutory committee of National board for wild life under the provision of Wildlife (Protection) Act, 1972 shall be obtained before commencement of work.
26. If in future this lease area becomes part of cluster of equal to or more than 05 ha. then additional conditions based on the EIA shall be imposed. The lease holder shall mandatorily follow cluster conditions otherwise it will amount to violation of E.C. conditions. If the certificate related to cluster provided by the competent authority is found false or incorrect then punitive actions as per law shall be initiated against the authority issuing the cluster certificate.
27. Project falling within 10 KM area of Wild Life Sanctuary is to obtain a clearance from National Board Wild Life (NBWL) even if the eco-sensitive zone is not earmarked.
28. To avoid ponding effect and adverse environmental conditions for sand mining in area, progressive mining should be done as per sustainable sand mining management guidelines 2016.
29. In case it has been found that the E.C. obtained by providing incorrect information, submitting that the distance between the two adjoining mines is greater than 500mt. and area is less than 05 ha, but factually the distance is less than 500 mt and the mine is located in cluster of area equal or more than 05 ha, the E.C issued will stand revoked.
30. The project proponent shall in 2 years conduct detailed replenishment study duly authenticated by a QCI-NABET accredited consultant, and the District Mines Officer which shall form the basis for midterm review of conditions of Environmental Clearance.

31. The mining work will be open-cast and manual/semi mechanized (subject to order of Hon'ble NGT/Hon'ble Courts (s)). Heavy machine such as excavator, scooper etc. should not be employed for mining purpose. No drilling/blasting should be involved at any stage.
32. It shall be ensured that there shall be no mining of any type within 03 m or 10% of the width which-ever is less, shall be left on both the banks of precise area to control and avoid erosion of river bank. The mining is confined to extraction of sand/moram from the river bank only.
33. The project proponent shall undertake adequate safeguard measures during extraction of river bank material and ensure that due to this activity the hydro-geological regime of the surrounding area shall not be affected.
34. The project proponent shall adhere to mining in conformity to plan submitted for the mine lease conditions and the Rules prescribed in this regard clearly showing the no work zone in the mine lease i.e. the distance from the bank of river to be left un-worked (Non mining area), distance from the bridges etc. It shall be ensured that no mining shall be carried out during the monsoon season.
35. The project proponent shall ensure that wherever deployment of labour attracts the Mines Act, the provision thereof shall be strictly followed.
36. The project proponent will provide personal protective equipment (PPE) as required, also provide adequate training and information on safety and health aspects. Periodical medical examination of the workers engaged in the project shall be carried out and records maintained. For the purpose, schedule of health examination of the workers should be drawn and followed accordingly.
37. The critical parameters such as PM10, PM2.5, SO2 and NOx in the ambient air within the impact zone shall be monitored periodically. Further, quality of discharged water if any shall also be monitored [(TDS, DO, pH, Fecal Coliform and Total Suspended Solids (TSS)].
38. Effective safeguard measures, such as regular water sprinkling shall be carried out in critical areas prone to air pollution and having high levels of particulate matter such as loading and unloading point and all transfer points. Extensive water sprinkling shall be carried out on haul roads.
39. It should be ensured that the Ambient Air Quality parameters conform to the norms prescribed by the Central Pollution Control Board in this regard.
40. The extended mining scheme will be submitted by the proponent before expiry of present mining plan.
41. Four ambient air quality-monitoring stations should be established in the core zone as well as in the buffer zone for monitoring PM10, PM2.5, SO2 and NOx. Location of the stations should be decided based on the meteorological data, topographical features and environmentally and ecologically sensitive targets and frequency of monitoring should be undertaken in consultation with the State Pollution Control Board.
42. Common road for transportation of mineral is to be maintained collectively. Total cost will be shared/worked out on the basis of lease area among users.
43. Proponent will provide adequate sanitary facility in the form of mobile toilets to the labours engaged for the project work.
44. Solid waste material viz., gutkhapouchs, plastic bags, glasses etc. to be generated during project activity will be separately storage in bins and managed as per Solid Waste Management rules.
45. Natural/customary paths used by villagers should not be obstructed at any time by the activities proposed under the project.
46. Digital processing of the entire lease area in the district using remote sensing technique should be done regularly once in three years for monitoring the change of river course by Directorate of Geology and Mining, Govt. of Uttar Pradesh. The record of such study to be maintained and report be submitted to Integrated Regional Office, MoEF&CC, GoI, Lucknow, SEIAA, U.P. and UPPCB.
47. The project authorities shall advertise at least in two local newspapers widely circulated, one of which shall be in the vernacular language of the locality concerned, within 7 days of the issue of



the clearance letter informing that the project has been accorded environmental clearance and a copy of the clearance letter is available with the State Pollution Control Board and also at web site of the SEIAA at <http://www.seiaaup.in> and a copy of the same shall be forwarded to the Integrated Regional Office, MoEF&CC, GoI, Lucknow, CPCB, State PCB.

48. The MoEF&CC/SEIAA or any other competent authority may alter/modify the above conditions or stipulate any further condition in the interest of environment protection.
49. Concealing factual data or submission of false/fabricated data and failure to comply with any of the conditions mentioned above may result in withdrawal of this clearance and attract action under the provisions of Environment (Protection) Act, 1986.
50. Any appeal against this environmental clearance shall lie with the National Green Tribunal, if preferred, within a period of 30 days as prescribed under Section 11 of the National Environment Appellate Authority Act, 1997.
51. Waste water from potable use be collected and reused for sprinkling.
52. A width of not less than 50 meter or 10% width of river can be restricted for mining activities from river bank. A condition can be imposed that mining will be done from river activities from river bank.

**Annexure-4**

**General and Specific Conditions for Soil Earth Mining Projects:-**

**General condition:**

1. This environmental clearance does not create or verify any claim of applicant on the proposed site/activity.
2. Any mining activity shall be undertaken only after valid permission from Mining Department/District Administration and written agreement with land owner from where earth excavation is proposed.
3. No change in mining technology and scope of working shall be made without approval of Authority.
4. Personnel working in dusty areas shall be provided with protective respiratory devices and they shall also be imparted adequate training and information on safety and health aspects.
5. The Authority reserves the right to revoke the clearance if conditions stipulated are not implemented. The Authority will also be entitled to impose additional environmental conditions or modify the existing ones, if necessary.
6. In case of any deviation or alteration in the project proposed from those submitted to this Authority for clearance, a fresh reference should be made to the Authority to assess the adequacy of the condition(s) imposed and to add additional environmental protection Measures required, if any.
7. Concealing factual data or submission of false/fabricated data and failure to comply with any of the conditions mentioned above may result in withdrawal of this clearance and attract action under the provisions of Environment (Protection) Act, 1986.

**Specific Conditions:**

1. Environment management should be in accordance with the present environment status of the project.
2. The Environmental clearance will be co-terminus with the agreement/lease.
3. Approach kachcha road should be made motorable and maintained periodically.
4. Transportation of soil should be undertaken in covered containers.
5. Rehabilitation plan with planting of trees to be submitted along with the closure plan.
6. Land to be leveled and handed over to the owners after completion of excavation work.
7. A valid NOC from State Pollution Control Board shall be obtained for the Brick kiln prior to operation as per law and all guidelines must be followed, if applicable.
8. The mining operations shall be strictly limited to the proposed mining sites and proposed purpose.
9. Top soil should be adequately preserved and should be used for landscaping.
10. Excavated soil should be properly stored in a manner not to increase surrounding air pollution level.
11. Water sprinkling should be exercised during excavation and storage of soil for suppression of fugitive dust.
12. Excavated area should be properly reclaimed and ensured that no open bore hole is left.
13. Safety measures for the people working at the site shall be duly taken care of as per law.

14. The excavation work shall be done in day time only.
15. The project boundary shall be properly covered to restrict dust dispersion.
16. Precautionary measures during soil excavation for conservation and protection of rare and endangered flora and fauna found in the study area.
17. Noise level shall be maintained as per standards for both day and night.
18. The route map for soil transportation from excavation plots to work site should be firmed up and necessary permissions shall be sought from District Administration.
19. Vehicles hired for the transportation should be in good condition and should have Pollution Check Certificate and should conform to applicable air and noise emission standards.
20. Personnel exposure monitoring for respirable mineral dust shall be carried out for the workers and records maintained including health records of the workers. Awareness program for workers on impact of mining on their health and precautionary measures like use of personal protective equipments etc. shall be carried out periodically. First aid facilities and adequate sanitary facility in the form of temporary toilets/septic tanks.
21. Solid waste material viz gutkha rappers, plastic bags, glasses etc. to be generated during project activity will be separately stored in bins and managed as per Solid Waste Management Rules.
22. Project proponent should maintain daily register for information of (a) collection of soil/clay, (b) manpower & (c) transportation purpose.
23. Soil mining shall strictly be undertaken as per rules and regulations/permissions obtained from District Administration/Mining Department
24. Corporate Environmental Responsibility (CER) shall be prepared by the project proponent and the details of the various heads of expenditure to be submitted as per the guidelines provided in the recent CER notification No. 22-65/2017-IA.III dated 01/05/2018. A copy of resolution as above shall be submitted to the authority along with list of beneficiaries with their mobile nos./address.
25. The borrowing/excavation activity shall be restricted to a maximum depth of 2 m. below general ground level at the site.
26. The borrowing/excavation activity shall be restricted to 2 m. above the ground water table at the site.
27. The borrowing/excavation activity shall not alter the natural drainage pattern of the area.
28. The borrowed/excavated pit shall be restored by the project proponent for useful purpose(s).
29. Appropriate fencing all around the borrowed/excavated pit shall be made to prevent any mishap.
30. Measures shall be taken to prevent dust emission by covering of borrowed/excavated earth during transportation.
31. Safeguards shall be adopted against health risks on account of breeding of vectors in the water bodies created due to borrowing/excavation of earth.
32. Workers/labourers shall be provided with facilities for drinking water and sanitation.
33. A berm shall be left from the boundary of adjoining field having a width equal to at least half the depth of proposed excavation.
34. A minimum distance of 15 m from any civil structure shall be kept from the periphery of any excavation area.