

Minutes of 787th SEAC-2 Meeting Dated 18/09/2023

The 787th meeting of SEAC-2 was held in the Directorate of Environment, U.P. through dual-mode (physically/virtually) at 10:00 AM on 18/09/2023. Following members participated in the meeting:

- | | | |
|----|-----------------------------|-----------------------------|
| 1. | Dr. Harikesh Bahadur Singh, | Chairman, SEAC-2 |
| 2. | Dr. Amrit Lal Haldar, | Member, SEAC-2 |
| 3. | Shri Tanzar Ullah Khan, | Member, SEAC-2 |
| 4. | Prof. Jaswant Singh, | Member, SEAC-2 |
| 5. | Dr. Shiv Om Singh, | Member, SEAC-2 (through VC) |
| 6. | Shri Ashish Tiwari, | Member-Secretary, SEAC-2 |

The Chairman welcomed the members to the 787th SEAC-2 meeting which was conducted via dual-mode (virtually/physically). Nodal Officer, SEAC-2 informed the committee that the agenda has been approved by the Member Secretary, SEAC-2/Director, Environment. Nodal Officer, SEAC-2 placed the agenda items along with the available file and documents before the SEAC-2.

1. Building stone (Granite Khanda, Gitty, Boulder, Red Morrum) Sandstone Mining Project at Gata No-715, Khand No-5B, at Village - Gonda, Tehsil-Karwi, District-Chitrakoot, Shri Surendra Kumar Shukla, Area- 2.0240 ha., 8152/SIA/UP/MIN/441080/2023

The consultant informed the committee that they are strictly following the rules, regulations and other instructions of QCI/NABET. A presentation was made by the project proponent along with their consultant M/s Paramarsh Servicing Environment and development. Based on the documents submitted and presentation made by the project proponent along with the consultant, the following facts have emerged: -

1. The terms of reference is sought for Building stone (Granite Khanda, Gitty, Boulder, Red Morrum) Sandstone Mining Project at Gata No-715, Khand No-5 B, Village - Gonda, Tehsil-Karwi, District-Chitrakoot, U.P., (Leased Area- 2.0240 ha).
2. Salient features of the project as submitted by the project proponent:

1.	On-line proposal No.	SIA/UP/MIN/441080/2023
2.	File No. allotted by SEIAA, UP	8152
3.	Name of Proponent	Shri Surendra Kumar Shukla (Prop) S/o Shri Parmanand Shukla
4.	Full correspondence address of proponent and mobile no.	R/o H.No.307, Miyapur 5, District- Jaunpur- 222162, U.P. Mobile no. -9170957700 E mail ID - sssand2023@gmail.com
5.	Name of Project	Building stone (Granite Khanda, Gitty, Boulder, Red Morrum) Sandstone Mining Project in Gata No-715, Khand No-5B, Lease area 2.0240 ha at Village - Gonda, Tehsil-Karwi, District-Chitrakoot, U.P. of Shri Surendra Kumar Shukla.
6.	Project Location (Plot. Khasra/Gata No.)	Gata No-715, Khand No-5B
7.	Name of River	NA
8.	Name of Village	Village – Gonda
9.	Tehsil	Karwi
10.	District	Chitrakoot
11.	Name of Minor Mineral	Building stone (Granite Khanda, Gitty, Boulder, Red Morrum)
12.	Sanctioned Lease Area (in Ha.)	2.0240 ha
13.	Max. & Min mRL within lease area	Highest mRL-248.50 mRL Lowest mRL-216.10 mRL

14.	Pillar Coordinates (Verified by DMO)	Pillar	Latitude	Longitude
		Total Area 2.0240 ha		
		A	25°12 '26.307'N	80°44'51.666'E
		B	25°12'24.918'N	80°44'58.286'E
		C	25°12'20.460'N	80°44'57.270'E
		D	25°12'21.240'N	80°44' 53.880'E
		E	25°12'23.100'N	80°44'54.300'E
		F	25°12'23.520'N	80°44'51.300'E
15.	Total Geological Reserves	5,22,150 m ³		
16.	Total Mineable Reserve	3,79,416 m ³		
17.	Total Proposed Production	3,54,200 m ³ (5 years)		
18.	Proposed Production /year (as per LoI)	70,840 m ³		
19.	Sanctioned Period of Mine lease	Lease Period – 10 years Mine plan Period – 5 Years		
20.	Method of Mining	Opencast, Semi-mechanized		
21.	No. of worker	32		
22.	Type of Land	Govt./Non Forest Land		
23.	Depth of Mining	42.0 m		
24.	Nearest metallad road from site	0.40 km		
25.	Water Requirement	PURPOSE		
		Drinking	- 0.32 KLD	
		Suppression of dust	- 04.8 KLD	
		Plantation	- 2.0 KLD	
		Others (if any)	- 0.00 KLD	
		Total	- 7.12 KLD	
26.	Name of QCI Accredited Consultant with QCI No and period of validity.	Paramarsh Servicing Environment and development NABET/EIA/2124 RA 0224, Valid till –01 May 2024		
27.	Any litigation pending against the project or land in any court	No		
28.	Details of 500 m Cluster Certificate verified by Mining Officer	Letter No- 1784/Khanij/2023-24 Dated: 03/06/2023		
29.	Details of Lease Area in approved DSR	Table No.17, Serial no. 01, in village-Gonda, Page no. 29		
30.	Project Cost	97.0 Lacs		
31.	Proposed CER cost	1.94 Lacs		
32.	Length and breadth of Haul Road	Length – 0.40 km, Breadth – 6.00 m		
33.	No. of Trees to be Planted	2000		

- The mining would be restricted to unsaturated zone only above the phreatic water table and will not intersect the ground water table at any point of time.
- This project does not attract any of the general conditions applicable on mining projects specified in EIA Notification 14/09/2006.
- The mining operation will not be carried out in safety zone of any bridge or embankment or in eco-fragile zone such as habitat of any wild fauna.
- There is no litigation pending in any court regarding this project.
- The project proposal falls under category–1(a) of EIA Notification, 2006 (as amended).

The consultant (EIA Coordinator) also submitted an affidavit dated 12/09/2023 mentioning is as follows:

- I Pankaj Srivastava S/o Shri V. V. Srivastava is EIA Coordinator of Paramarsh servicing Environment and Development.
- I have prepared ToR application along with Form 1, Pre-feasibility Report for the Proposed Building stone (Granite Khanda, Gitty, Boulder, Red Morrum) Sandstone Mining Project in Gata No-715, Khand No-5B, Lease area 2.0240 ha at Village - Gonda, Tehsil-Karwi, District-Chitrakoot, U.P. of Shri Surendra Kumar Shukla, Proposal number: SIA/UP/MIN/441080/2023 with my team.

3. I have personally visited the site of proposal and certify that no mining activity has been undertaken on the project site for the present proposal.
4. I am satisfied with that all the necessary data/information required for ToR application along with Form 1, Pre-feasibility Report preparations are true and correct.
5. I certify that this project has been uploaded for the first time on Parivesh Portal.
6. I certify that there is no mismatch between information/data provided on online application and hard copy/presentation submitted.
7. The ToR application along with Form 1, Pre-feasibility Report for the Proposal is prepared by my team as per guidelines laid down by QCI/NABET.

RESOLUTION AGAINST AGENDA NO. 01

The committee discussed the matter and recommended to issue the standard terms of reference for the preparation of EIA as annexed at annexure-1 to the minutes. The committee also stipulated following additional TOR Points:

Additional TOR:

1. To ensure proper monitoring, the project proponent/consultant should provide evidence in form of (A) Raw Data (B) Logbook of their site visit along with activities carried out during monitoring (C) Real time photographs showing monitoring machine, public, lab person etc. Proprietor/proprietor representative should be present at the time of monitoring and monitoring should be conducted as per CPCB SOP/NABET/QCI guidelines. Lab responsible person should be present at the time of EIA presentation.
2. EIA coordinator & FAE should give a notarized affidavit during EIA presentation that they have personally visited the site & they have also taken all the mitigating measures for any critical issues involved in the project.
3. The project proponent will have to inform the schedule of monitoring/data collection programme to the SEIAA/SEAC, UP before start of data collection. In case of failure, the collected baseline monitoring data will be treated as null and void.
4. The details of equipment used for baseline monitoring alongwith its photograph mentioning date, time and geo coordinates for preparation of EIA report should be clearly displayed to the people present during public hearing and the complete details related to monitoring period must be mentioned in the minutes of public hearing.
5. Original lab analysis report of the project proposal along with EIA report should be uploaded on Parivesh Portal.
6. Combined KML of all mines in a cluster should be submitted at the time of EIA.
7. The project proponent/Consultant should identify the core & buffer zone (2.5 km) of the mining site.
8. Agreement/ Consent between project proponent and competent authority/ landowner for haulage road from lease site to link road to be submitted at the time of EIA presentation.
9. Proponent/Consultant should submit the plan/information along with technology (photographs of water sprinklers/ tankers) to be implemented for mitigating dust at source points in lease area and haulage road during operation activity/vehicular movement. Technology should be displayed at the time of EIA presentation.
10. Proposed plantation plan with area specific plant species, number of plants to be planted and place of plantation along with a proper map to be submitted at the time of EIA presentation.
11. Water requirement details along with source of water and the permission/ agreement with the concerning authority/ person to be submitted at the time of EIA presentation.

12. Proponent/consultant shall present TOR specific/additional conditions compliance, observation/suggestions raised during the public hearing and commitment made by the project proponent in a tabular form with a time bound plan at the time of EIA presentation.
13. Corporate Social Responsibility (CSR) to be prepared as per the MoEF guidelines and present it at the time of EIA presentation.

2. “Imarati Patthar (Sandstone)” Mine at Gata No.- 36/6/5, Village- Sonbarsa, Tehsil- Lalganj, District- Mirzapur, Shri Imaran Ahamad, Area- 0.809 Ha., 8154/SIA/UP/MIN/441426/2023

The consultant informed the committee that they are strictly following the rules, regulations and other instructions of QCI/NABET. A presentation was made by the project proponent along with their consultant M/s AWS Envirotech (OPC) Pvt. Ltd. Based on the documents submitted and presentation made by the project proponent along with the consultant, the following facts have emerged: -

1. The terms of reference is sought for “Imarati Patthar (Sandstone)” Mine at Araji/Gata no.- 36/6/5, Village- Sonbarsa, Tehsil- Lalganj, District- Mirzapur, State- Uttar Pradesh, (Leased Area- 0.809 ha.).
2. Salient features of the project as submitted by the project proponent:

1.	On-line proposal No.	SIA/UP/MIN/441426/2023															
2.	File No. allotted by SEIAA, UP	8154															
3.	Name of Proponent	Shri Imaran Ahamad															
4.	Full correspondence address of proponent and E-mail Id	Shri Imaran Ahamad S/o Shri Jamil Ahamad R/o- 258, Vindhyanchal, Akorhi, District- Mirzapur, Uttar Pradesh-231307 Email: aimaran589@gmail.com															
5.	Name of Project	“Imarati Patthar (Sandstone)” Mine at Araji/Gata no.- 36/6/5, Village- Sonbarsa, Tehsil- Lalganj, District- Mirzapur, State- Uttar Pradesh															
6.	Project Location (Plot.Khasra/Gata No.)	Gata No.-36/6/5, Village- Sonbarsa, Tehsil- Lalganj, District- Mirzapur, State- Uttar Pradesh.															
7.	Name of River	NA															
8.	Name of Village	Sonbarsa															
9.	Tehsil	Lalganj															
10.	District	Mirzapur															
11.	Name of Minor Mineral	Imarati Patthar (Sandstone)															
12.	Sanctioned Lease Area (in Ha.)	0.809 ha.															
13.	Max. & Min mRL within lease area	Highest mRL is 113.50 & Lowest is 110.50 mRL															
14.	Pillar Coordinates (Verified by DMO)	GPS Co-ordinates are- <table border="1"> <thead> <tr> <th>Pillars</th><th>N</th><th>E</th></tr> </thead> <tbody> <tr> <td>A</td><td>25°05'21.73"N</td><td>82°24'24.85"E</td></tr> <tr> <td>B</td><td>25°05'20.57"N</td><td>82°24'27.71"E</td></tr> <tr> <td>C</td><td>25°05'17.35"N</td><td>82°24'25.96"E</td></tr> <tr> <td>D</td><td>25°05'18.33"N</td><td>82°24'23.00"E</td></tr> </tbody> </table>	Pillars	N	E	A	25°05'21.73"N	82°24'24.85"E	B	25°05'20.57"N	82°24'27.71"E	C	25°05'17.35"N	82°24'25.96"E	D	25°05'18.33"N	82°24'23.00"E
Pillars	N	E															
A	25°05'21.73"N	82°24'24.85"E															
B	25°05'20.57"N	82°24'27.71"E															
C	25°05'17.35"N	82°24'25.96"E															
D	25°05'18.33"N	82°24'23.00"E															
15.	Total Geological Reserves	3,87,222 m ³															
16.	Total Mineable Reserve (as per Approved Mine Plan)	1,23,084 m ³															
17.	Total Proposed Production	80,900 m ³ (in 5 Years of approved mine plan period)															
18.	Proposed Production	16,180 m ³ /year															
19.	Sanctioned Period of Mine lease	20 years (maximum)															
20.	Method of Mining	Opencast, Semi-Mechanized															
21.	Working hours/day	8															
22.	No. of worker	52															
23.	Type of Land	Govt. revenue land															
24.	Ultimate of Depth of Mining	Upto 80 mRL															

25.	Nearest metalled road from site	200 m
26.	Water Requirement	PURPOSE
		Drinking
		Suppression of dust
		Plantation
		Total
27.	Name of QCI Accredited Consultant with QCI No and period of validity.	AWS Envirotech (OPC) Pvt. Ltd. Certificate no. NABET/EIA/2225/IA 0097(Rev.01) Valid Till July 14, 2025
28.	Any litigation pending against the project or land in any court	No
29.	Details of 500 m Cluster Certificate verified by Mining Officer	vide letter no. 5156/M.M.C.-30/2022-23 Dated on 11.07.2023
30.	Details of Lease Area in approved DSR	In approved DSR at page no. 22, Sl no. 05 DSR Corrigendum letter No. 5218/khanij/DSR/2023-24 dated on 19/07/2023
31.	Baseline data collection period	October to December 2023
32.	Proposed CER cost	Rs. 1.76 Lakhs
33.	EMP cost	EMP cost is Rs. 8.5 lakhs as capital cost and Rs. 5.5 lakhs as recurring cost
34.	Distance of Haul Road	200 m
35.	No. of Trees to be Planted	250

- The mining would be restricted to unsaturated zone only above the phreatic water table and will not intersect the ground water table at any point of time.
- This project does not attract any of the general conditions applicable on mining projects specified in EIA Notification 14/09/2006.
- The mining operation will not be carried out in safety zone of any bridge or embankment or in eco-fragile zone such as habitat of any wild fauna.
- There is no litigation pending in any court regarding this project.
- The project proposal falls under category-1(a) of EIA Notification, 2006 (as amended).

The consultant (EIA Coordinator) also submitted an affidavit dated 23/08/2023 mentioning is as follows:

- I, Sandeep Kumar, S/o Shri R.K. Verma is EIA Coordinator of M/s AWS Envirotech (OPC) Pvt. Ltd.
- I have prepared the TOR application report for the proposal “Imarati Patthar (Sandstone)” Mine at Araji/Gata no.- 36/6/5, Village- Sonbarsa, Tehsil- Lalganj, District- Mirzapur, State- Uttar Pradesh, (Leased Area- 0.809 ha.) with my team.
- I have personally visited the site of proposal and certify that no Mining activity has been undertaken on the project site for the present proposal.
- I am satisfied that all the necessary data/ information submitted along with TOR application are true and correct.
- I certify that this project proposal has been uploaded for the first time on PARIVESH Portal.
- I certify that there will be no mismatch between information/data provided on the online application submitted on PARIVESH Portal and the hard copy/presentation which will be submitted after acceptance of application.
- The TOR Report for the Proposal is prepared by my team as per guidelines laid down by QCI/NABET.

RESOLUTION AGAINST AGENDA NO. 02

The committee discussed the matter and recommended to issue the standard terms of reference for the preparation of EIA as annexed at annexure-1 to the minutes. The committee also stipulated following additional TOR Points:

Additional TOR:

1. To ensure proper monitoring, the project proponent/consultant should provide evidence in form of (A) Raw Data (B) Logbook of their site visit along with activities carried out during monitoring (C) Real time photographs showing monitoring machine, public, lab person etc. Proprietor/proprietor representative should be present at the time of monitoring and monitoring should be conducted as per CPCB SOP/NABET/QCI guidelines. Lab responsible person should be present at the time of EIA presentation.
2. EIA coordinator & FAE should give a notarized affidavit during EIA presentation that they have personally visited the site & they have also taken all the mitigating measures for any critical issues involved in the project.
3. The project proponent will have to inform the schedule of monitoring/data collection programme to the SEIAA/SEAC, UP before start of data collection. In case of failure, the collected baseline monitoring data will be treated as null and void.
4. The details of equipment used for baseline monitoring alongwith its photograph mentioning date, time and geo coordinates for preparation of EIA report should be clearly displayed to the people present during public hearing and the complete details related to monitoring period must be mentioned in the minutes of public hearing.
5. Original lab analysis report of the project proposal along with EIA report should be uploaded on Parivesh Portal.
6. Combined KML of all mines in a cluster should be submitted at the time of EIA.
7. The project proponent/Consultant should identify the core & buffer zone (2.5 km) of the mining site.
8. Agreement/ Consent between project proponent and competent authority/ landowner for haulage road from lease site to link road to be submitted at the time of EIA presentation.
9. Proponent/Consultant should submit the plan/information along with technology (photographs of water sprinklers/ tankers) to be implemented for mitigating dust at source points in lease area and haulage road during operation activity/vehicular movement. Technology should be displayed at the time of EIA presentation.
10. Proposed plantation plan with area specific plant species, number of plants to be planted and place of plantation along with a proper map to be submitted at the time of EIA presentation.
11. Water requirement details along with source of water and the permission/ agreement with the concerning authority/ person to be submitted at the time of EIA presentation.
12. Proponent/consultant shall present TOR specific/additional conditions compliance, observation/suggestions raised during the public hearing and commitment made by the project proponent in a tabular form with a time bound plan at the time of EIA presentation.
13. Corporate Social Responsibility (CSR) to be prepared as per the MoEF guidelines and present it at the time of EIA presentation.

3. Sand/Morrum Mining Riverbed Betwa at Khand No.- 25/24 at Village –Ichhaura-Jitkari, Tehsil- Sarila, District- Hamirpur, Shri Harpal Singh, M/s Parmar Brothers, Area- 33.00 ha., 8156/SIA/UP/MIN/441440/2023

The consultant informed the committee that they are strictly following the rules, regulations and other instructions of QCI/NABET. A presentation was made by the project proponent along with their consultant M/s Paramarsh Servicing Environment and development. Based on the documents submitted and presentation made by the project proponent along with the consultant, the following facts have emerged: -

1. The terms of reference is sought for Sand/Morrum Mining Riverbed Betwa at Khand No.- 25/24 at Village –Ichhaura-Jitkari, Tehsil- Sarila, District- Hamirpur, U.P., (Leased Area- 33.00 ha.), M/s Parmar Brothers.

2. Salient features of the project as submitted by the project proponent:

1.	On-line proposal No.	SIA/UP/MIN/441440/2023		
2.	File No. allotted by SEIAA, UP	8156		
3.	Name of Proponent	M/s Parmar Brothers Prop: Shri Harpal Singh S/o: Sri Bahadur Singh		
4.	Full correspondence address of proponent and mobile no.	R/o: 206, Katra Gursarai, Tehsil – Garautha, Jhansi - 284202 U.P.		
		Mobile no.- 7380307384		
		E mail ID - singhharpalsand@gmail.com		
5.	Name of Project	Environment Clearance of proposed riverbed sand/morrum mining having lease area 33.00 ha along river Betwa in Khand No. 25/24 at Village –Ichhaura-Jitkari, Tehsil- Sarila, District- Hamirpur, Uttar Pradesh of M/s Parmar Brothers.		
6.	Project Location (Plot. Khasra/Gata No.)	Khand No. 25/24		
7.	Name of River	Betwa river		
8.	Name of Village	Ichhaura-Jitkari		
9.	Tehsil	Sarila		
10.	District	Hamirpur		
11.	Name of Minor Mineral	“River bed Sand/morrum mining”		
12.	Sanctioned Lease Area (in Ha.)	33.00 ha		
13.	Max. & Min mRL within lease area	The Highest level is 1130.2 mRL The Lowest level is 123.6 mRL		
14.	Pillar Coordinates (Verified by DMO)	Total Area-33.0 ha		
		Sr. no.	Latitude	Longitude
		A	25°53'04.30"N	79°33'28.20"E
		B	25°53'12.75"N	79°33' 06.77"E
		C	25°53'15.69"N	79°32'57.32"E
		D	25°53' 26.13"N	79°33' 01.92"E
		E	25°53' 21.07"N	79°33' 11.75"E
		F	25°53'18.13"N	79°33' 34.29"E
		Submerged Area – 8.34 ha		
		A	25°53'04.30"N	79°33'28.20"E
		B	25°53'12.75"N	79°33' 06.77"E
		C	25°53'15.69"N	79°32'57.32"E
		S1	25°53'21.69"N	79°33'00.03"E
		S2	25°53'19.66"N	79°33'11.64"E
		S3	25°53'13.30"N	79°33'32.03"E
		15.	Total Geological Reserves	7,26,429 m ³
16.	Total Mineable Reserve	5,27,988 m ³		
17.	Total Proposed Production	26,39,670 m ³ (5 years)		
18.	Proposed Production /year (as per LoI)	5,27,934 m ³ /annum		
19.	Sanctioned Period of Mine lease	Lease Period 5 years		
20.	Method of Mining	Opencast semi - mechanized		
21.	No. of worker	55		
22.	Type of Land	Govt./Non Forest Land		
23.	Ultimate Depth of Mining	3.0 m		
24.	Nearest metalled road from site	0.70 km		
25.	Water Requirement	PURPOSE		
		Drinking	- 0.55 KLD	
		Suppression of dust	- 8.40 KLD	
		Plantation	- 3.30 KLD	
		Others (if any)	- 0.00 KLD	
		Total	- 12.25KLD	
26.	Name of QCI Accredited Consultant with QCI No and period of validity.	Paramarsh Servicing Environment and development NABET/EIA/2124 RA 0224, Valid till –01 May 2024		
27.	Any litigation pending against the project or land in any court	No		
28.	Details of 500 m Cluster Certificate verified	Letter No-136/Khanij-MMC-30-Vividh(2022-23),dated-		

	by Mining Officer	06/05/2023
29.	Details of Lease Area in approved DSR	Letter No 557/Khanij- MMC-30-Vividh (2023-24) dt. 04/07/2023, at Page No.66, Serial no. 43
30.	Project Cost	1.20 Crore
31.	Proposed CER cost	2.40 lacs
32.	Length and breadth of Haul Road	Length – 0.70 km, Breadth – 6.00 m
33.	No. of Trees to be Planted	3,300

3. The mining would be restricted to unsaturated zone only above the phreatic water table and will not intersect the ground water table at any point of time.
4. This project does not attract any of the general conditions applicable on mining projects specified in EIA Notification 14/09/2006.
5. The mining operation will not be carried out in safety zone of any bridge or embankment or in eco-fragile zone such as habitat of any wild fauna.
6. There is no litigation pending in any court regarding this project.
7. The project proposal falls under category–1(a) of EIA Notification, 2006 (as amended).

The consultant (EIA Coordinator) also submitted an affidavit dated 12/09/2023 mentioning is as follows:

1. I Dr. Abdul Rahman S/o Shri Mohammed Khalid is EIA Coordinator of Paramarsh servicing Environment and Development.
2. I have prepared ToR Application for the Environment Clearance of proposed riverbed sand/morrum mining having lease area 33.00 ha along river Betwa in Khand No. 25/24 at Village –Ichhaura-Jitkari, Tehsil- Sarila, District- Hamirpur, Uttar Pradesh of M/s Parmar Brothers.
3. Prop: Shri Harpal Singh. Proposal number: SIA/UP/MIN/441440/2023 with my team.
4. I have personally visited the site of proposal and certify that no Mining activity has been undertaken on the project site for the present proposal.
5. I am satisfied with that all the necessary data/information required for ToR Application preparations are true and correct.
6. I certify that this project has been uploaded for the first time on Parivesh Portal.
7. I certify that there is no mismatch between information/data provided on online application and hard copy/presentation submitted.
8. The ToR Application for the Proposal is prepared by my team as per guidelines laid down by QCI/NABET.

RESOLUTION AGAINST AGENDA NO. 03

The committee discussed the matter and recommended to issue the standard terms of reference for the preparation of EIA as annexed at annexure-1 to the minutes. The committee also stipulated following additional TOR Points:

Additional TOR:

1. Project proponent should present latest drone videography (not older than 07 days) of the project site mentioning the date, time and geo coordinates at the time of EIA presentation.
2. NOC from Irrigation Department/Concerning Authority regarding river bed mining to be submitted at the time of EIA presentation.
3. To ensure proper monitoring, the project proponent/consultant should provide evidence in form of (A) Raw Data (B) Logbook of their site visit along with activities carried out during monitoring (C) Real time photographs showing monitoring machine, public, lab person etc. Proprietor/proprietor representative should be present at the time of monitoring and monitoring should be conducted as per CPCB SOP/NABET/QCI guidelines. Lab responsible person should be present at the time of EIA presentation.

4. EIA coordinator & FAE should give a notarized affidavit during EIA presentation that they have personally visited the site & they have also taken all the mitigating measures for any critical issues involved in the project.
5. The project proponent will have to inform the schedule of monitoring/data collection programme to the SEIAA/SEAC, UP before start of data collection. In case of failure, the collected baseline monitoring data will be treated as null and void.
6. The details of equipment used for baseline monitoring alongwith its photograph mentioning date, time and geo coordinates for preparation of EIA report should be clearly displayed to the people present during public hearing and the complete details related to monitoring period must be mentioned in the minutes of public hearing.
7. Original lab analysis report of the project proposal along with EIA report should be uploaded on Parivesh Portal.
8. Combined KML of all mines in a cluster should be submitted at the time of EIA.
9. The project proponent/Consultant should identify the core & buffer zone (2.5 km) of the mining site.
10. Agreement/ Consent between project proponent and competent authority/ landowner for haulage road from lease site to link road to be submitted at the time of EIA presentation.
11. Proponent/ Consultant should submit the plan/information along with technology (photographs of water sprinklers/ tankers) to be implemented for mitigating dust at source points in lease area and haulage road during operation activity/vehicular movement. Technology should be displayed at the time of EIA presentation.
12. Proposed plantation plan with area specific plant species, number of plants to be planted and place of plantation along with a proper map to be submitted at the time of EIA presentation.
13. Water requirement details along with source of water and the permission/ agreement with the concerning authority/ person to be submitted at the time of EIA presentation.
14. Proponent/consultant shall present TOR specific/additional conditions compliance, observation/suggestions raised during the public hearing and commitment made by the project proponent in a tabular form with a time bound plan at the time of EIA presentation.
15. Corporate Social Responsibility (CSR) to be prepared as per the MoEF guidelines and present it at the time of EIA presentation.
16. Submit the hydrological study report of lease area that the quantity given in LoI will be mined without affecting the geo-hydrology of the River.

4. Building Stone (Khanda, Gitti, Boulder) Sand Stone Mine, Araj number-669mi, Khand No.-39, Village –Khailar, Tehsil –Sadar, District-Jhansi, Shri Shusil Kumar Gupta, M/s Sushil Stone Gramodyog, Area- 4.046 ha., 8158/SIA/UP/MIN/441518/2023

The consultant informed the committee that they are strictly following the rules, regulations and other instructions of QCI/NABET. A presentation was made by the project proponent along with their consultant M/s Paramarsh Servicing Environment and development. Based on the documents submitted and presentation made by the project proponent along with the consultant, the following facts have emerged: -

1. The terms of reference is sought for Building Stone (Khanda, Gitti, Boulder) Sand Stone Mine, Araj number- 669mi, Khand No.-39, Village –Khailar, Tehsil –Sadar, District-Jhansi, Uttar Pradesh, (Leased Area- 4.046 ha.), M/s Sushil Stone Gramodyog.
2. Salient features of the project as submitted by the project proponent:

1.	On-line proposal No.	SIA/UP/MIN/441518/2023
2.	File No. allotted by SEIAA, UP	8158
3.	Name of Proponent	M/s Sushil Stone Gramodyog Prop: Shri Sushil Kumar Gupta S/o Late Gendan Lal Gupta
4.	Full correspondence address of proponent and mobile no.	R/o-P-5, Ansal Palm court, Medical Collage, Thana-Nawabad, Tehsil & District – Jhansi, U. P.-284128. Mobile no. – 9140157272 E mail ID - sushilstone2022@gmail.com

Minutes of 787th SEAC-2 Meeting Dated 18/09/2023

5.	Name of Project	Building Stone (Khanda, Gitti, Boulder) Sand Stone Mine, Araj number-669mi, Khand No.39, Area- 4.046 ha Village –Khailar, Tehsil –Sadar, District-Jhansi, Uttar Pradesh of M/s Sushil Stone Gramodyog.			
6.	Project Location (Plot. Khasra/Gata No.)	Araj number-669mi, Khand No.39			
7.	Name of River	NA			
8.	Name of Village	Khailar			
9.	Tehsil	Sadar			
10.	District	Jhansi			
11.	Name of Minor Mineral	Building Stone (Khanda, Gitti, Boulder) Sand Stone Mine			
12.	Sanctioned Lease Area (in Ha.)	4.046 ha			
13.	Max. & Min mRL within lease area	Highest mRL - 342.70 mRL Lowest mRL - 295.70 mRL			
14.	Pillar Coordinates (Verified by DMO)	Pillar	Latitude	Longitude	
		Total Area 4.046 ha			
		A	25°20' 44.73"N	78° 31' 29.24"E	
		B	25°20' 36.76"N	78° 31' 28.74"E	
		C	25°20' 37.03"N	78° 31' 22.88"E	
		D	25°20' 44.88"N	78° 31' 23.42"E	
15.	Total Geological Reserves	31,99,285 m ³			
16.	Total Mineable Reserve	17,06,367 m ³			
17.	Total Proposed Production	5,05,750 m ³ (5 years)			
18.	Proposed Production /year (as per Lol)	1,01,150 m ³ per annum			
19.	Sanctioned Period of Mine lease	Plan Period 5 years			
20.	Method of Mining	Opencast semi- mechanized method			
21.	No. of worker	54			
22.	Type of Land	Govt./Non Forest Land			
23.	Depth of Mining	36.0 m (plan period)			
24.	Nearest metalled road from site	0.30 km			
25.	Water Requirement	PURPOSE			
		Drinking	- 0.54 KLD		
		Suppression of dust	- 3.60 KLD		
		Plantation	- 4.00 KLD		
		Others (if any)	- 0.00 KLD		
		Total	- 8.14 KLD		
26.	Name of QCI Accredited Consultant with QCI No and period of validity.	Paramarsh Servicing Environment and development NABET/EIA/2124 RA 0224, Valid till –01 May 2024			
27.	Any litigation pending against the project or land in any court	No			
28.	Details of 500 m Cluster Certificate verified by Mining Officer	Letter No – 1840/30 MMC/(2022-23), dated 23/03/2023			
29.	Details of Lease Area in approved DSR	Serial no. 38, in village - Khailar, Page no. 04			
30.	Project Cost	70.0 Lacs			
31.	Proposed CER cost	1.40 Lacs			
32.	Length and breadth of Haul Road	Length – 0.30 km, Breadth – 6.00 m			
33.	No. of Trees to be Planted	4,000			

- The mining would be restricted to unsaturated zone only above the phreatic water table and will not intersect the ground water table at any point of time.
- This project does not attract any of the general conditions applicable on mining projects specified in EIA Notification 14/09/2006.
- The mining operation will not be carried out in safety zone of any bridge or embankment or in eco-fragile zone such as habitat of any wild fauna.
- There is no litigation pending in any court regarding this project.
- The project proposal falls under category–1(a) of EIA Notification, 2006 (as amended).

The consultant (EIA Coordinator) also submitted an affidavit dated 12/09/2023 mentioning is as follows:

1. I Dr. Abdul Rahman S/o Shri Mohammed Khalid is EIA Coordinator of Paramarsh servicing Environment and Development.
2. I have prepared ToR application along with Form 1, Pre-feasibility Report for the Proposed Building Stone (Khanda, Gitti, Boulder) Sand Stone Mine, Araj number-669mi, Khand No.39, Area- 4.046 ha Village –Khailar, Tehsil –Sadar, District-Jhansi, Uttar Pradesh of M/s Sushil Stone Gramodyog, Prop: Sushil Kumar Gupta Proposal number: SIA/UP/MIN/441518/2023 with my team.
3. I have personally visited the site of proposal and certify that no mining activity has been undertaken on the project site for the present proposal.
4. I am satisfied with that all the necessary data/information required for ToR application along with Form 1, Pre-feasibility Report preparations are true and correct.
5. I certify that this project has been uploaded for the first time on Parivesh Portal.
6. I certify that there is no mismatch between information/data provided on online application and hard copy/presentation submitted.
7. The ToR application along with Form 1, Pre-feasibility Report for the Proposal is prepared by my team as per guidelines laid down by QCI/NABET.

RESOLUTION AGAINST AGENDA NO. 04

The committee discussed the matter and recommended to issue the standard terms of reference for the preparation of EIA as annexed at annexure-1 to the minutes. The committee also stipulated following additional TOR Points:

Additional TOR:

1. To ensure proper monitoring, the project proponent/consultant should provide evidence in form of (A) Raw Data (B) Logbook of their site visit along with activities carried out during monitoring (C) Real time photographs showing monitoring machine, public, lab person etc. Proprietor/proprietor representative should be present at the time of monitoring and monitoring should be conducted as per CPCB SOP/NABET/QCI guidelines. Lab responsible person should be present at the time of EIA presentation.
2. EIA coordinator & FAE should give a notarized affidavit during EIA presentation that they have personally visited the site & they have also taken all the mitigating measures for any critical issues involved in the project.
3. The project proponent will have to inform the schedule of monitoring/data collection programme to the SEIAA/SEAC, UP before start of data collection. In case of failure, the collected baseline monitoring data will be treated as null and void.
4. The details of equipment used for baseline monitoring alongwith its photograph mentioning date, time and geo coordinates for preparation of EIA report should be clearly displayed to the people present during public hearing and the complete details related to monitoring period must be mentioned in the minutes of public hearing.
5. Original lab analysis report of the project proposal along with EIA report should be uploaded on Parivesh Portal.
6. Combined KML of all mines in a cluster should be submitted at the time of EIA.
7. The project proponent/Consultant should identify the core & buffer zone (2.5 km) of the mining site.
8. Agreement/ Consent between project proponent and competent authority/ landowner for haulage road from lease site to link road to be submitted at the time of EIA presentation.

9. Proponent/Consultant should submit the plan/information along with technology (photographs of water sprinklers/ tankers) to be implemented for mitigating dust at source points in lease area and haulage road during operation activity/vehicular movement. Technology should be displayed at the time of EIA presentation.
10. Proposed plantation plan with area specific plant species, number of plants to be planted and place of plantation along with a proper map to be submitted at the time of EIA presentation.
11. Water requirement details along with source of water and the permission/ agreement with the concerning authority/ person to be submitted at the time of EIA presentation.
12. Proponent/consultant shall present TOR specific/additional conditions compliance, observation/suggestions raised during the public hearing and commitment made by the project proponent in a tabular form with a time bound plan at the time of EIA presentation.
13. Corporate Social Responsibility (CSR) to be prepared as per the MoEF guidelines and present it at the time of EIA presentation.

5. Sand/Morrum mining having along river Betwa in khand No.- 10/6 at Village – Beri, Tehsil- Hamirpur, District- Hamirpur, Shri Kanwar Pal Singh, M/s Kanwar Enterprises Private Limited, Area- 36.437 ha., 8160/4479/SIA/UP/MIN/29073/2018

A presentation was made by the project proponent along with their consultant M/s Paramarsh Servicing Environment and Development. The project proponent/consultant submitted the following chronology of the project:

“The project for river sand/morrum mining at Village Beri, Tehsil- Hamirpur, District- Hamirpur, U.P. of M/s Kanwar Enterprises Private Limited. An e-tender was floated for the project and letter of intent was issued to the project proponent on 7th June 2018. Subsequently, the mine plan approval letter was issued on 24th September, 2018. The SEAC issued the terms of reference on 12th December, 2018. The Public hearing was conducted on 6th March, 2019 and Final Environmental Impact Assessment (EIA) report was submitted on 30th May, 2019. It is apposite to mention that as per MoEFCC, OM dated 08th June 2022, at point no. 6 (iii), it has been categorically mentioned that “The baseline data and public hearing shall not be more than three years old at the time of submission of application for consideration of EC”.

The project was scheduled for presentation in the 411th SEAC meeting held on 12th July 2019. However, we had already intimated the authorities on 8th July 2019, that 50 percent of the lease area was submerged under water. SEAC requested factual reports from the DGM and the District Magistrate (DM) of Hamirpur through letters dated 13th September 2019 and 24th January 2020, respectively.

Unfortunately, the report sent by mining department Hamirpur on 04th February 2020, did not adequately reflect the extent of the submerged and dry areas within the lease area. In light of this, we arranged for a site inspection to be conducted by experts from the Academic of Science Communication. Their report confirmed that 16.17 hectares were submerged, while only 10.8 hectares remained dry and mineable. However, the mining department, Hamirpur did not agree with the report of Academic of Science Communication; therefore, the project proponent sought the new factual report from the district mining department, Hamirpur.

It is significant to mention here that on the basis of several correspondence in this matter i.e. SEIAA letter 170/parya/samanya/2020 dt. 4th August 2022, request letter of project proponent dated 18th June and some other letter dated 21st September 2022 on the same issue, a joint committee comprising of SDM Hamirpur, mine inspector Hamirpur and surveyor Hamirpur was appointed to

probe into the matter. After conducting an inspection of the lease area, they submitted the final factual report on 25th June 2023. This report estimates the quantity of sand to be 5,89,791 cubic meters. Therefore, the project proponent applying for Environment Clearance based on proposed production capacity of 5,82,912 cubic meters as mentioned in the letter of intent dated 07th June 2018.”

Based on the documents submitted and presentation made by the project proponent along with the consultant, the following facts have emerged: -

1. The environmental clearance is sought for Sand/Morrum mining having along river Betwa in khand No.- 10/6 at Village – Beri, Tehsil- Hamirpur, District- Hamirpur, Shri Kanwar Pal Singh, M/s Kanwar Enterprises Private Limited, (Leased Area- 36.437 ha.).
2. The Terms of Reference in the matter were issued by SEIAA, U.P vide Letter No. 572/Parya/SEAC/4479/2017 dated 12 December, 2018.
3. The Public Hearing was organized on 06/03/2019. Final EIA report submitted by the project proponent on 28/05/2019.
4. Salient features of the project as submitted by the project proponent:

1.	On-line proposal No.	Proposal No. SIA/UP/MIN/29073/2018																														
2.	File No. allotted by SEIAA, UP	8160-4479																														
3.	Name of Proponent	M/s Kanwar Enterprises Private Limited Kanwar Pal Singh S/o Sri Harbhajan Singh R/o: D-19, Sector -40, Noida, District – Gautam Buddha Nagar, Uttar Pradesh – 201301																														
4.	Full correspondence address of proponent and mobile no.	R/o: D-19, Sector -40, Noida, District – Gautam Buddha Nagar, Uttar Pradesh – 201301 Mobile no. – E mail ID - keplberi@gmail.com																														
5.	Name of Project	Environmental clearance for proposed river bed sand/morrum mining having lease area 36.437 ha along river Betwa in khand No. 10/6 at Village – Beri, Tehsil- Hamirpur, District- Hamirpur, U. P. of M/s Kanwar Enterprises Private Limited.																														
6.	Project Location (Plot. Khasra/Gata No.)	khand No. 10/6																														
7.	Name of River	Betwa																														
8.	Name of Village	Beri																														
9.	Tehsil	Hamirpur																														
10.	District	Hamirpur																														
11.	Name of Minor Mineral	“River bed Sand/morrum mining”																														
12.	Sanctioned Lease Area (in Ha.)	36.437 ha																														
13.	Max. & Min mRL within lease area	Highest mRL is 102.7* near boundary pillar “A” in east Lowest mRL is 94.9* near boundary pillar “D”																														
14.	Pillar Coordinates (Verified by DMO)	<table border="1"> <thead> <tr> <th>Pillar No.</th><th>Latitude</th><th>Longitude</th></tr> </thead> <tbody> <tr> <td>A</td><td>25°52'37.11"N</td><td>79° 55'1.59"E</td></tr> <tr> <td>B</td><td>25°52'39.48"N</td><td>79° 55'29.22"E</td></tr> <tr> <td>C</td><td>25°52'27.04"N</td><td>79° 55'33.78"E</td></tr> <tr> <td>D</td><td>25°52'18.53"N</td><td>79° 55'0.08"E</td></tr> <tr> <td colspan="3">Submerge Area</td></tr> <tr> <td>S1</td><td>25°52'22.82"N</td><td>79° 55'0.62"E</td></tr> <tr> <td>S2</td><td>25°52'34.81"N</td><td>79° 55'30.76"E</td></tr> <tr> <td>S3</td><td>25°52'28.99"N</td><td>79° 55'33.00"E</td></tr> <tr> <td>S4</td><td>25°52'19.76"N</td><td>79° 55'0.28"E</td></tr> </tbody> </table>	Pillar No.	Latitude	Longitude	A	25°52'37.11"N	79° 55'1.59"E	B	25°52'39.48"N	79° 55'29.22"E	C	25°52'27.04"N	79° 55'33.78"E	D	25°52'18.53"N	79° 55'0.08"E	Submerge Area			S1	25°52'22.82"N	79° 55'0.62"E	S2	25°52'34.81"N	79° 55'30.76"E	S3	25°52'28.99"N	79° 55'33.00"E	S4	25°52'19.76"N	79° 55'0.28"E
Pillar No.	Latitude	Longitude																														
A	25°52'37.11"N	79° 55'1.59"E																														
B	25°52'39.48"N	79° 55'29.22"E																														
C	25°52'27.04"N	79° 55'33.78"E																														
D	25°52'18.53"N	79° 55'0.08"E																														
Submerge Area																																
S1	25°52'22.82"N	79° 55'0.62"E																														
S2	25°52'34.81"N	79° 55'30.76"E																														
S3	25°52'28.99"N	79° 55'33.00"E																														
S4	25°52'19.76"N	79° 55'0.28"E																														
15.	Total Geological Reserves	9,39,614 m ³																														
16.	Total Mineable Reserve	5,89,791 m ³ as per final factual report on dt. 14/06/2023																														
17.	Total Proposed Production	29,14,560 m ³ for 5 years																														
18.	Proposed Production /year (as per LoI)	5,82,912 m ³ / annum as per LoI																														
19.	Sanctioned Period of Mine lease	5 years																														
20.	Method of Mining	Opencast semi - mechanized																														
21.	No. of worker	80																														

22.	Type of Land	Govt./Non Forest Land
23.	Depth of Mining	3.0 m (maximum)
24.	Nearest metalled road from site	0.86 km
25.	Water Requirement	PURPOSE
		Drinking - 0.80 KLD
		Suppression of dust - 10.32 KLD
		Plantation - 13.0 KLD
		Others (if any) - 3.60 KLD
		Total - 14.72~15.0 KLD
26.	Name of QCI Accredited Consultant with QCI No and period of validity.	Paramarsh Servicing Environment and development NABET/EIA/2124 RA 0224, Valid till –01 May 2024
27.	Any litigation pending against the project or land in any court	No
28.	Details of 500 m Cluster Certificate verified by Mining Officer	Letter No – 1751/Khanij-30, Banda, dated - 04/12/2020
29.	Details of Lease Area in approved DSR	Serial no. 71 at Page no. 01
30.	Project Cost	97.0 Lacs
31.	Proposed CER cost	1.94 Lacs
32.	Length and breadth of Haul Road	Length – 0.86 km, Breadth – 6.00 m
33.	No. of Trees to be Planted	3,600

5. The mining would be restricted to unsaturated zone only above the phreatic water table and will not intersect the ground water table at any point of time.
6. This project does not attract any of the general conditions applicable on mining projects specified in EIA Notification 14/09/2006.
7. The mining operation will not be carried out in safety zone of any bridge or embankment or in eco-fragile zone such as habitat of any wild fauna.
8. There is no litigation pending in any court regarding this project.
9. The project proposal falls under category–I(a) of EIA Notification, 2006 (as amended).

The consultant (EIA Coordinator) also submitted an affidavit dated 12/09/2023 mentioning is as follows:

1. I Dr. Surendra Vikram Ghavri S/o Shri Pratap Kumar is EIA Coordinator of Paramarsh servicing Environment and Development.
2. I have prepared EIA/EMP report for the Environmental clearance for proposed river bed sand/morrum mining having lease area 36.437 ha along river Betwa in khand No. 10/6 at Village – Beri, Tehsil- Hamirpur, District- Hamirpur, U. P. of M/s Kanwar Enterprises Private Limited Kanwar Pal Singh, Proposal number Proposal No. SIA/UP/MIN/29073/2018 with my team.
3. I have personally visited the proposed site along with team and certify that no mining activity has been undertaken on the project site for the present proposal.
4. I am satisfied with that all the necessary data/information required for EIA/EMP preparations are true and correct.
5. I certify that this project has been uploaded for the first time on Parivesh Portal.
6. I certify that there is no mismatch between information/data provided on online application and hard copy/presentation submitted.
7. I state that all the TOR Points have been complied and all the issues raised during Public Hearing have been properly addressed in EIA report.
8. The EIA/EMP report for the Proposal is prepared by my team as per guidelines laid down by QCI/NABET.

RESOLUTION AGAINST AGENDA NO. 05

The committee discussed the matter and recommended grant of environmental clearance for the project proposal along with general and specific conditions as annexed at Annexure-2 to these minutes. The committee also stipulated the following additional conditions:

1. Project proponent should submit the drone videography (not older than 07 days) of the project site mentioning the date, time and geo coordinates before starting the mining process.
2. Directorate of Geology and Mining will ensure conduct of replenishment study from reputed institution for subsequent years in compliance of Hon'ble NGT orders. The quantity mentioned in LoI or quantity mentioned in replenishment study, whichever is less, would be maximum quantity which project proponent may extract. It will be ensured by District Administration and Geology and Mining Department.
3. NOC from Irrigation Department/ Concerning Authority regarding river bed mining to be obtained before start of mining activity.
4. Project proponent has committed to plant 1000 number of trees/hectare. The project proponent/consultant if desires may approach to concerned District Forest Authority to plant 1000 trees/ha on a land available to the Forest Department. The project proponent will deposit the required amount for this entire plantation work (including its maintenance and security) to the Forest Department.
5. The project proponent shall install solar light in their site office.
6. During the submission of 6 monthly compliance reports, the project proponent should make sure that the periodically taken site photographs should also be annexed along with the compliance report.
7. Preference should be given to indigenous local species as per the consultation of the local district Forest Officer.
8. Link Road from the quarry site to the main road shall be constructed as an all-weather road with blacktopping and maintained by the project proponent.
9. Vehicular emissions should be kept under control and regularly monitored. Suitable measures shall be taken for proper maintenance of vehicles used in a quarry operation and transportation.
10. The project proponent should explore the possibilities of rainwater harvesting.
11. Agreement/ Consent between project proponent and competent authority/ landowner for haulage road from lease site to link road.
12. Latest technology (water sprinklers/ tankers) to be adopted for mitigating dust at source points in lease area and haulage road during operational activity/vehicular movement.
13. As per the proposed plan, plantation with area specific plant species, number of plants to be planted and report of green belt development to be submitted to the concerning department
14. Water requirement details along with source of water and the permission/ agreement with the concerning authority/ water supplying agencies to be submitted.
15. Submit the Hydrological study report of lease area that the quantity given in LoI will be mined without affecting the geo-hydrology of the River.

6. Khanda-Boulder/Gitti-Ballast Mine (Except Granite Dimensional Stone) at Gata no. -339 Village- Shivni Khurd, Tehsil- Lalitpur, District- Lalitpur, Shri Anshul Dixit, M/s R.S.D. Enterprises, Area-1.011 Ha., 8162/SIA/UP/MIN/441405/2023

The consultant informed the committee that they are strictly following the rules, regulations and other instructions of QCI/NABET. A presentation was made by the project proponent along with their consultant M/s AWS Envirotech (OPC) Pvt. Ltd. Based on the documents submitted and presentation made by the project proponent along with the consultant, the following facts have emerged: -

1. The environmental clearance is sought for “Khanda-Boulder/Gitti-Ballast Mine (Except Granite Dimensional Stone)” at Araj/Gata no.- 339, Village- Shivni Khurd, Tehsil- Lalitpur, District- Lalitpur, State- Uttar Pradesh, (Lease Area- 1.011 ha.), M/s R.S.D. Enterprises.
2. Salient features of the project as submitted by the project proponent:

1.	On-line proposal No.	SIA/UP/MIN/441405/2023
2.	File No. allotted by SEIAA, UP	8162
3.	Name of Proponent	M/s R.S.D. Enterprises (Prop. Shri Anshul Dixit)
4.	Full correspondence address of proponent and E-mail Id	Prop. Shri Anshul Dixit S/o Shri Anil Kumar Dixit R/o-585, Near Little Flower School, Gandhinagar,

		District- Lalitpur, U.P.																			
		E-mail Id- rsdenterprises5418@gmail.com																			
5.	Name of Project	“Khanda-Boulder/Gitti-Ballast Mine (Except Granite Dimensional Stone)” at Village- Shivni Khurd, Tehsil- Lalitpur, District- Lalitpur, Uttar Pradesh																			
6.	Project Location (Plot.Khasra/Gata No.)	Gata no.- 339, Village- Shivni Khurd, Tehsil- Lalitpur, District- Lalitpur, State- Uttar Pradesh																			
7.	Category of Project	B ₂																			
8.	Name of Village	Shivni Khurd																			
9.	Tehsil	Lalitpur																			
10.	District	Lalitpur																			
11.	Name of Minor Mineral	Khanda-Boulder/Gitti-Ballast (Except Granite Dimensional Stone)																			
12.	Sanctioned Lease Area (in Ha.)	1.011 ha																			
13.	Max. & Min mRL within lease area	Highest mRL is 365.5 mRL & Lowest is 362.5 mRL																			
14.	Pillar Coordinates (Verified by DMO)	Geo-coordinates are- <table><tr><td>Pillar</td><td>N</td><td>E</td></tr><tr><td>A</td><td>24°43'52.22"N</td><td>78°24'39.76"E</td></tr><tr><td>B</td><td>24°43'51.00"N</td><td>78°24'41.71"E</td></tr><tr><td>C</td><td>24°43'50.78"N</td><td>78°24'43.66"E</td></tr><tr><td>D</td><td>24°43'48.66"N</td><td>78°24'44.09"E</td></tr><tr><td>E</td><td>24°43'47.78"N</td><td>78°24'40.00"E</td></tr></table>		Pillar	N	E	A	24°43'52.22"N	78°24'39.76"E	B	24°43'51.00"N	78°24'41.71"E	C	24°43'50.78"N	78°24'43.66"E	D	24°43'48.66"N	78°24'44.09"E	E	24°43'47.78"N	78°24'40.00"E
Pillar	N	E																			
A	24°43'52.22"N	78°24'39.76"E																			
B	24°43'51.00"N	78°24'41.71"E																			
C	24°43'50.78"N	78°24'43.66"E																			
D	24°43'48.66"N	78°24'44.09"E																			
E	24°43'47.78"N	78°24'40.00"E																			
15.	Total Geological Reserves	6,05,811 m ³																			
16.	Total Mineable Reserve (as per Approved Mine Plan)	2,47,500 m ³																			
17.	Total Proposed Production (In 5 Years)	1,51,650 m ³ in 5 Years																			
18.	Proposed Production	30,330 m ³ /year																			
19.	Sanctioned Period of Mine lease	10 years																			
20.	Method of Mining	Opencast, Semi-Mechanized																			
21.	Working hours/day	8																			
22.	No. of worker	52																			
23.	Type of Land	Govt. land																			
24.	Ultimate of Depth of Mining	Upto 324 mRL																			
25.	Nearest metalled road from site	200m																			
26.	Water Requirement	PURPOSE	REQUIREMENT (KLD)																		
		Drinking	0.52 KLD																		
		Suppression of dust	1.80 KLD																		
		Plantation	0.50 KLD																		
		Others (if any)	-																		
		Total	2.82 KLD																		
27.	Name of QCI Accredited Consultant with QCI No and period of validity.	AWS Envirotech (OPC) Pvt. Ltd. Certificate no. NABET/EIA/2225/IA 0097(Rev.01) Valid Till July 14, 2025																			
28.	Any litigation pending against the project or land in any court	No																			
29.	Details of 500 m Cluster Certificate verified by Mining Officer	vide letter no. 468/30 M.M.C./ (2023-24) Dated on 23.06.2023																			
30.	Details of Lease Area in approved DSR	DSR attached																			
31.	Proposed CER cost	Rs. 1.76 Lakhs																			
32.	Proposed EMP cost	EMP cost is Rs. 7.5 Lakhs as capital cost and Rs. 5.25 lakhs as Recurring cost																			
33.	Distance of Haul Road	200 m																			
34.	No. of Trees to be Planted	250																			

- The mining would be restricted to unsaturated zone only above the phreatic water table and will not intersect the ground water table at any point of time.
- This project does not attract any of the general conditions applicable on mining projects specified in EIA Notification 14/09/2006.
- The mining operation will not be carried out in safety zone of any bridge or embankment or in eco-fragile zone such as habitat of any wild fauna.

6. There is no litigation pending in any court regarding this project.
7. The project proposal falls under category-1(a) of EIA Notification, 2006 (as amended).

The consultant (EIA Coordinator) also submitted an affidavit dated 19/08/2023 mentioning is as follows:

1. I, Sandeep Kumar, S/o Shri R.K. Verma is EIA Coordinator of M/s AWS Envirotech (OPC) Pvt. Ltd.
2. I have prepared the EC application report for the proposal “Khanda-Boulder/Gitti-Ballast Mine (Except Granite Dimensional Stone)” at Araj/Gata no.- 339, Village- Shivni Khurd, Tehsil- Lalitpur, District- Lalitpur, State- Uttar Pradesh, (Lease Area- 1.011 ha.), M/s R.S.D. Enterprises with my team.
3. I have personally visited the site of proposal and certify that no Mining activity has been undertaken on the project site for the present proposal.
4. I am satisfied that all the necessary data/ information submitted along with EC application are true and correct.
5. I certify that this project proposal has been uploaded for the first time on PARIVESH Portal.
6. I certify that there will be no mismatch between information/data provided on the online application submitted on PARIVESH Portal and the hard copy/presentation which will be submitted after acceptance of application.
7. The EC Report for the Proposal is prepared by my team as per guidelines laid down by QCI/NABET.

RESOLUTION AGAINST AGENDA NO. 06

The committee discussed the matter and recommended grant of environmental clearance for the project proposal along with general and specific conditions as annexed at Annexure-3 to these minutes. The committee also stipulated the following specific conditions:

1. Project proponent has committed to plant 1000 number of trees/hectare. The project proponent/consultant if desires may approach to concerned District Forest Authority to plant 1000 trees/ha on a land available to the Forest Department. The project proponent will deposit the required amount for this entire plantation work (including its maintenance and security) to the Forest Department.
2. The project proponent shall install solar light in their site office.
3. During the submission of 6 monthly compliance reports, the project proponent should make sure that the periodically taken site photographs should also be annexed along with the compliance report.
4. Preference should be given to indigenous local species as per the consultation of the local district Forest Officer.
5. The maximum height of the bench should be 06 meters and the width of the bench should be at least twice the height of the bench as per the mine plan approval letter by DGM, U.P
6. In case the blasting is proposed during a mining operation, the project proponent needs to assess its impact on the displacement of human beings/wild animals/birds/other species, and the suitable measures proposed and taken for their rehabilitation and resettlement need to be clearly described in first 6 monthly compliance report.
7. The project proponent shall submit a final mine closure plan/Exit protocol for rehabilitation of mined-out land to match its surrounding land use 3years before the closure of the mine to SEIAA, UP and Department of Mines and Geology, UP for approval. The project proponent shall ensure the implementation of the approved plan under the supervision of the Dept. of Mines and Geology.
8. The project proponent shall plan and implement collection drain and siltation basins of adequate size to arrest the silt and sediment flow from the quarry area. The surface runoff rainwater

harvesting and other water conservation measures on a long-term basis are to be taken in consultation with the Central/State Groundwater Board. The water so collected should be utilized for watering the haulage area, roads, and green belt development, etc.

9. The project proponent shall take all suitable measures to prevent pollution of groundwater and nearby water bodies in consultation with the State Pollution Control Board and consent to operate (if applicable) should be obtained from the State Pollution Control Board before the start of production from the mine.
10. Link Road from the quarry site to the main road shall be constructed as an all-weather road with blacktopping and maintained by the project proponent.
11. Vehicular emissions should be kept under control and regularly monitored. Suitable measures shall be taken for proper maintenance of vehicles used in a quarry operation and transportation.
12. The project proponent should explore the possibilities of rainwater harvesting.
13. Agreement/ Consent between project proponent and competent authority/ landowner for haulage road from lease site to link road.
14. Latest technology (water sprinklers/ tankers) to be adopted for mitigating dust at source points in lease area and haulage road during operational activity/vehicular movement.
15. As per the proposed plan, plantation with area specific plant species, number of plants to be Planted and report of green belt development to be submitted to the Forest Department, UPPCB and Directorate of Environment, UP.

7. Group Housing Project “Stellar One” On Plot No: Gh-09, Sector - 01, Greater Noida, Shri Benny. K. John., 2656/SIA/UP/MIS/303321/2023

The project proponent/consultant informed the committee that the environmental clearance for the existing project was issued by SEIAA, U.P. vide letter no. 3076/Parya/SEAC/2656/2014/SPO(V), dated 21/03/2016 for the plot area 65,813 sqm and built up area 2,57,013.134 sqm. A presentation was made by the project proponent along with their consultant M/s Ind Tech House Consult, Delhi.

The project proponent/consultant informed the committee that the project is proposed to be developed in phases, the collective built-up area of the project for phase-1 (completed) & phase-2 is 2,44,433.349 sqm which is less than the built up area mentioned in EC letter. So the project is being applied for amendment in the environment clearance through online Parivesh Portal on 18/08/2023.

Based on the documents submitted and presentation made by the project proponent along with the consultant, the following facts have emerged: -

1. The amendment in environmental clearance is sought for Group Housing Project “Stellar One” On Plot No: Gh-09, Sector - 01, Greater Noida, U.P., M/s Stellar Spring Projects Pvt. Ltd.
2. Environmental clearance for the existing project was issued by SEIAA, U.P. vide letter no. 3076/Parya/SEAC/2656/2014/SPO(V), dated 21/03/2016, for the plot area 65,813 sqm and built up area 2,57,013.134 sqm.
3. Maximum number of floors for Phase 2 will be B+G+18.
4. Comparative details of existing project and proposed amendment:

S.No.	Particulars	As per EC	Phase-I + Phase-II	Difference	Unit
1	Total Plot Area	65813	65813	No Change	sqm
2	Net Plot Area	64803	64803	No Change	sqm
3	Proposed Built-up Area	257013.135	244433.349	-12579.786	sqm
4	Total No. of Saleable DU's		1548	1548	sqm
5	No. of Blocks	15	11	-4	
6	Max No. of Floors	B+S+14	B+G+18	+4	nos.
7	Max Height of the building	48	65.2	+17.2	m
8	Permissible Ground Coverage	22681.05	22681.05	No Change	sqm

9	Proposed Ground Coverage	14836.732	11893.932	-2942.8	sqm
10	Permissible FAR	178208.25	178208.25	No Change	sqm
11	Proposed FAR	178025.916	173734.867	-4291.049	sqm
12	Non-FAR Areas (basement, 15% services area, stilt etc.)	78987.219	70698.482	-8288.737	sqm
13	Total Water Requirement	828	728.21	-99.79	KLD
14	Fresh water requirement	552	481.49	-70.51	KLD
15	Proposed Capacity of STP	330	700	+370	KLD
16	Total Required Parking	2228	2175	-53	ECS
17	Total Proposed Parking	2229	2175	-54	ECS
18	Proposed Green Area	25081.667	21810.503	-3271.164	sqm
19	Total Solid Waste Generation	4.33	3.73	-0.60	TPD
20	Organic Waste	2.16	1.49	-0.67	TPD
21	Total Power Requirement	6500	4686	-1814	KVA
22	DG set backup	7040	3030	-4010	KVA
23	No of DG Sets	2x1500+4x1010	3x1010	-4010	No.

5. Landscape plan:

Plot Area	65803 m ²
Proposed Green Area (33.14 % of plot area)	21810.503 m ²
Required No of Trees	822.53 Nos.
Proposed No. of trees	825 Nos.

The project proponent requested to amend the environmental clearance letter dated 21/03/2016 as per above details.

RESOLUTION AGAINST AGENDA NO. 07

The committee discussed the matter and recommend to amend the environmental clearance letter no. 3076/Parya/SEAC/2656/2014/SPO(V), dated 21/03/2016 as per above details. All the other contents mentioned in EC letter dated 21/03/2016 shall remain the same. The committee also stipulated following additional conditions:

1. The project proponent will ensure that there is no mismatch/deviation between the project proposal submitted to SEIAA for environmental clearance and maps/drawings were approved by concerned development authority. In case of any mismatch/deviation, amended environmental clearance will be obtained by project proponent. In case of failure, the granted environmental clearance shall automatically deem to be cancelled.
2. The project proponent shall obtain all necessary clearances/permission from all relevant agencies including town planning authority before commencement of work. All the construction shall be done in accordance with the local building byelaws.
3. The approval of the Competent Authority shall be obtained for structural safety of buildings due to earthquakes, adequacy of firefighting equipment etc as per National Building Code including protection measures from lightning etc.
4. The project proponent shall obtain Consent to Establish / Operate under the provisions of Air (Prevention & Control of Pollution) Act, 1981 and the Water (Prevention & Control of Pollution) Act, 1974 from the concerned State Pollution Control Board/ Committee.
5. The project proponent shall obtain the necessary permission for drawl of ground water / surface water required for the project from the competent authority.
6. Project proponent is advised to explore the possibility and getting the cement in a closed container rather through the plastic bag to prevent dust emissions at the time of loading/unloading.
7. Project proponent should ensure that there will be no use of "Single use of Plastic" (SUP).
8. In compliance to Hon'ble Supreme Court order dated 13/01/2020 in IA no. 158128/2019 and 158129/2019 in Writ petition no. 13029/1985 (MC Mehta Vs. GoI and others) anti-smog guns shall be installed to reduce dust during excavation.
9. Project Proponent should submit the certified compliance report (CCR) from IRO Office, MoEF Lucknow of previous Environment clearance dated 21/03/2016 as per EIA notification to the Directorate & Concerning authorities.

8. “Ordinary Earth Mine” at Khasra/Gata No.- 923 & 924, Village- Adampur Bhatpura, Pargana- Satrikh, Tehsil- Nawabganj, District- Barabanki, Shani Kumar, Area- 0.560 Ha., 7936/SIA/UP/MIN/431003/2023

The committee noted that the matter was earlier listed in 734th SEAC meeting dated 14/03/2023 and the project proponent did not appear in the meeting. The project proponent through online Parivesh Portal on 22/08/2023 has requested to list the matter in next SEAC meeting and the matter was listed in 787th SEAC meeting dated 18/09/2023.

The consultant informed the committee that they are strictly following the rules, regulations and other instructions of QCI/NABET. A presentation was made by the project proponent along with their consultant M/s AWS Envirotech (OPC) Pvt. Ltd. Based on the documents submitted and presentation made by the project proponent along with the consultant, the following facts have emerged: -

1. The environmental clearance is sought for “Ordinary Earth Mining” at Araji/Gata no.- 923 & 924, Village- Adampur Bhatpura, Pargana- Satrikh, Tehsil- Nawabganj, District- Barabanki, Uttar Pradesh, (Leased Area- 0.560 ha.).
2. Salient features of the project as submitted by the project proponent:

1.	On-line proposal No.	SIA/UP/MIN/431003/2023			
2.	File No. allotted by SEIAA, UP	7936			
3.	Name of Proponent	Shani Kumar			
4.	Full correspondence address of proponent and mobile no.	Shani Kumar S/o Ramchandra R/o- Murliganj, Jaidpur, Siddhapur, Barabanki, Uttar Pradesh E-mail Id- shanikumar541818@gmail.com			
5.	Name of Project	“Ordinary Earth Mining” at Village- Adampur Bhatpura, Pargana- Satrikh, Tehsil- Nawabganj, District- Barabanki, Uttar Pradesh.			
6.	Project Location (Plot.Khasra/Gata No.)	Gata No.- 923 & 924, Village- Adampur Bhatpura, Pargana- Satrikh, Tehsil- Nawabganj, District- Barabanki, Uttar Pradesh.			
7.	Name of River	NA			
8.	Name of Village	Adampur Bhatpura			
9.	Tehsil	Nawabganj			
10.	District	Barabanki			
11.	Name of Minor Mineral	Ordinary earth			
12.	Sanctioned Lease Area (in Ha.)	0.560 ha.			
13.	Max. & Min mRL within lease area	Highest- 132 mRL & Lowest- 131 mRL			
14.	Pillar Coordinates (Verified by DMO)	Plot No	Points	Latitude	Longitude
		923	A	26°46'53.46"N	81°16'11.19"E
			B	26°46'51.93"N	81°16'9.57"E
			C	26°46'53.24"N	81°16'8.36"E
			D	26°46'53.82"N	81°16'8.93"E
			E	26°46'54.13"N	81°16'8.62"E
			F	26°46'54.85"N	81°16'9.49"E
		924	A	26°46'53.46"N	81°16'11.19"E
			B	26°46'51.93"N	81°16'9.57"E
			C	26°46'51.28"N	81°16'10.22"E
			D	26°46'52.77"N	81°16'12.02"E
15.	Total Geological Reserves	12,320 m ³			
16.	Total Mineable Reserve (as per Approved Mine Plan)	9,576 m ³			
17.	Total Proposed Production	9,500 m ³ (in 3 months)			
18.	Proposed Production	9,500 m ³ (in 3 months)			
19.	Sanctioned Period of Mine lease	03 months			
20.	Method of Mining	Opencast, Semi-Mechanized			
21.	Working hours/day	8			
22.	No. of worker	10			

23.	Type of Land	Private land	
24.	Ultimate of Depth of Mining	2.2m	
25.	Nearest metalled road from site	200 m	
26.	Water Requirement	PURPOSE	REQUIREMENT (KLD)
		Drinking	0.10 KLD
		Suppression of dust	1.80 KLD
		Plantation	0.06 KLD
		Total	1.96 KLD
27.	Name of QCI Accredited Consultant with QCI No and period of validity.	M/s AWS Envirotech (OPC) Pvt. Ltd 2 nd floor Devpuri plaza, Neelgiri crossing, Faizabad road, Indranagar, Lucknow-226016, U.P. Certificate no. NABET/EIA/2225/IA 0097 (Rev.01) Valid Till July 14, 2025	
28.	Any litigation pending against the project or land in any court	No	
29.	Details of 500 m Cluster Certificate verified by Mining Officer	vide letter no.- 1222/A.J.A. II Dated- 26.04.2023	
30.	Details of Lease Area in approved DSR	Its ordinary soil mining project, DSR not applicable	
31.	Proposed CER cost	Rs. 8,000/-	
32.	Proposed EMP cost	EMP Cost- Rs. 86,500/-	
33.	Length and breadth of Haul Road	200 m	
34.	No. of Trees to be Planted	30	

3. The mining would be restricted to unsaturated zone only above the phreatic water table and will not intersect the ground water table at any point of time.
4. This project does not attract any of the general conditions applicable on mining projects specified in EIA Notification 14/09/2006.
5. The mining operation will not be carried out in safety zone of any bridge or embankment or in eco-fragile zone such as habitat of any wild fauna.
6. There is no litigation pending in any court regarding this project.
7. The project proposal falls under category-1(a) of EIA Notification, 2006 (as amended).

The consultant (EIA Coordinator) also submitted an affidavit dated 13/05/2023 mentioning is as follows:

1. I, Sandeep Kumar, S/o Shri R.K. Verma is EIA Coordinator of M/s AWS Envirotech (OPC) Pvt. Ltd.
2. I have prepared the EC application report for the proposal "Ordinary Earth Mining" at Araj/Gata no.- 923 & 924, Village- Adampur Bhatpura, Pargana- Satrikh, Tehsil- Nawabganj, District- Barabanki, Uttar Pradesh, (Leased Area- 0.560 ha.) with my team.
3. I have personally visited the site of proposal and certify that no Mining activity has been undertaken on the project site for the present proposal.
4. I am satisfied that all the necessary data/ information submitted along with EC application are true and correct.
5. I certify that this project proposal has been uploaded for the first time on PARIVESH Portal.
6. I certify that there will be no mismatch between information/data provided on the online application submitted on PARIVESH Portal and the hard copy/presentation which will be submitted after acceptance of application.
7. The EC Report for the Proposal is prepared by my team as per guidelines laid down by QCI/NABET.

RESOLUTION AGAINST AGENDA NO. 08

The committee discussed the matter and recommended grant of environmental clearance for the project proposal along with general and specific conditions as annexed at Annexure-4 to these minutes.

9. Building Stone (Khanda – Boulder/Gitti- Ballast) Mining project at Gata/Araji No -996 Khand-1, Village-Gariya, Tehsil- Taalbehat & District-Lalitpur, Shri Swami Prasad, Area:1.618 Ha., 7638/SIA/UP/MIN/417841/2023

The committee noted that the matter was earlier listed in 734th SEAC meeting dated 14/03/2023 and the project proponent did not appear in the meeting. The project proponent through online Parivesh Portal on 22/08/2023 has requested to list the matter in next SEAC meeting and the matter was listed in 787th SEAC meeting dated 18/09/2023.

The consultant informed the committee that they are strictly following the rules, regulations and other instructions of QCI/NABET. A presentation was made by the project proponent along with their consultant M/s Ind Tech House Consult. Based on the documents submitted and presentation made by the project proponent along with the consultant, the following facts have emerged: -

1. The terms of reference is sought for Building Stone Khanda- Boulder/ Gitti Ballast Mining project at Khand No. 1, Araji no.- 996, Village-Gariya, Tehsil- Taalbehat, District- Lalitpur, Uttar Pradesh, (Leased Area 1.618 Ha).
2. Salient features of the project as submitted by the project proponent:

1.	On Line Proposal No.	SIA/UP/MIN/417841/2023		
2.	File No. allotted by SEIAA, UP	7638		
3.	Name of Proponent	Shri. Swami Prasad S/o Shri Raghuvar Singh		
4.	Full correspondence address of proponent and mobile no.	Shri. Swami Prasad R/o-198 Vill- Lakhanpura, Tehsil & District - Lalitpur U.P.		
5.	Name of Project	Building Stone Khanda- Boulder/ Gitti Ballast Mining project named Shri. Swami Prasad at Khand No'-1 Araji no. 996, Village-Gariya, Tehsil- Taalbehat, District- Lalitpur, Uttar Pradesh. Area 1.618 Ha		
6.	Project Location(Plot.Khsra/Gata/Araji No.)	Khand No'-1, Araji no. 996		
7.	Name of Village	Gariya		
8.	Tehsil	Taalbehat		
9.	District	Lalitpur		
10.	Name of Minor Mineral	Building Stone Khanda- Boulder/ Gitti -Ballast		
11.	Sanctioned Lease Area (in Ha.)	1.618 Ha		
12.	Max. & Min mRL within lease area	335.5 mRL & 331.0 mRL		
13.	Pillar Coordinates (Verified by DMO)	PILLAR NO.	LATITUDE	LONGITUDE
		A	24°50'52.03"N	78°29'46.86"E
		B	24°50'57.83"N	78°29'50.16"E
		C	24°50'57.18"N	78°29'53.04"E
		D	24°50'51.38"N	78°29'50.16"E
14.	Total Geological Reserves	771825 m ³		
15.	Total Mineable Reserve in LOI	24270.00 m ³ /Annum		
16.	Total Proposed Production in LOI	24270.00 m ³ /Annum		
17.	Sanctioned Period of Mine lease	20 Years		
18.	Method of Mining	Open cast Manual/ Semi Mechanized Mining		
19.	No. of working days	300 Days		
20.	Working hours/day	8 Hours		
21.	No. of worker	30 Workers		
22.	No. of vehicles movement/day	9 Trucks / Day		
23.	Type of Land	Govt. Land		
24.	Ultimate of Depth of Mining	9.0 m		
25.	Nearest metalled road from site	1.00 Km		
26.	Water Requirement	PURPOSE	REQUIREMENT (KLD)	
		Drinking	0.30 KLD	
		Suppression of dust	4.20 KLD	

		Plantation	0.32 KLD
		Others (if any)	
		Total	4.82 KLD
27.	Details of Lease Area in approved DSR (Shuddhi Patra)	Page No -1, Sr.No -5 Letter Vide No'-786 Kh/30 Mines/ 2019-20 dated 6.2.2020	
28.	Proposed CER cost	2% of total project cost i.e. Rs. 2.10 Lakhs	
29.	Proposed EMP cost	16.26 Lakhs	
30.	Proposed Project cost	1.05 Crore	
31.	Length and breadth of Haul Road	700 mt Length & 6m width haulage road	
32.	No. of Trees to be Planted	160 Trees/Year	
33.	Baseline Monitoring Period	October 2022 to December 2022	

3. The mining would be restricted to unsaturated zone only above the phreatic water table and will not intersect the ground water table at any point of time.
4. This project does not attract any of the general conditions applicable on mining projects specified in EIA Notification 14/09/2006.
5. The mining operation will not be carried out in safety zone of any bridge or embankment or in eco-fragile zone such as habitat of any wild fauna.
6. There is no litigation pending in any court regarding this project.
7. The project proposal falls under category-1(a) of EIA Notification, 2006 (as amended).

The consultant (EIA Coordinator) also submitted an affidavit dated 15/09/2023 mentioning is as follows:

1. I, Anand Kumar Dubey, S/o Shri. Amar Nath Dubey am EIA Coordinator of Ind Tech House Consult.
2. I have prepared TOR report for the Proposal (SIA/UP/MIN/417841/2023), Project Name- Swami Prasad Building Stone (Khanda – Boulder/Gitti- Ballast) Mining at Gata/Araji No -996 Khand-1, Village-Gariya (गड़िया), Tehsil- Taalbehat & District-Lalitpur, U.P. Area:1.618 Ha with my team
3. I have personally visited the site of proposal and certify that no mining activity has been undertaken on the project site for the present proposal.
4. I am satisfied with that all the necessary data/information required submitted along with Application/TOR are true and correct.
5. I certify that this project has been uploaded for this first time on Parivesh portal.
6. I certify that there will be no mismatch between information/data provided on the online application submitted on Parivesh Portal and hard copy/presentation submitted which will be submitted after acceptance of application.
7. The TOR report for the Proposal is prepared by my team as per guidelines laid down by QCI/ NABET.

RESOLUTION AGAINST AGENDA NO. 09

The committee discussed the matter and recommended to issue the standard terms of reference for the preparation of EIA as annexed at annexure-1 to the minutes. The committee also stipulated following additional TOR Points:

Additional TOR:

1. To ensure proper monitoring, the project proponent/consultant should provide evidence in form of (A) Raw Data (B) Logbook of their site visit along with activities carried out during monitoring (C) Real time photographs showing monitoring machine, public, lab person etc. Proprietor/proprietor representative should be present at the time of monitoring and monitoring should be conducted as per CPCB SOP/NABET/QCI guidelines. Lab responsible person should be present at the time of EIA presentation.

2. EIA coordinator & FAE should give a notarized affidavit during EIA presentation that they have personally visited the site & they have also taken all the mitigating measures for any critical issues involved in the project.
3. The project proponent will have to inform the schedule of monitoring/data collection programme to the SEIAA/SEAC, UP before start of data collection. In case of failure, the collected baseline monitoring data will be treated as null and void.
4. The details of equipment used for baseline monitoring alongwith its photograph mentioning date, time and geo coordinates for preparation of EIA report should be clearly displayed to the people present during public hearing and the complete details related to monitoring period must be mentioned in the minutes of public hearing.
5. Original lab analysis report of the project proposal along with EIA report should be uploaded on Parivesh Portal.
6. Combined KML of all mines in a cluster should be submitted at the time of EIA.
7. The project proponent/Consultant should identify the core & buffer zone (2.5 km) of the mining site.
8. Agreement/ Consent between project proponent and competent authority/ landowner for haulage road from lease site to link road to be submitted at the time of EIA presentation.
9. Proponent/Consultant should submit the plan/information along with technology (photographs of water sprinklers/ tankers) to be implemented for mitigating dust at source points in lease area and haulage road during operation activity/vehicular movement. Technology should be displayed at the time of EIA presentation.
10. Proposed plantation plan with area specific plant species, number of plants to be planted and place of plantation along with a proper map to be submitted at the time of EIA presentation.
11. Water requirement details along with source of water and the permission/ agreement with the concerning authority/ person to be submitted at the time of EIA presentation.
12. Proponent/consultant shall present TOR specific/additional conditions compliance, observation/suggestions raised during the public hearing and commitment made by the project proponent in a tabular form with a time bound plan at the time of EIA presentation.
13. Corporate Social Responsibility (CSR) to be prepared as per the MoEF guidelines and present it at the time of EIA presentation.

10. Review the decision of 731st Minutes of meeting dated 24/05/2023 SL No. 16 of M/s Bio World Waste Management (OPC) Private Limited File No 7354.

The Secretariat informed the committee that the matter was earlier discussed in 748th SEAC-1 meeting dated 12/05/2023 and the SEAC-1 recommended to issued the terms of reference for the preparation of EIA report regarding the project. Subsequently, SEIAA take up the matter in its 731st meeting dated 24/05/2023 wherein:

“SEIAA noted that SEAC has recommended to issue terms of reference to the above project. SEIAA also noted that as per Hon’ble Supreme Court Order dated December 8, 2021:

“A representative of NEERI shall be included as a member in the Environmental Appraisal Committee (EAC) and State Environmental Appraisal Committee (SEAC) constituted by the Ministry of Environment, Forest and Climate Change for dealing with industrial units falling in TTZ Area.

“...And as per MoEFCC OM IA3-22/43/2021-IA III dated 01.04.2022 -para-2:-

In this regard, NEERI has nominated Dr. S.K. Goyal, Chief Scientist & Head, CSIR-NEERI, Delhi Zonal Centre as its representative for the meeting of EACs and SEACs involving projects which fall in the TTZ area.

SEAC has carried out this appraisal without associating the representative of NEERI, thus SEIAA opined to refer back the project to SEAC to review the case in presence of a representative of NEERI."

As per the above decision of SEIAA, the matter was listed in 731st SEAC meeting dated 24/05/2023. The committee discussed the matter and decided that the project proponent/consultant should be called for presentation before the SEAC along with proposed CBWTF site documents and TTZ area map for appraisal of the matter.

The project proponent submitted their replies through letter dated 26/06/2023 and 18/09/2023. A presentation was made by the project proponent along with their consultant M/s Ind Tech House Consult. The project proponent informed the committee that the distance between project site and boundary of TTZ is more than 32 km and self attested map of TTZ area submitted before SEAC. The project proponent also submitted Google map indicating the boundary of TTZ area and location of project site.

The committee has gone through the reply submitted by the project proponent and opined that as per documents presented before SEAC it seems that the project site outside the boundary of TTZ area. Hence, the committee recommended to issue terms of reference for the preparation of Environment Impact Assessment Report (EIA) as earlier prescribed in 748th SEAC meeting dated 12/05/2023 subjected to the proponent to submit the confirmation letter from Taj Trapezium Zone (Prevention and Control of Pollution) Authority, Agra with regard to the proposed site does not fall in TTZ area. PP shall also provide land conversion documents for industrial use i.e. CBWTF and a gap analysis report as per CPCB prescribed proforma from UPPCB for establishment of this proposed CBWTF to SEIAA.

**(Prof. Jaswant Singh)
Member**

**(Dr. Amrit Lal Halidar)
Member**

**(Dr. Shiv Om Singh)
Member**

**(Tanzar Ullah Khan)
Member**

**(Ashish Tiwari)
Member-Secretary**

**(Dr. Harikesh Bahadur Singh)
Chairman**

Nodal, SEAC-2

MoM prepared by Secretariat in consultation with
Chairman & Members on the basis of decisions
taken by SEAC-2 during the meeting.

Annexure-3

General and Specific Conditions for Gitti, Patthar & Boulder Mining Projects: -

A. General Conditions:

1. This environmental clearance is subject to allotment of mining lease in favour of project proponent by District Administration/Mining Department.
2. Forest clearance shall be taken by the proponent as necessary under the law.
3. Any addition of the mining area, change of Khasra numbers, enhancement of capacity, change in mining technology, modernization, and scope of working shall again require prior environmental clearance as per EIA notification, 2006.
4. No change in the calendar plan including excavation, the quantum of mineral and waste shall be made.
5. Mining will be carried out as per the approved mining plan. In case of any violation of the mining plan, the Environmental Clearance given by SEIAA will stand cancelled.
6. Four ambient air quality monitoring stations shall be established in the core zone as well as in the buffer zone for RSPM, SPM, SO₂, NO_x monitoring. The location of the stations should be decided based on the meteorological data, topographical features, and environmentally and ecologically sensitive targets and frequency of monitoring should be undertaken in consultation with the State Pollution Control Board. The monitored data for criteria pollutants shall be regularly uploaded on the company's website and also displayed on the website.
7. Data on ambient air quality (RPM, SPM, SO₂, NO_x) should be regularly submitted to the Integrated Regional Office, MoEF&CC, GoI, Lucknow and the State Pollution Control Board / Central Pollution Control Board once in six months.
8. Ambient air quality at the boundary of the mine premises shall conform to the norms prescribed in MoEF notification no. GSR/826(E) dated 16.11.09.
9. Fugitive dust emissions from all the sources shall be controlled regularly. Water spraying arrangement on haul roads, loading and unloading, and at transfer points shall be provided and properly maintained.
10. Measures shall be taken for control of noise levels below 85 dBA in the work environment. Workers engaged in operations of HEMM, etc. shall be provided with earplugs/muffs and health records of the workers shall be maintained.
11. Industrial wastewater (workshop and wastewater from the mine) should be properly collected, treated to conform to the standards prescribed under GSR 422 (E) dated 19th May 1993 and 31st December 1993 or as amended from time to time. Oil and grease traps shall be installed before the discharge of workshop effluents.
12. Personnel working in areas shall be provided with protective respiratory devices like masks and they shall also be imparted adequate training and information on safety and health aspects.
13. Special measures shall be adopted to prevent the nearby settlements from the impacts of mining activities.
14. The transportation of the materials shall be limited to the day hours' time only.
15. Provision shall be made for housing the laborers within the site with all necessary infrastructure and facilities such as fuel for cooking, mobile toilets, safe drinking water, medical health care, crèche, etc. The housing may be in the form of temporary structures to be removed after the completion of the project.
16. A separate Environmental Management Cell with suitably qualified personnel shall be setup under the control of a Senior Executive, who will report directly to the Head of the Organization.
17. The Project Proponent shall inform the Integrated Regional Office, MoEF&CC, GoI, Lucknow and State Pollution Control Board regarding the date of financial closures and final approval of the project by the concerned authorities and the date of start of land development work.

18. The funds earmarked for environmental protection measures shall be kept in a separate account and shall not be diverted for other purposes. The year-wise expenditure shall be reported to the Integrated Regional Office, MoEF&CC, GoI, Lucknow and State Pollution Control Board
19. The Integrated Regional Office, MoEF&CC, GoI, Lucknow and State Pollution Control Board shall monitor compliance with the stipulated conditions. A complete set of documents including Environment Impact Assessment Report, Environmental Management Plan, Public hearing, and other documents information should be given to the Integrated Regional Office, MoEF&CC, GoI, Lucknow and State Pollution Control Board
20. A copy of the environmental clearance shall be submitted by the Project Proponent to the Heads of the Local Bodies, Panchayat, and Municipal Bodies as applicable in the matter.
21. The Project Proponent shall advertise at least in two local newspapers widely circulated, one of which shall be in the vernacular language of the locality concerned, within 7 days of the issue of the clearance letter informing that the project has been accorded environmental clearance and a copy of the clearance letter is available with the State Level Environment Impact Assessment Authority (SEIAA).
22. The Project Proponent has to submit a regular half-yearly compliance report of the stipulated prior environmental clearance terms and conditions in hard and soft copy to the SEIAA, U.P. on 1st June and 1st December of each calendar year.
23. The SEIAA may alter/modify the above conditions or stipulate any further condition in the interest of environmental protection.
24. Concealing factual data or submission of false/fabricated data and failure to comply with any of the conditions mentioned above may result in withdrawal of this clearance and attract action under the provisions of the Environment (Protection) Act, 1986.

B. Specific Conditions:

1. At the time of operation, the project proponent will comply with all the guidelines issued by the Government of India/State Govt./District Administration related to Covid-19.
2. This environmental clearance does not create or verify any claim of the applicant on the proposed site/activity.
3. In case it has been found that the E.C. obtained by providing incorrect information, submitting that the distance between the two adjoining mines is greater than 500mt. and the area is less than 05ha, but factually the distance is less than 500 mt, and the mine is located in the cluster of area equal to or more than 05ha, the E.C issued will stand revoked.
4. This environmental clearance shall be subject to a valid lease in favor of the project proponent for the proposed mining proposals. In case, the project proponent does not have a valid lease, this environmental clearance shall automatically become null and void.
5. The Environmental clearance will be co-terminus with the mining lease period/Mining Plan whichever is less. The Mining plan approved by the Dept. of Mines and Geology shall be strictly implemented and shall not be operated beyond the validity period.
6. Explosive cannot be stored on the site. The Project proponent shall take approval from Chief Controller of Explosive, if applicable for use or storage of explosive or any such materials.
7. A comprehensive EIA including mining areas within 15 K.M. to assess the impact of the mining activity on the surrounding area shall be undertaken and a report submitted to this Authority within one year.
8. No two pits shall be simultaneously worked i.e. before the first is exhausted and reclamation work completed, no mineral bearing area shall be worked.
9. After exhausting the first mine pit and before starting mining operations in the next pit, reclamation and plantation work in the exhausted pit shall be completed to ensure that reclamation, forest cover, and vegetation are visible during the first year of mining operations in the next pit. This process will follow till the last pit is exhausted. Adequate rehabilitation of mined pit shall be completed before any new ore-bearing area is worked for expansion.
10. An adequate buffer zone shall be maintained between two consecutive mineral-bearing deposits.
11. The sprinkling of water on haul roads to control dust will be ensured by the project proponent.

12. Green belt development shall be carried out considering CPCB guidelines including the selection of plant species and in consultation with the local DFO / Agriculture Department. Herbs and shrubs shall also form a part of the afforestation programme besides tree plantation. The company shall involve local people in the plantation programme. Details of year-wise afforestation programme including rehabilitation of mined-out area shall be submitted to the Integrated Regional Office, MoEF&CC, GoI, Lucknow every year.
13. Blast vibrations study shall be conducted and an observation report submitted to the Integrated Regional Office, MoEF&CC, GoI, Lucknow and UPPCB within six months. The report shall also include measures for the prevention of blasting associated impact on nearby houses and agricultural fields.
14. Controlled blasting techniques with sequential blasting shall be adopted. The blasting shall be carried out in the daytime only. The project proponent shall ensure prevention of displacement of human beings/wild animals/birds etc. and in case any such displacement is caused due to blasting/mining operation by any chance the project proponent shall take suitable measures for their rehabilitation and resettlement.
15. Appropriate arrangement for shelter and drinking water for the mining workers has to be ensured at the mining site.
16. Maintenance of village roads used for transportation of minerals is to be done by the company regularly at its own expenses. The link roads from mining area to main road shall be constructed as all-weather road with black topping and maintained by the project proponent.
17. The surface runoff rain water harvesting/rain water recharge and water conservation measures will be taken by project proponent in consultation with central /State ground water Board .The project proponent shall plan and implement collection drain and siltation basins of adequate size to arrest the silt and sediment flows from the mining area. The supernatant of the siltation basin and rain water harvested water shall be utilized for watering the haulage area, roads and green belt development etc.
18. Status of implementation shall be submitted to the Integrated Regional Office, MoEF&CC, GoI, Lucknow and UP Pollution Control Board within six months and thereafter every year from the next consequent year.
19. The self-environmental audit shall be conducted annually. Every three years third-party environmental audit shall be carried out.
20. Measures for prevention and control of soil erosion and management of silt shall be undertaken. Protection of dumps against erosion shall be carried out with geotextile matting or other suitable material, and thick plantations of native trees and shrubs shall be carried out at the dump slopes. Dumps shall be protected by retaining walls.
21. Trenches/garland drains shall be constructed at foot of dumps and coco filters installed at regular intervals to arrest silt from being carried to water bodies. An adequate number of Check Dams and Gully Plugs shall be constructed across seasonal/perennial nallahs if any flowing through the ML area and silts arrested. De silting at regular intervals shall be carried out.
22. Garland drain of appropriate size, gradient, and length shall be constructed for both mine pit and waste dump and sump capacity shall be designed keeping 50% safety margin over and above peak sudden rainfall (based on 50 years data) and maximum discharge in the area adjoining the mine site. Sump capacity shall also provide an adequate retention period to allow proper settling of silt material. Sedimentation pits shall be constructed at the corners of the garland drains and de silted at regular intervals.
23. Ground and surface water, if any in and near the core zone (within 5.0 km of the lease) shall be regularly monitored for contamination and depletion due to mining activity and records maintained. The monitoring data shall be submitted to the Integrated Regional Office, MoEF&CC, GoI, Lucknow and U.P. Pollution Control Board regularly. Further, monitoring points shall be located between the mine, and drainage in the direction of flow of groundwater shall be set up and records maintained.
24. Fugitive dust generation shall be controlled. Fugitive dust emission shall be regularly monitored at locations of nearest human habitation (including schools and other public amenities located nearest to sources of dust generation as applicable) and records submitted to the Integrated Regional Office, MoEF&CC, GoI, Lucknow and U.P. Pollution Control Board regularly.

25. Baseline data for ambient air quality shall be generated and maintained and RSPM level in ambient air in the nearby human habitation (villages) shall also be monitored along with other parameters.
26. Corporate Environmental Responsibility (CER) shall be by the project proponent and the details of the various heads of expenditure are to be submitted as per the guidelines provided in the recent CER notification No. 22-65/2017-IA.III dated 01/05/2018. Work to be executed with the installation of five hand pumps for drinking water, solar light in villages of streets, construction of two numbers of toilets at the primary school with name displayed and address and details of the beneficiary and gram Pradhan along with phone number, photographs should be submitted to Directorate as well as to the District Magistrate / Chief Development officers.
27. Transportation of minerals shall be done by covering the trucks with tarpaulin or other suitable mechanisms so that no spillage of mineral/dust takes place.
28. Occupational health and safety measures for the workers including identification of work-related health hazards, training on malaria eradication, HIV, and health effects on exposure to mineral dust, etc. shall be carried out. Periodic monitoring for exposure to respirable mineral dust on the workers shall be conducted and records maintained including the health records of the workers. Awareness programmes for workers on the impact of mining on their health and precautionary measures like the use of personal protective equipment etc. shall be carried out periodically. A review of the impact of various health measures shall be conducted followed by follow-up action wherever required.
29. The project proponent will ensure for employing local people as per requirement, necessary protection measures around the mine pit and waste dump, and garland drain around the mine pit and waste dump.
30. Topsoil / solid waste shall be stacked properly with proper slope and adequate safeguards and shall be utilized for backfilling (wherever applicable) for reclamation and rehabilitation of the mined-out area. Topsoil shall be separately stacked for utilization later for reclamation and shall not be stacked along with overburden.
31. Overburden (OB) shall be stacked at the earmarked dump site(s) only and shall not be kept active for long period. The maximum height of the dump shall not exceed 20 m, each stage shall preferably be of a maximum of 10 m and the overall slope of the dump shall not exceed 35°. The OB dump shall be backfilled. The OB dumps shall be scientifically vegetated with suitable native species to prevent erosion and surface runoff.
32. Monitoring and management of rehabilitated areas shall continue until the vegetation becomes self-sustaining. Compliance status shall be submitted to the Regional Office, Ministry of Environment & Forests, GoI, Lucknow, and U.P. Pollution Control Board on a six-monthly basis.
33. The slope of the mining bench and ultimate pit limit shall be as per the mining scheme approved by the Indian Bureau of Mines.
34. Permission for the abstraction of groundwater shall be taken from Central Ground Water Board. Regular monitoring of ground and surface water sources for level and quality shall be carried out by establishing a network of existing wells and constructing new piezometers during the mining operation. The monitoring shall be carried out four times in a year i.e., premonsoon (April/May), monsoon (August), post-monsoon (November), and winter (January), and the data thus collected shall be regularly sent to MoEF&CC, Central Ground Water Authority, and Regional Director, Central Ground Water Board.
35. The wastewater from the mine shall be treated to conform to the prescribed standards before discharging into the natural stream. The discharged water from the Tailing Dam, if any shall be regularly monitored and report submitted to the Integrated Regional Office, MoEF&CC, GoI, Lucknow, Central Pollution Control Board, and the State Pollution Control Board.
36. Hydrogeological study of the area shall be reviewed by the project proponent annually. In case the adverse effect on groundwater quality and quantity is observed mining shall be stopped and resumed only after mitigating steps to contain any adverse impact on groundwater is implemented.
37. Vehicular emissions shall be kept under control and regularly monitored. Vehicles used for transportation of minerals and others shall have valid permissions as prescribed under Central Motor Vehicle Rules, 1989 and its amendments. The vehicles transporting minerals shall be

- covered with a tarpaulin or other suitable enclosures so that no dust particles / fine matters escape during the period of transportation. No overloading of minerals for transportation shall be committed. The trucks transporting minerals shall not pass through the wildlife sanctuary if any in the study area.
38. Prior permission from the Competent Authority shall be obtained for the extraction of groundwater if any.
 39. A final mine closure plan, along with details of Corpus Fund, shall be submitted to the Integrated Regional Office, MoEF&CC, GoI, Lucknow and U.P. Pollution Control Board 5 years in advance of final mine closure for approval.
 40. Project Proponent shall explore the possibility of using solar energy where ever possible.
 41. Commitment towards CER has to be followed strictly.
 42. Regular health checkup record of the mineworkers has to be maintained at the site in a proper register. It should be made available for inspection whenever asked.
 43. Project Proponent has to strictly follow the direction/guidelines issued by MoEF&CC, CPCB, and other Govt. Agencies from time to time.
 44. The blasting will be done only after getting permission from the Mining Department.

Annexure-2

General and Specific Conditions for Sand/Morum Mining Proposals

General Conditions:

1. This environmental clearance is subject to allotment of mining lease in favour of project proponent by District Administration/Mining Department.
2. Forest clearance shall be taken by the proponent as necessary under law.
3. Any change in mining area, khasra numbers, entailing capacity addition with change in process and or mining technology, modernization and scope of working shall again require prior Environmental Clearance as per the provisions of EIA Notification, 2006 (as amended).
4. Precise mining area will be jointly demarcated at site by project proponent and officials of Mining/Revenue department prior to starting of mining operations. Such site plan, duly verified by competent authority along-with copy of the Environmental Clearance letter will be displayed on a hoarding/board at the site. A copy of site plan will also be submitted to SEIAA within a period of 02 months.
5. Mining and loading shall be done only within day hours' time.
6. No mining shall be carried out in the safety zone of any bridge and/or embankment.
7. It shall be ensured that standards related to ambient air quality/effluent as prescribed by the Ministry of Environment & Forests are strictly complied with. Water sprinklers and other dust control majors should be applied to take-care of dust generated during mining operation. Sprinkling of water on haul roads to control dust will be ensured by the project proponent.
8. All necessary statutory clearances shall be obtained before start of mining operations. If this condition is violated, the clearance shall be automatically deemed to have been cancelled.
9. Parking of vehicles should not be made on public places.
10. No tree-felling will be done in the leased area, except only with the permission of Forest Department.
11. No wildlife habitat will be infringed.
12. It shall be ensured that excavation of minor mineral does not disturb or change the underlying soil characteristics of the river bed /basin, where mining is carried out.
13. It shall be ensured that mining operation of Sand/Moram will not in any way disturb the, velocity and flow pattern of the river water significantly.
14. It shall be ensured that there is no fauna dependant on the river bed or areas close to mining for its nesting. A report on the same, vetted by the competent authority shall be submitted to the RO, PCB and SEIAA within 02 months.
15. Primary survey of flora and fauna shall be carried out and data shall be submitted to the RO, PCB and SEIAA within six months.
16. Hydro-geological study shall be carried out by a reputed organization/institute within six months and establish that mining in the said area will not adversely affect the ground water regime. The report shall be submitted to the RO, PCB and SEIAA within six months. In case adverse impact is observed /anticipated, mining shall not be carried out.
17. Adequate protection against dust and other environmental pollution due to mining shall be made so that the habitations (if any) close by the lease area are not adversely affected. The status of implementation of measures taken shall be reported to the RO, UPPCB and SEIAA and this activity should be completed before the start of sand mining.
18. Need-based assessment for the nearby villages shall be conducted to study economic measures which can help in improving the quality of life of economically weaker section of society. Income generating projects/tools such as development of fodder farm, fruit bearing orchards, vocational training etc. can form a part of such program me. The project proponent shall provide separate budget for community development activities and income generating programmes.
19. Green cover development shall be carried out following CPCB guidelines including selection of plant species and in consultation with the local DFO/Horticulture Officer.
20. Separate stock piles shall be maintained for excavated top soil, if any, and the top soil should be utilized for green cover/tree plantation.
21. Dispensary facilities for first-aid shall be provided at site.
22. An Environmental Audit should be annually carried out during the operational phase and submitted to the SEIAA.

23. The District Mining Officer should quarterly monitor compliance of the stipulated conditions. The project proponent will extend full cooperation to the District Mining Officer by furnishing the requisite data/information/monitoring reports. In case of any violations of stipulated conditions the District Mining Officer will report to SEIAA.
24. The project proponent shall submit six monthly reports on the status of compliance of the stipulated environmental clearance conditions including results of monitored data (both in hard & soft copies) to the SEIAA, the District Officer and the respective Regional Office of the State Pollution Control Board by 1st June and 1st December every year.
25. A copy of the clearance letter shall be sent by the proponent to concerned Panchayat, Zila Parisad/ Municipal Corporation and Urban Local Body.
26. Transportation of materials shall be done by covering the trucks / tractors with tarpaulin or other suitable mechanism to avoid fugitive emissions and spillage of mineral/dust.
27. Waste water, from temporary habitation campus be properly collected & treated before discharging into water bodies the treated effluent should conform to the standards prescribed by MoEF/CPCB.
28. Measures shall be taken for control of noise level to the limits prescribed by C.P.C.B.
29. Special Measures shall be adopted to protect the nearby settlements from the impacts of mining activities. Maintenance of Village roads through which transportation of minor minerals is to be undertaken, shall be carried-out by the project proponent regularly at his own expenses.
30. Measure for prevention & control of soil erosion and management of silt shall be undertaken. Protection of dumps against erosion, if any, shall be carried-out with geo textile matting or other suitable material.
31. Under corporate social responsibility a sum of 5% of the total project cost or total income whichever is higher is to be earmarked for total lease period. Its budget is to be separately maintained. CER component shall be prepared based on need of local habitant. Income generating measures which can help in upliftment of poor section of society, consistent with the traditional skills of the people shall be identified. The programme can include activities such as development of fodder farm, fruit bearing orchards, free distribution of smokeless Chula etc.
32. Possibility for adopting nearest three villages shall be explored and details of civic amenities such as roads, drinking water etc proposed to be provided at the project proponent's expenses shall be submitted within 02 months from the date of issuance of Environment Clearance.
33. The funds earmarked for environmental protection measures should be kept in separate account and should not be diverted for other purpose. Year wise expenditure should be reported to the Integrated Regional Office, MoEF&CC, GoI, Lucknow, SEIAA, U.P and UPPCB.
34. Action plan with respect to suggestion/improvement and recommendations made and agreed during Public Hearing shall be submitted to the District mines Officer, concern Regional Officer of UPPCB and SEIAA within 02 months.
35. Environmental clearance is subject to obtaining clearance under the Wildlife (Protection) Act, 1972 from the competent authority, if applicable to this project.
36. The proponent shall observe every 15 day for nesting of any turtle in the area. Based on the observations so made, if turtle nesting is observed, necessary safeguard measures shall be taken in consultation with the State Wildlife Department. For the purpose, awareness shall be created amongst the workers about the nesting sites so that such sites, if any, are identified by the workers during operations of the mine for taking required safeguard measures. In this regards the safety notified zone should be left so that the habitat/nesting area is undisturbed.
37. The project proponent shall undertake adequate safeguard measures during extraction of river bed material and ensure that due to this activity the hydro geological regime of the surrounding area shall not be affected.
38. The project proponent shall obtain necessary prior permission of the competent Authorities for withdrawal of requisite quantity of water (surface water and groundwater), required for the project.
39. Appropriate mitigative measures shall be taken to prevent pollution of the river in consultation with the State Pollution Control Board. It shall be ensured that there is no leakage of oil and grease in the river from the vehicles used for transportation.
40. Vehicular emissions shall be kept under control and regularly monitored. The vehicles carrying the mineral shall not be overloaded.
41. Provision shall be made for the housing of construction labour within the site with all necessary infrastructure and facilities such as fuel for cooking, mobile toilets, mobile STP, safe drinking water, medical health care, crèche etc. (MoEF circular Dated : 22-09-2008 regarding stipulation of condition to improve the living conditions of construction labour at site).

42. Personnel working in dusty areas should wear protective respiratory devices and they should also be provided with adequate training and information on safety and health aspects. Occupational health surveillance program of the workers should be undertaken periodically to observe any contractions due to exposure to dust and take corrective measures, if needed.
43. A copy of the clearance letter shall be sent by the proponent to concerned Panchayat, Zila Parishad/ Municipal Corporation, Urban Local Body and the Local NGO, if any, from whom suggestions/ representations, if any, were received while processing the proposal. The clearance letter shall also be put on the website of the Company by the proponent.
44. The environmental statement for each financial year ending 31st March in Form-V as is mandated to be submitted by the project proponent to the concerned State Pollution Control Board as prescribed under the Environment (Protection) Rules, 1986, as amended subsequently, shall also be put on the website of the company along with the status of compliance of environmental clearance conditions and shall also be sent to the Integrated Regional Office, MoEF&CC, GoI, Lucknow by e-mail.
45. The green cover development/tree plantation is to be done in an area equivalent to 20% of the total leased area either on river bank or along road side (Avenue Plantation).
46. Debris from the river bed will be collected and stored at secured place and may be utilized for strengthen the embankment.
47. Safety measures to be taken for the safety of the people working at the mine lease area should be given, which would also include measure for treatment of bite of poisonous reptile/insect like snake.
48. Periodical and Annual medical checkup of workers as per Mines Act and they should be covered under ESI as per rule.

Specific Conditions:

1. The Environmental clearance will be co-terminus with the mining lease period/mining plan whichever is less.
2. At the time of operation, project proponent will comply with all the guidelines issued by Government of India/State Govt./District Administration related to Covid-19.
3. Environment management in according to environmental status and impact of the project.
4. During the school opening and closing time transportation of minerals will be restricted.
5. Selection of plants for green belt should be on the basis of pollution removal index. Project proponent should ensure survival of tree saplings. Mortality should be replaced from time to time.
6. No mining activity should be carried out in-stream channel as per SSMMG, 2016.
7. Pakkamotorable haul road to be maintained by the project proponent.
8. A separate Environmental Management Cell with suitable qualified personnel shall be set-up under the control of a Senior Executive, who will report directly to the Head of the Organization.
9. Permission from the competent authority regarding evacuation route should be taken.
10. One month monitoring report of the area for air quality, water quality, Noise level. Besides flora & fauna should be examined twice a week and be submitted within 45 days for a record.
11. Provision for cylinder to workers should be made for cooking.
12. The capacity of trucks/tractor for loading purpose will be in tonnes as per Transport Department applicable norms and standard fixed by the Government.
13. Approach road kaccha is to be made motarable and tree saplings to be planted on both sides of the road. Width of the haul road shall be more than 6 meter.
14. Indigenous plants should be planted according to CPCB guidelines and in consultation with local Divisional Forest Officer.
15. The project proponent shall in 2 years conduct detailed replenishment study duly authenticated by a QCI-NABET accredited consultant, and the District Mines Officer.
16. Provision for two toilets and hand pumps should be made at mining site.
17. Drinking water for workers would be provided by tankers.
18. Mining should be done by Bar scalping methods extraction (typically 0.3 -0.6 m or 1 - 2 ft) as per sustainable sand mining management guidelines 2016.
19. A buffer/safe zone shall be maintained from the habitation as per mining guidelines.
20. Corporate Environmental Responsibility (CER) plan shall be prepared by the project proponent and the details of the various heads of expenditure to be submitted as per the guidelines provided in the recent CER notification No. 22-65/2017-IA.III dated 01/05/2018.

21. Health/Insurance card, Medical claim, regular health check-up camps, facilities shall be provided to the regular/temporary/Contractual or any base workers. Copy of receipt shall be produced to the Directorate of Environment along with the compliance report.
22. Measure for conservation of water through rainwater harvesting and cleaning and maintenance of natural surface water bodies of the nearby areas may be considered as one of the activity in CER.
23. The excavated mining material should be carried and transported in such a way that no obstruction to the free flow of water takes place. Suitable measure should be taken and details to be provided to concern Department.
24. Submit annual replenishment report certified by an authorized agency. In case the replenishment is lower than the approved rate of production, then the mining activity / production levels shall be decreased / stopped accordingly till the replenishment is completed.
25. The project proponent shall ensure that if the project area falls within the eco-sensitive zone of National park/ Sanctuary prior permission of statutory committee of National board for wild life under the provision of Wildlife (Protection) Act, 1972 shall be obtained before commencement of work.
26. If in future this lease area becomes part of cluster of equal to or more than 05 ha. then additional conditions based on the EIA shall be imposed. The lease holder shall mandatorily follow cluster conditions otherwise it will amount to violation of E.C. conditions. If the certificate related to cluster provided by the competent authority is found false or incorrect then punitive actions as per law shall be initiated against the authority issuing the cluster certificate.
27. Project falling within 10 KM area of Wild Life Sanctuary is to obtain a clearance from National Board Wild Life (NBWL) even if the eco-sensitive zone is not earmarked.
28. To avoid ponding effect and adverse environmental conditions for sand mining in area, progressive mining should be done as per sustainable sand mining management guidelines 2016.
29. In case it has been found that the E.C. obtained by providing incorrect information, submitting that the distance between the two adjoining mines is greater than 500mt. and area is less than 05 ha, but factually the distance is less than 500 mt and the mine is located in cluster of area equal or more than 05 ha, the E.C issued will stand revoked.
30. The project proponent shall in 2 years conduct detailed replenishment study duly authenticated by a QCI-NABET accredited consultant, and the District Mines Officer which shall form the basis for midterm review of conditions of Environmental Clearance.
31. The mining work will be open-cast and manual/semi mechanized (subject to orders). Heavy machine such as excavator, scooper etc. should not be employed for mining purpose. No drilling/blasting should be involved at any stage.
32. It shall be ensured that there shall be no mining of any type within 03 m or 10% of the width which-ever is less, shall be left on both the banks of precise area to control and avoid erosion of river bank. The mining is confined to extraction of sand/moram from the river bank only.
33. The project proponent shall undertake adequate safeguard measures during extraction of river bank material and ensure that due to this activity the hydro-geological regime of the surrounding area shall not be affected.
34. The project proponent shall adhere to mining in conformity to plan submitted for the mine lease conditions and the Rules prescribed in this regard clearly showing the no work zone in the mine lease i.e. the distance from the bank of river to be left un-worked (Non mining area), distance from the bridges etc. It shall be ensured that no mining shall be carried out during the monsoon season.
35. The project proponent shall ensure that wherever deployment of labour attracts the Mines Act, the provision thereof shall be strictly followed.
36. The project proponent will provide personal protective equipment (PPE) as required, also provide adequate training and information on safety and health aspects. Periodical medical examination of the workers engaged in the project shall be carried out and records maintained. For the purpose, schedule of health examination of the workers should be drawn and followed accordingly.
37. The critical parameters such as PM10, PM2.5, SO2 and NOx in the ambient air within the impact zone shall be monitored periodically. Further, quality of discharged water if any shall also be monitored [(TDS, DO, pH, Fecal Coliform and Total Suspended Solids (TSS))].
38. Effective safeguard measures, such as regular water sprinkling shall be carried out in critical areas prone to air pollution and having high levels of particulate matter such as loading and unloading point and all transfer points. Extensive water sprinkling shall be carried out on haul roads.
39. It should be ensured that the Ambient Air Quality parameters conform to the norms prescribed by the Central Pollution Control Board in this regard.

40. The extended mining scheme will be submitted by the proponent before expiry of present mining plan.
41. Four ambient air quality-monitoring stations should be established in the core zone as well as in the buffer zone for monitoring PM10, PM2.5, SO2 and NOx. Location of the stations should be decided based on the meteorological data, topographical features and environmentally and ecologically sensitive targets and frequency of monitoring should be undertaken in consultation with the State Pollution Control Board.
42. Common road for transportation of mineral is to be maintained collectively. Total cost will be shared/worked out on the basis of lease area among users.
43. Proponent will provide adequate sanitary facility in the form of mobile toilets to the labours engaged for the project work.
44. Solid waste material viz., gutkha pouchs, plastic bags, glasses etc. to be generated during project activity will be separately storage in bins and managed as per Solid Waste Management rules.
45. Natural/customary paths used by villagers should not be obstructed at any time by the activities proposed under the project.
46. Digital processing of the entire lease area in the district using remote sensing technique should be done regularly once in three years for monitoring the change of river course by Directorate of Geology and Mining, Govt. of Uttar Pradesh. The record of such study to be maintained and report be submitted to Integrated Regional Office, MoEF&CC, GoI, Lucknow, SEIAA, U.P. and UPPCB.
47. The project authorities shall advertise at least in two local newspapers widely circulated, one of which shall be in the vernacular language of the locality concerned, within 7 days of the issue of the clearance letter informing that the project has been accorded environmental clearance and a copy of the clearance letter is available with the State Pollution Control Board and also at web site of the SEIAA at <http://www.seiaaup.in> and a copy of the same shall be forwarded to the Integrated Regional Office, MoEF&CC, GoI, Lucknow, CPCB, State PCB.
48. The MoEF&CC/SEIAA or any other competent authority may alter/modify the above conditions or stipulate any further condition in the interest of environment protection.
49. Concealing factual data or submission of false/fabricated data and failure to comply with any of the conditions mentioned above may result in withdrawal of this clearance and attract action under the provisions of Environment (Protection) Act, 1986.
50. Any appeal against this environmental clearance shall lie with the National Green Tribunal, if preferred, within a period of 30 days as prescribed under Section 11 of the National Environment Appellate Authority Act, 1997.
51. Waste water from potable use be collected and reused for sprinkling.
52. A width of not less than 50 meter or 10% width of river can be restricted for mining activities from river bank. A condition can be imposed that mining will be done from river activities from river bank.

Annexure-1

Standard Terms of Reference for the Mining Project prescribed by MoEF&CC, GoI

- 1) Year-wise production details since 1994 should be given, clearly stating the highest production achieved in any one year prior to 1994. It may also be categorically informed whether there had been any increase in production after the EIA Notification 1994 came into force, w.r.t. the highest production achieved prior to 1994.
- 2) A copy of the document in support of the fact that the proponent is the rightful lessee of the mine should be given.
- 3) All documents including approved mine plan, EIA and Public Hearing should be compatible with one another in terms of the mine lease area, production levels, waste generation and its management, mining technology etc. and should be in the name of the lessee.
- 4) All corner coordinates of the mine lease area, superimposed on a High Resolution Imagery/ toposheet, topographic sheet, geomorphology and geology of the area should be provided. Such an Imagery of the proposed area should clearly show the land use and other ecological features of the study area (core and buffer zone).
- 5) Information should be provided in Survey of India Toposheet in 1:50,000 scale indicating geological map of the area, geomorphology of land forms of the area, existing minerals and mining history of the area, important water bodies, streams and rivers and soil characteristics.
- 6) Details about the land proposed for mining activities should be given with information as to whether mining conforms to the land use policy of the State; land diversion for mining should have approval from State land use board or the concerned authority.
- 7) It should be clearly stated whether the proponent Company has a well laid down Environment Policy approved by its Board of Directors? If so, it may be spelt out in the EIA Report with description of the prescribed operating process/procedures to bring into focus any infringement/deviation/ violation of the environmental or forest norms/ conditions? The hierarchical system or administrative order of the Company to deal with the environmental issues and for ensuring compliance with the EC conditions may also be given. The system of reporting of non-compliances / violations of environmental norms to the Board of Directors of the Company and/or shareholders or stakeholders at large, may also be detailed in the EIA Report.
- 8) Issues relating to Mine Safety, including subsidence study in case of underground mining and slope study in case of open cast mining, blasting study etc. should be detailed. The proposed safeguard measures in each case should also be provided.
- 9) The study area will comprise of 10 km zone around the mine lease from lease periphery and the data contained in the EIA such as waste generation etc. should be for the life of the mine / lease period.
- 10) Land use of the study area delineating forest area, agricultural land, grazing land, wildlife sanctuary, national park, migratory routes of fauna, water bodies, human settlements and other ecological features should be indicated. Land use plan of the mine lease area should be prepared to encompass preoperational, operational and post operational phases and submitted. Impact, if any, of change of land use should be given.
- 11) Details of the land for any Over Burden Dumps outside the mine lease, such as extent of land area, distance from mine lease, its land use, R&R issues, if any, should be given.
- 12) A Certificate from the Competent Authority in the State Forest Department should be provided, confirming the involvement of forest land, if any, in the project area. In the event of any contrary claim by the Project Proponent regarding the status of forests, the site may be inspected by the State Forest Department along with the Regional Office of the Ministry to ascertain the status of forests, based on which, the Certificate in this regard as mentioned above be issued. In all such cases, it would be desirable for representative of the State Forest Department to assist the Expert Appraisal Committees.
- 13) Status of forestry clearance for the broken up area and virgin forestland involved in the Project including deposition of net present value (NPV) and compensatory afforestation (CA) should be indicated. A copy of the forestry clearance should also be furnished.

- 14) Implementation status of recognition of forest rights under the Scheduled Tribes and other Traditional Forest Dwellers (Recognition of Forest Rights) Act, 2006 should be indicated.
- 15) The vegetation in the RF / PF areas in the study area, with necessary details, should be given.
- 16) A study shall be got done to ascertain the impact of the Mining Project on wildlife of the study area and details furnished. Impact of the project on the wildlife in the surrounding and any other protected area and accordingly, detailed mitigative measures required, should be worked out with cost implications and submitted.
- 17) Location of National Parks, Sanctuaries, Biosphere Reserves, Wildlife Corridors, Ramsar site Tiger/ Elephant Reserves/(existing as well as proposed), if any, within 10 km of the mine lease should be clearly indicated, supported by a location map duly authenticated by Chief Wildlife Warden. Necessary clearance, as may be applicable to such projects due to proximity of the ecologically sensitive areas as mentioned above, should be obtained from the Standing Committee of National Board of Wildlife and copy furnished.
- 18) A detailed biological study of the study area [core zone and buffer zone (10 km radius of the periphery of the mine lease)] shall be carried out. Details of flora and fauna, endangered, endemic and RET Species duly authenticated, separately for core and buffer zone should be furnished based on such primary field survey, clearly indicating the Schedule of the fauna present. In case of any scheduled- I fauna found in the study area, the necessary plan alongwith budgetary provisions for their conservation should be prepared in consultation with State Forest and Wildlife Department and details furnished. Necessary allocation of funds for implementing the same should be made as part of the project cost.
- 19) Proximity to Areas declared as 'Critically Polluted' or the Project areas likely to come under the 'Aravali Range', (attracting court restrictions for mining operations), should also be indicated and where so required, clearance certifications from the prescribed Authorities, such as the SPCB or State Mining Department should be secured and furnished to the effect that the proposed mining activities could be considered.
- 20) R&R Plan/compensation details for the Project Affected People (PAP) should be furnished. While preparing the R&R Plan, the relevant State/National Rehabilitation & Resettlement Policy should be kept in view. In respect of SCs /STs and other weaker sections of the society in the study area, a need based sample survey, family-wise, should be undertaken to assess their requirements, and action programmes prepared and submitted accordingly, integrating the sectoral programmes of line departments of the State Government. It may be clearly brought out whether the village(s) located in the mine lease area will be shifted or not. The issues relating to shifting of village(s) including their R&R and socio-economic aspects should be discussed in the Report.
- 21) One season (non-monsoon) [i.e. March-May (Summer Season); October-December (post monsoon season); December-February (winter season)] primary baseline data on ambient air quality as per CPCB Notification of 2009, water quality, noise level, soil and flora and fauna shall be collected and the AAQ and other data so compiled presented date-wise in the EIA and EMP Report. Site-specific meteorological data should also be collected. The location of the monitoring stations should be such as to represent whole of the study area and justified keeping in view the pre-dominant downwind direction and location of sensitive receptors. There should be at least one monitoring station within 500 m of the mine lease in the pre-dominant downwind direction. The mineralogical composition of PM₁₀, particularly for free silica, should be given.
- 22) Air quality modeling should be carried out for prediction of impact of the project on the air quality of the area. It should also take into account the impact of movement of vehicles for transportation of mineral. The details of the model used and input parameters used for modeling should be provided. The air quality contours may be shown on a location map clearly indicating the location of the site, location of sensitive receptors, if any, and the habitation. The wind roses showing pre-dominant wind direction may also be indicated on the map.
- 23) The water requirement for the Project, its availability and source should be furnished. A detailed water balance should also be provided. Fresh water requirement for the Project should be indicated.
- 24) Necessary clearance from the Competent Authority for drawl of requisite quantity of water for the Project should be provided.
- 25) Description of water conservation measures proposed to be adopted in the Project should be given.
- 26) Details of rainwater harvesting proposed in the Project, if any, should be provided.
- 27) Impact of the Project on the water quality, both surface and groundwater, should be assessed and necessary safeguard measures, if any required, should be provided.

- 28) Based on actual monitored data, it may clearly be shown whether working will intersect groundwater.
- 29) Necessary data and documentation in this regard may be provided. In case the working will intersect groundwater table, a detailed Hydro Geological Study should be undertaken and Report furnished. The Report inter-alia, shall include details of the aquifers present and impact of mining activities on these aquifers. Necessary permission from Central Ground Water Authority for working below ground water and for pumping of ground water should also be obtained and copy furnished.
- 30) Details of any stream, seasonal or otherwise, passing through the lease area and modification / diversion proposed, if any, and the impact of the same on the hydrology should be brought out.
- 31) Information on site elevation, working depth, groundwater table etc. Should be provided both in AMSL and bgl. A schematic diagram may also be provided for the same.
- 32) A time bound Progressive Greenbelt Development Plan shall be prepared in a tabular form (indicating the linear and quantitative coverage, plant species and time frame) and submitted, keeping in mind, the same will have to be executed up front on commencement of the Project. Phase-wise plan of plantation and compensatory afforestation should be charted clearly indicating the area to be covered under plantation and the species to be planted. The details of plantation already done should be given. The plant species selected for green belt should have greater ecological value and should be of good utility value to the local population with emphasis on local and native species and the species which are tolerant to pollution.
- 33) Impact on local transport infrastructure due to the Project should be indicated. Projected increase in truck traffic as a result of the Project in the present road network (including those outside the Project area) should be worked out, indicating whether it is capable of handling the incremental load. Arrangement for improving the infrastructure, if contemplated (including action to be taken by other agencies such as State Government) should be covered. Project Proponent shall conduct Impact of Transportation study as per Indian Road Congress Guidelines.
- 34) Details of the onsite shelter and facilities to be provided to the mine workers should be included in the EIA Report.
- 35) Conceptual post mining land use and Reclamation and Restoration of mined out areas (with plans and with adequate number of sections) should be given in the EIA report.
- 36) Occupational Health impacts of the Project should be anticipated and the proposed preventive measures spelt out in detail. Details of pre-placement medical examination and periodical medical examination schedules should be incorporated in the EMP. The project specific occupational health mitigation measures with required facilities proposed in the mining area may be detailed.
- 37) Public health implications of the Project and related activities for the population in the impact zone should be systematically evaluated and the proposed remedial measures should be detailed along with budgetary allocations.
- 38) Measures of socio economic significance and influence to the local community proposed to be provided by the Project Proponent should be indicated. As far as possible, quantitative dimensions may be given with time frames for implementation.
- 39) Detailed environmental management plan (EMP) to mitigate the environmental impacts which, should inter-alia include the impacts of change of land use, loss of agricultural and grazing land, if any, occupational health impacts besides other impacts specific to the proposed Project.
- 40) Public Hearing points raised and commitment of the Project Proponent on the same along with time bound Action Plan with budgetary provisions to implement the same should be provided and also incorporated in the final EIA/EMP Report of the Project.
- 41) Details of litigation pending against the project, if any, with direction /order passed by any Court of Law against the Project should be given.
- 42) The cost of the Project (capital cost and recurring cost) as well as the cost towards implementation of EMP should be clearly spelt out.
- 43) A Disaster management Plan shall be prepared and included in the EIA/EMP Report.
- 44) Benefits of the Project if the Project is implemented should be spelt out. The benefits of the Project shall clearly indicate environmental, social, economic, employment potential, etc.
- 45) Besides the above, the below mentioned general points are also to be followed:-
 - a) Executive Summary of the EIA/EMP Report
 - b) All documents to be properly referenced with index and continuous page numbering.

- c) Where data are presented in the Report especially in Tables, the period in which the data were collected and the sources should be indicated.
- d) Project Proponent shall enclose all the analysis/testing reports of water, air, soil, noise etc. using the MoEF&CC/NABL accredited laboratories. All the original analysis/testing reports should be available during appraisal of the Project.
- e) Where the documents provided are in a language other than English, an English translation should be provided.
- f) The Questionnaire for environmental appraisal of mining projects as devised earlier by the Ministry shall also be filled and submitted.
- g) While preparing the EIA report, the instructions for the Proponents and instructions for the Consultants issued by MoEF&CC vide O.M. No. J-11013/41/2006-IA.II(I) dated 4th August, 2009, which are available on the website of this Ministry, should be followed.
- h) Changes, if any made in the basic scope and project parameters (as submitted in Form-I and the PFR for securing the TOR) should be brought to the attention of MoEF&CC with reasons for such changes and permission should be sought, as the TOR may also have to be altered. Post Public Hearing changes in structure and content of the draft EIA/EMP (other than modifications arising out of the P.H. process) will entail conducting the PH again with the revised documentation.
- i) As per the circular no. J-11011/618/2010-IA.II(I) dated 30.5.2012, certified report of the status of compliance of the conditions stipulated in the environment clearance for the existing operations of the project, should be obtained from the Regional Office of Ministry of Environment, Forest and Climate Change, as may be applicable.
- j) The EIA report should also include: (i) surface plan of the area indicating contours of main topographic features, drainage and mining area, (ii) geological maps and sections and (iii) sections of the mine pit and external dumps, if any, clearly showing the land features of the adjoining area.

Annexure-4

General and Specific Conditions for Soil/Earth Mining Projects:-

General condition:

1. This environmental clearance does not create or verify any claim of applicant on the proposed site/activity.
2. Any mining activity shall be undertaken only after valid permission from Mining Department/District Administration and written agreement with land owner from where earth excavation is proposed.
3. No change in mining technology and scope of working shall be made without approval of Authority.
4. Personnel working in dusty areas shall be provided with protective respiratory devices and they shall also be imparted adequate training and information on safety and health aspects.
5. The Authority reserves the right to revoke the clearance if conditions stipulated are not implemented. The Authority will also be entitled to impose additional environmental conditions or modify the existing ones, if necessary.
6. In case of any deviation or alteration in the project proposed from those submitted to this Authority for clearance, a fresh reference should be made to the Authority to assess the adequacy of the condition(s) imposed and to add additional environmental protection Measures required, if any.
7. Concealing factual data or submission of false/fabricated data and failure to comply with any of the conditions mentioned above may result in withdrawal of this clearance and attract action under the provisions of Environment (Protection) Act, 1986.

Specific Conditions:

1. The Environmental clearance will be co-terminus with the agreement/mining plan whichever is less.
2. Environment management should be in accordance with the present environment status of the project.
3. Approach kaccha road should be made motorable and maintained periodically.
4. Transportation of soil should be undertaken in covered containers.
5. Rehabilitation plan with planting of trees to be submitted along with the closure plan.
6. Land to be leveled and handed over to the owners after completion of excavation work.
7. A valid NOC from State Pollution Control Board shall be obtained for the Brick kiln prior to operation as per law and all guidelines must be followed, if applicable.
8. The mining operations shall be strictly limited to the proposed mining sites and proposed purpose.
9. Top soil should be adequately preserved and should be used for landscaping.
10. Excavated soil should be properly stored in a manner not to increase surrounding air pollution level.
11. Water sprinkling should be exercised during excavation and storage of soil for suppression of fugitive dust.
12. Excavated area should be properly reclaimed and ensured that no open bore hole is left.
13. Safety measures for the people working at the site shall be duly taken care of as per law.
14. The excavation work shall be done in day time only.
15. The project boundary shall be properly covered to restrict dust dispersion.
16. Precautionary measures during soil excavation for conservation and protection of rare and endangered flora and fauna found in the study area.
17. Noise level shall be maintained as per standards for both day and night.
18. The route map for soil transportation from excavation plots to work site should be firmed up and necessary permissions shall be sought from District Administration.
19. Vehicles hired for the transportation should be in good condition and should have Pollution Check Certificate and should conform to applicable air and noise emission standards.

20. Personnel exposure monitoring for respirable mineral dust shall be carried out for the workers and records maintained including health records of the workers. Awareness program for workers on impact of mining on their health and precautionary measures like use of personal protective equipments etc. shall be carried out periodically. First aid facilities and adequate sanitary facility in the form of temporary toilets/septic tanks.
21. Solid waste material vizguthka rappers, plastic bags, glasses etc. to be generated during project activity will be separately stored in bins and managed as per Solid Waste Management Rules.
22. Project proponent should maintain daily register for information of (a) collection of soil/clay, (b) manpower & (c) transportation purpose.
23. Soil mining shall strictly be undertaken as per rules and regulations/permissions obtained from District Administration/Mining Department
24. Corporate Environmental Responsibility (CER) shall be prepared by the project proponent and the details of the various heads of expenditure to be submitted as per the guidelines provided in the recent CER notification No. 22-65/2017-IA.III dated 01/05/2018. A copy of resolution as above shall be submitted to the authority along with list of beneficiaries with their mobile nos./address.
25. The borrowing/excavation activity shall be restricted to a maximum depth of 2 m. below general ground level at the site.
26. The borrowing/excavation activity shall be restricted to 2 m. above the ground water table at the site.
27. The borrowing/excavation activity shall not alter the natural drainage pattern of the area.
28. The borrowed/excavated pit shall be restored by the project proponent for useful purpose(s).
29. Appropriate fencing all around the borrowed/excavated pit shall be made to prevent any mishap.
30. Measures shall be taken to prevent dust emission by covering of borrowed/excavated earth during transportation.
31. Safeguards shall be adopted against health risks on account of breeding of vectors in the water bodies created due to borrowing/excavation of earth.
32. Workers/labourers shall be provided with facilities for drinking water and sanitation.
33. A berm shall be left from the boundary of adjoining field having a width equal to at least half the depth of proposed excavation.
34. A minimum distance of 15 m from any civil structure shall be kept from the periphery of any excavation area.